

**PREVENTIV: : " RIKONSTRUKSION I PEDIATRISE, SARANDE " VAZHDIM**

**Per: Drejtoria e Sherbimit Spitalor Sarande**

Nr.	Nr. Analize	EMERTIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
<b>1- PUNIME TE NDRYSHME PRISHJE</b>						
1	An	Vendosje adezivi (per vendosje murale me material plastik dhe ngjites)	m2	30	3,200	96,000
2	An.	Porta druri me veshje MDF dhe mbushje material termik	cope	25	37,000	925,000
3	An	Porte duralumini me dyfish xham dhe me sistem elektronik per hapje	m2	6.4	42,000	268,800
<b>SHUMA 1</b>						<b>1,289,800</b>
<b>2 - PUNIME SUVATIMI E VESHJE</b>						
1	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25, ne pjeset e mureve ku jane kryer riparime	m2	30.0	674	20,220
1	An.	Prishje pllaka koridori dhe dhoma me pastrim	m2	314	800	251,434
2	2.267/b	Shtrese me pllaka grez importi	m2	440	2,446	1,076,240
3	2.297/b	Tavan i varur me pllaka gipsi 60*60cm	m2	415	2,132	884,780
<b>SHUMA 2</b>						<b>2,232,674</b>
<b>3-PUNIME SHTRESASH</b>						
1	2.330	Patinim tavani allçi (stuko)	m2	453	387	175,311
2	2.404/1	Boje hidroplastike importi cilesi e l-re	m2	1332	471	627,372
<b>SHUMA 3</b>						<b>802,683</b>
<b>4- PUNIME HIDROSANITARE PER DHOMAT E MJEKUT</b>						
<b>4/a Furnizim me uje</b>						
1	2.491/b	F.V Tuba e rakorderi ujesjellesi PPR d=20~25mm, PN 16	ml	102	300	30,600
2	2.491/c	F.V Tuba e rakorderi ujesjellesi PPR d=20~32mm, PN 16	ml	30	330	9,900
3	2.538	PJESE SPECIALE REKORDERI	KG	50	200	10,000
4	An - 9	F.V Saraçineske PPR 1/2"	cope	2	800	1,600
5	An - 10	F.V Saraçineske fundore	cope	16	600	9,600
<b>SHUMA 4/a</b>						<b>61,700</b>
<b>4/b-Shkarkimet e ujrave te ndotura</b>						
1	An.	TUB SHKARKIMI PLASTIK d=50 mm	ml	40	600	24,000
2	2.520	TUB SHKARKIMI PŁASTIK d=110 mm	ml	30	1,200	36,000
3	2.538	PJESE SPECIALE RAKORDERIE	kg	50	200	10,000
<b>SHUMA 4/b</b>						<b>70,000</b>
<b>4/C - PAJISJET HIDRISANITARE</b>						

1	2.495	F.V lavaman porcelani importi me mishelator	cope	3	10,613	31,840
2	An.	Grup Lamani	cope	3	5,000	15,000
	2.505	F.V pisuar importi porcelani	cope	1	8,451	8,451
						<b>55,291</b>
						<b>186,991</b>
		<b>5. PUNIME ELEKTRIKE PAISJE</b>				
4	An.	Ndricues led 60*60cm	cope	40	3,500	140,000
	An.	Ndricues led d=150mm,	cope	12	1,500	18,000
5	An.	Sistemi me kamera per dhomat e pacienteve (per 8 dhoma)	leke	1	200,000	200,000
6	An.	Celsa e priza (bitichino) te cdo lloji, OSE EKUIVALENT	cope	80	600	48,000
						<b>406,000</b>
						<b>4,918,148</b>
						<b>983,630</b>
						<b>5,901,778</b>

Preventivuesi : Ing. Ark. Edmond Rumani  
Lic. Nr. A.1279/1,

