

Emërtimi I Objektivit: - Rikostruksion I rrjetit TU me kabull me vetmbajtje ABC Njesia Elbasan 1

Nr	KABINA	PREVENTIVI	TU	Makineri-Pajisje	Puntori	TM	TOTALI
1	F4 N/St.Belsh	Kabina " Merhoj "					
2	F4 N/St.Belsh	Kabina " Pajalli "					
3	F4 N/St.Belsh	Kabina "Pepaj "					
4	F4 N/St.Belsh	Kabina " Pokgjen 1 "					
5	F4 N/St.Belsh	Kabina " Shkoze "					
6	F4 N/St.Belsh	Kabina " Soshke"					
7	F4 N/St.Belsh	Kabina " Stanaj "					
8	F4 N/St.Belsh	Kabina " Shegas "					
9	F4 N/St.Belsh	Kabina " Nafta "					
10	F4 N/St.Belsh	Kabina "Rrase 1 "					
11	F4 N/St.Belsh	Kabina " Rrase e Siperme "					
12	F4 N/St.Belsh	Kabina " Rrase e Poshtme "					
13	F4 N/St.Belsh	Kabina " Rrase e Poshtme 2"					
14	F1 N/St.Kajan	Kabina " Grekan 1"					
15	F1 N/St.Kajan	Kabina " Grekan 2"					
16	F1 N/St.Kajan	Kabina " Grekan 3"					
17	F1 N/St.Kajan	Kabina " Grekan 4"					
18	F1 N/St.Kajan	Kabina " Grekan 5"					
19	F3 N/St.Kajan	Kabina " Gjolene 1 "					
20	F3 N/St.Kajan	Kabina " Gjolene 2 "					
21	F3 N/St.Kajan	Kabina " Kajan 1 "					
22	F3 N/St.Kajan	Kabina " Kajan 2 "					
23	F3 N/St.Kajan	Kabina " Kosove 1"					
24	F3 N/St.Kajan	Kabina " Kosove 2 "					
25	F6 N/St.Nr:1	Kabina "Mamel 1 "					
26	F6 N/St.Nr:1	Kabina "Mamel 2 "					
27	F6 N/St.Nr:1	Kabina "Mamel 3 "					
28	F6 N/St.Nr:1	Kabina "Mamel 5 "					
29	F13 N/St.Nr:1	Kabina "Petresh 1 "					
30	F13 N/St.Nr:1	Kabina "Petresh 2 "					
31	F13 N/St.Nr:1	Kabina "Shemhill "					
32	F2 N/St.Fiber	Kabina "Polis 1"					
33	F2 N/St.Fiber	Kabina "Polis 2"					
34	F13 N/St.Cerrik	Kabina "Paper Sallak 2"					
35	F.Shales N/St.Cerrik	Kabina " Blate "					
36	F.Shales N/St.Cerrik	Kabina " Sopi Gelqeres"					
37	F.Shales N/St.Cerrik	Kabina " Xibrake Qender 1 "					
38	F.Shales N/St.Cerrik	Kabina "Xibrake 2 "					

39	F.Shales N/St.Cerrik	Kabina " Gjyrale 1 "					
40	F.Shales N/St.Cerrik	Kabina " Gjyrale 2 "					
		SHUMA					
		5%					
		SHUMA ME 5%					
		20%					
		SHUMA ME TVSH					

PREVENTIV KABINA 1

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Merhoj, me transformator Sn = 100 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	33.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,960.00		
3	MK - 10/22	Demontim traverse te vogla	cope	33.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	3.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	35.00		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	3.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	31.82		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	1.59		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	11.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	7.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	201.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	85.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	346.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	976.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	37.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	18.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	12.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	20.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	46.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	52.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	36.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	630.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	42.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	84.00		

4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	42.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	23.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	4.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	7.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	55.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	17.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	14.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	7.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	7.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	7.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	7.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	38.85		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	18.90		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	12.05		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	35.00		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.23		
shuma			leke			

PREVENTIV KABINA 2

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Pajalli, me transformator Sn = 250 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	27.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,240.00		
3	MK - 10/22	Demontim traverse te vogla	cope	27.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	4.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	36.29		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	4.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	32.98		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	1.65		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	11.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	7.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	149.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	153.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	373.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	536.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	30.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	14.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	8.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	30.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	26.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	36.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	20.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	675.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	45.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	90.00		

4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	45.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	21.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	4.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.92		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	3.92		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	8.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	50.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	20.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	16.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	8.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	8.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	8.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	8.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	33.60		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	18.90		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	12.05		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	36.29		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.00		
<i>shuma</i>			<i>leke</i>			

PREVENTIV KABINA 3

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Pajalli, me transformator Sn = 180 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	28.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,360.00		
3	MK - 10/22	Demontim traverse te vogla	cope	28.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	4.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	45.32		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	4.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	41.09		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.11		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	18.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	7.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	121.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	193.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	167.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	792.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	28.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	16.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	18.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	10.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	40.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	40.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	28.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	705.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	60.00		
2	MK - 35/70	FV. Tirantues abONENTI 4 x(16-95)mm ²	cope	49.00		

3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	94.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	8.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	49.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	23.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	4.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	4.48		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	4.48		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	8.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	40.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	20.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	16.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	8.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	8.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	8.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	8.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	35.70		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	26.25		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	16.60		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	45.32		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.13		
shuma			leke			

PREVENTIV KABINA 4

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Pokgjen 1, me transformator Sn = 180 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	28.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,360.00		
3	MK - 10/22	Demontim traverse te vogla	cope	28.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	6.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	50.00		
2	MK - 1/1	Ngjitje shtyll betoni me vinc per vendosje ne grope	cope	6.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	45.46		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.27		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	14.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	10.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetblokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	352.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	591.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	674.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	41.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	22.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	18.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	50.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	36.00		
10	MK-35/70	F.V. Konektor izolues linje (16-95/16-95)	cope	44.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	28.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	450.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	60.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	32.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	60.00		

5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	8.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	32.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	17.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	5.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	9.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	55.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	22.50		
4	MK-31/61	F.V.Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	18.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	9.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	9.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	9.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllle	9.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1 ton, teleskopik per h > 7 m (1,05 ore/shtyllle)	ore	43.05		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	25.20		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	16.10		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	50.00		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.14		
shuma			leke			

PREVENTIV KABINA 5

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Shkoze, me transformator Sn =250 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	40.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,800.00		
3	MK - 10/22	Demontim traverse te vogla	cope	40.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	3.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	63.23		
2	MK - 1/1	Ngjitje shtyll betoni me vinc per vendosje ne grope	cope	3.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	57.67		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.78		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	2.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	16.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	16.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablllo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	215.00		
1	MK-43/102.C	FV. Kablllo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	93.00		
2	MK-43/102.C	FV. Kablllo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	241.00		
3	MK-43/102.C	FV. Kablllo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	325.00		
4	MK-43/101.C	FV. Kablllo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	950.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	37.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	33.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	18.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	28.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	48.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	68.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	44.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	795.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	120.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	57.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	106.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	16.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	57.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	27.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	9.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.92		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.92		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	10.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	65.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	25.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	20.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	10.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	10.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	10.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	10.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	50.40		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	33.60		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	21.80		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	63.23		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.52		
shuma			leke			

PREVENTIV KABINA 6

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Soshke, me transformator Sn =250 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	93.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	11,160.0		
3	MK - 10/22	Demontim traverse te vogla	cope	93.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	12.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	119.03		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	12.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	108.13		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	5.45		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	1.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	39.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	22.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	30.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	485.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	171.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	632.00		
3	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	1,145.00		
4	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,894.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	97.00		
6	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	45.00		
7	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	32.00		
8	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	86.00		
9	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	92.00		
10	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	120.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	68.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	1,005.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	30.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	68.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	134.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	4.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	68.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	34.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	7.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	20.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	120.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	50.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	40.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	20.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	20.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	20.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	20.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	111.30		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	64.05		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	40.85		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	119.03		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	3.33		
shuma			leke			

PREVENTIV KABINA 7

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Stanaj, me transformator Sn =100 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	38.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,560.0		
3	MK - 10/22	Demontim traverse te vogla	cope	38.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	6.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	48.87		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	6.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	44.39		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.24		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	1.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	15.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	9.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	166.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	141.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	326.00		
3	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	511.00		
4	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	923.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	53.00		
6	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	22.00		
7	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	16.00		
8	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	42.00		
9	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	48.00		
10	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	76.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	56.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	720.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonenti	ml	30.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	49.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	96.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	4.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	49.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	29.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	7.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.80		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	2.80		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	10.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	75.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	25.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	20.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	10.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	10.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	10.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	10.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	56.70		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	25.20		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	16.15		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	48.87		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.64		
shuma			leke			

PREVENTIV KABINA 8

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Shegas, me transformator Sn =250 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	45.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	5,400.0		
3	MK - 10/22	Demontim traverse te vogla	cope	45.00		
7	MK - 16	Drejtim shtyll betoni	cope	1.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	99.35		
3	2-262/4	Shtrese betoni C 16/20	m ³	90.12		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	4.61		
5	Mk-8	F.V Shtylla Druri te impenjuara 8ml, 2.4kN ml (me krahe)	cope	1.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	47.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	16.00		
B3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	30.00		
3	4-141/a7.0	FV.Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	211.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	443.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	215.00		
3	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	1,003.00		
4	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,907.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	88.00		
6	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	29.00		
7	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	32.00		
8	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	62.00		
9	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	96.00		
10	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	108.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	64.00		
B5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	1,245.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	30.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	84.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	166.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	4.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	84.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	38.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	11.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	3.92		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.92		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	20.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	140.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	50.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	40.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	20.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	20.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	20.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	20.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	100.80		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	66.15		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	41.85		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	99.35		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.92		
<i>shuma</i>			<i>leke</i>			

PREVENTIV KABINA 9

**Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Nafta, me transformator Sn =250 kVA , Fideri 4 ,
N/St Belsh**

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	27.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,240.0		
3	MK - 10/22	Demontim traverse te vogla	cope	27.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	75.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	68.19		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	3.41		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	30.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	15.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	198.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	188.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	243.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	380.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	979.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	42.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	30.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	20.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	32.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	54.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	88.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	56.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	1,005.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	90.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	70.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	134.00		

5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	12.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	70.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	30.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	11.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	11.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	60.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	27.50		
4	MK-31/61	F.V.Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	22.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	11.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	11.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	11.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllle	11.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllle)	ore	56.70		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	47.25		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	30.00		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	75.00		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.70		
shuma			leke			

PREVENTIV KABINA 10

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Rrase 1, me transformator Sn =250 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	32.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,840.0		
3	MK - 10/22	Demontim traverse te vogla	cope	32.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	1.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	40.00		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	1.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	36.37		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	1.82		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	15.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	8.00		
B3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	30.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	50.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	245.00		
3	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	527.00		
4	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	893.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	50.00		
6	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	18.00		
7	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	4.00		
8	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	42.00		
9	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	48.00		
10	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	68.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	40.00		
B5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	735.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	150.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	54.00		

3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	98.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	20.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	54.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	27.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	5.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek.` 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	10.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	65.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	25.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	20.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	10.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	10.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	10.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	10.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	50.40		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	24.15		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	15.35		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	40.00		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.28		
shuma			leke			

PREVENTIV KABINA 11

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Rrase e Siperme, me transformator Sn =320 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtylle	shtyll	40.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,800.0		
3	MK - 10/22	Demontim traverse te vogla	cope	40.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	3.00		
7	MK - 16	Drejtim shtylle betoni	cope	3.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	70.00		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	3.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	63.64		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	3.18		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	1.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	25.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	14.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	30.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	287.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	305.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	467.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	484.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,063.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	72.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	30.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	36.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	52.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	62.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	96.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	56.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	1,125.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	150.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	80.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	150.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	20.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	80.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	40.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	7.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.92		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.92		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	13.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	85.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	32.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	26.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	13.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	13.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	13.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	13.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	79.80		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	40.95		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	26.15		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	70.00		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.27		
shuma			leke			

PREVENTIV KABINA 12

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Rrase e Poshtme, me transformator Sn =400 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	22.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	2,640.0		
3	MK - 10/22	Demontim traverse te vogla	cope	22.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	3.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	57.42		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	3.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	52.23		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.59		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	19.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	12.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	145.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	265.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	243.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	437.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	394.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	29.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	22.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	22.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	34.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	20.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	52.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	28.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	1,050.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	120.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	74.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	140.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	16.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	74.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	23.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	12.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	8.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	40.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	20.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	16.00		
5	MK - 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	8.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	8.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	8.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	8.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	40.95		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	32.55		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	20.75		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	57.42		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.44		
<i>shuma</i>			<i>leke</i>			

PREVENTIV KABINA 13

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Rrase e Poshtme 2 , me transformator Sn =100 kVA , Fideri 4 , N/St Belsh

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	15.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	1,800.0		
3	MK - 10/22	Demontim traverse te vogla	cope	15.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	26.45		
3	2-262/4	Shtrese betoni C 16/20	m ³	23.98		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	1.24		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	13.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	4.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	234.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	483.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	16.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	7.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	12.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	22.00		
10	MK-35/70	F.V. Konektor izolues linje (16-95/16-95)	cope	24.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	16.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	270.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	30.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	19.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	36.00		
5	MK - 35/70	FV. Konektor abonenti 35-70/16-25mm ²	cope	4.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	19.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	10.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	3.00		

B/6 - PUNIME CIVILE					
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.80	
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	2.80	
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ					
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	5.00	
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	25.00	
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	12.50	
4	MK-31/61	F.V.Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	10.00	
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	5.00	
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	5.00	
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	5.00	
B/6 - KOLAUDIME					
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00	
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	5.00	
B/7- TRANSPORT					
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	18.90	
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	17.85	
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	11.25	
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	26.45	
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	0.48	
shuma			leke		

PREVENTIV MAKINERI PAJISJE KABINA E RE "Rrase e Poshte 2"

Emërtimi i objektit: MAKINERI PAJISJE per Kabinen Shtyllore Rrase e Poshtme 2 me transformator 100 kVA

Nr	Analize	Emertimi i materialit	Njesia	Sasia	Cmimi	Vlera
1	20001156	Ndares 3 P TM 12.5Kv200A 16 KA i jashtem	cope	1		
2	20001681	Siguresa TM 6/10 kV	komplet	1		
3	20001910	Shkarkues Vintil TM 6-10 KV	cope	3		
4	20000865	Trasformator 10/0.4 kV 100 KVA ONAN	cope	1		
5	20002592	Panel TU 1x100A + 2 X 63A Jashtem	cope	1		
		Shuma	leke			

PREVENTIV NR .1/2

B- PUNIME TEKNOLOGJIKE DHE MONTIMI KABINE RRASE E POSHTME 2

Nr	Analize	Emertimi i punimeve	Njesia	Sasia	Cmimi	Vlera
SHTYLLA						
1	MK-1	F.V. Shtylla B/A cent. 10/15 m/kN,350/350 d1/d2, me makineri	cope	1		
2	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	1		
3	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	7.54		
4	2-262/4	Shtrese betoni C 16/20	m ³	7.16		
5	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	0.193		
6	1.131/p	Tub Betoni Φ = 400 mm	ml	4		
AKSESORE SHTYLLE						
7	4.-3+AN	FV Konstruks thjeshta/metal (bazament trafo+ ndaresi,+shkarkuesi + Panel TU te zinkuara)	ton	0.156		
8	1.101/p+ An	Pergatitje traversa metalike TU/TM, per linja 04 ~ 10 KV	ton	0.02897		
9	3.569	Punime izolimi elektrik ne linja, T/M 6 - 10 kv, me izolator mbeshtetes, 6-10kv 3 cope	shtylle	2		
10	MK- 32/62.1	Berje lozanke ne shtylle ne shtyllat me dopio izolator per faze	shtylle	1		
11	MK-70	FV.Morseta me kanale paralele AL-AL 16-120 /16-120	cope	6		
URA TM 10 KV DHE AKSESORET E SAJ						
12	MK/45+49	FV. Percjelles ACSR - 50 mm ² per lidhje paisjesh (urat)	ml	30		
13	L6-106	F.V Kapikorde SY AL 50 x M10	cope	18		
URAT TU 0,6/1 KV DHE AKSESORET E TUJ						
14	L6-73	FV.Kabell Al - Kabell AL 4x95 mm ² izo.XLPE 0.6/1 kV	ml	10		
15	L6-107	FV..Kapikorde SY AL/Cu 95mm ² M12	cope	5		
16	MK - 112	FV.Koke e thate kablli(Gushore izoluar me 4 gishta S = [(4X25) - (4X95)]mm ²	set	2		
17	Analize	Fasheta Plastike per fiksime kablli ne shtylle	cope	5		
Montim makineri Pajisje						
18	L6- 161/a	Montim transformator shperndares deri ne 50 kVA, 20/10/6/0.4 kV	cope	1		
19	L6 - 120	Montim ndares i jashtem TM 10 kV 200 - 400 A	cope	1		
20	L6 - 36	Montim sig. te jashteme TM 10 kV (bazament + fisheke 5 A)	cope	3		
21	L6-43	Montim Panel TU i jashtem +Matja	cope	1		
22	L6 - 178/3	Montim shkarkues jashtem tip ventil TM 10 kV, 10kA	cope	3		
23	3..614	FV Tabela Paralajmeruese (2 cope)	cope	2		
24	Analize	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	3		
TOKEZIMI						
25	L6-197	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	10		
26	L6-193	F V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	4		
27	L6-196	F.V Shirit tokez.St/Zn 40x4 ne kanale	ml	10		
28	MK- 70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	4		
29	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	14		
30	Analize	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	20		
KOLAUDIMET						
31	L6-395	Kolaudim ndaresi te jashtem 20 kV 400 A	cope	1		
32	L6-366	Kolaudim shkarkuesve ventil 10 kV 10 kA	cope	3		

33	L6-364	Kolaudim transformatore fuqie 6-10 -20 35/0.4 kV	cope	1		
34	L6-394	Kolaudim panel TU me matje	cope	1		
35	L6-402	Kolaudim i rezistences se tokezimit kabines	shtylle	2		
TRANSPORTI						
36	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto 0.5 ore per shtylle	ore	1		
37	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton	7.16		
38	2 - 37/5a	Transp.dheu me auto deri 5km	m ³	7.54		
39	3.An50	Transport materialesh elektrike me auto deri 10 km	ton	0.18		
Shuma "1/2"					leke	

PREVENTIV NR .1/3

B- LINJA TM RRASE E POSHTME 2

Nr	Analize	Emertimi i punimeve	Njesia	Sasia	Cmimi	Vlera
LINJA TM						
1	1.101/p+An	Pergatitje traversa metalike TU/TM, per linja 04 ~ 10 KV	ton	0.089		
2	MK- 32/62.1	Berje lozanke ne shtylle(ne shtyllat me dopio izolator per faze)	shtylle	2		
3	3.549/2 An	Shtirir/terheq 3 fije teli (percjelles) me makineri, ALÇ-35m/m ²	km	0.05		
4	MK-35-70	FV.Morseta me kanale paralele AL-AL 16-120 /16-120	cope	6		
AKSESORE SHTYLLE						
5	MK - 20	Vendosje traversa te medha (120-220) ne shtylle	cope	2		
6	3.569	Punime izolimi elektrik ne linja, T/M 6 - 10 kv, me izolator mbeshtetes, 6-10kv 3 cope	shtylle	4		
TOKEZIMI						
7	L6-197	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	20		
8	L6-193	F V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	2		
9	MK- 70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	2		
10	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	2		
11	Analize	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	2		
TRANSPORTI						
12	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto 0.5 ore per shtylle	ore	1.0		
Shuma "1/3"					leke	

PREVENTIV KABINA 14

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Grekan 1, me transformator Sn =560 kVA , Fideri 1 , N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	72.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	8,640.0		
3	MK - 10/22	Demontim traverse te vogla	cope	72.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	7.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	89.35		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	7.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	81.03		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	4.16		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	36.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	14.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	20.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	40.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	4.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	4.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetblokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	12.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	4.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	599.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	336.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	346.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	839.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,424.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	85.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	39.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	54.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	60.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	74.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	104.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	56.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	1,515.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	660.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	123.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	202.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	88.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	123.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	56.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	9.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	5.12		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	5.12		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	18.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	125.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	45.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	36.00		
5	MK - 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	18.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	18.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	18.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	4.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	18.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	85.05		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	52.50		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	33.20		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	89.35		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	3.17		
shuma			leke			

PREVENTIV KABINA 15

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Grekan 2, me transformator Sn =400 kVA , Fideri 1 , N/St Kajaj

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	43.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	5,160.0		
3	MK - 10/22	Demontim traverse te vogla	cope	43.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	5.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	58.71		
2	MK - 1/1	Ngjitje shtyll betoni me vinc per vendosje ne grope	cope	5.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	53.39		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.66		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	18.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	12.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	30.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	132.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	213.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	149.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	436.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	993.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	49.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	27.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	20.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	32.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	56.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	72.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	48.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	1,410.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	94.00		

3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	188.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	94.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	35.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	7.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	4.48		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	4.48		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	14.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	100.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	35.00		
4	MK-31/61	F.V. Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	28.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	14.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	14.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	14.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllle	14.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1 ton, teleskopik per h > 7 m (1,05 ore/shtyllle)	ore	55.65		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	31.50		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	20.10		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	58.71		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.77		
shuma			leke			

PREVENTIV KABINA 16

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Grekan 3, me transformator Sn =100 kVA , Fideri 1, N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtylle	shtyll	15.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	1,800.0		
3	MK - 10/22	Demontim traverse te vogla	cope	15.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	4.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	22.58		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	4.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	20.50		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	1.04		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	6.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	4.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	64.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	144.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	76.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	458.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	21.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	8.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	4.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	12.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	24.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	40.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	28.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	660.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	30.00		
2	MK - 35/70	FV. Tirantues abONENTI 4 x(16-95)mm ²	cope	45.00		

3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	88.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	4.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	45.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	17.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	4.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	5.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	35.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	12.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	10.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	5.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	5.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	5.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	5.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	22.05		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	10.50		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	6.70		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	22.58		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	0.66		
shuma			leke			

PREVENTIV KABINA 17

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Grekan 4, me transformator Sn =50 kVA , Fideri 1 , N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	38.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,560.0		
3	MK - 10/22	Demontim traverse te vogla	cope	38.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	1.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	58.87		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	1.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	53.48		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.69		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	24.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	11.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kabli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kabli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	132.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	126.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	310.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,480.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	43.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	25.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	6.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	20.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	72.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	64.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	48.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	570.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	38.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	76.00		

4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	38.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	21.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	5.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.80		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	2.80		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	10.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	55.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	25.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	20.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	10.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	10.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	10.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	10.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	52.50		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	36.75		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	23.30		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	58.87		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.33		
<i>shuma</i>			<i>leke</i>			

PREVENTIV KABINA 18

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Grekan 5, me transformator Sn =250 kVA , Fideri 1, N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	39.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,680.0		
3	MK - 10/22	Demontim traverse te vogla	cope	39.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	4.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	60.32		
2	MK - 1/1	Ngjitje shtyll betoni me vinc per vendosje ne grope	cope	4.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	54.73		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.79		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	24.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	10.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	200.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	279.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	286.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	377.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	959.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	47.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	23.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	24.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	34.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	46.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	68.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	40.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	1,095.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	73.00		

3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	146.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	73.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	35.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	9.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.92		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	3.92		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	12.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	70.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	30.00		
4	MK-31/61	F.V. Elektroda tokezimi, "X" 50x50x5mm L=1.5m e galvanizuar	cope	24.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	12.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	12.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	12.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllle	12.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1 ton, teleskopik per h > 7 m (1,05 ore/shtyllle)	ore	54.60		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	35.70		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	22.60		
4	3 - 158/5a	Transport dhe me auto deri 5.0 km (auto vetshkarkuese)	m ³	60.32		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.86		
shuma			leke			

PREVENTIV KABINA 19

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Gjolene 1, me transformator Sn =100 kVA , Fideri 3 , N/St Kajjan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	55.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	6,600.0		
3	MK - 10/22	Demontim traverse te vogla	cope	55.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	10.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	75.00		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	10.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	68.19		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	3.41		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	20.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	15.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	401.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	290.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	509.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	523.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	881.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	50.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	33.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	32.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	48.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	44.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	84.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	56.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	945.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	60.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	65.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	126.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	8.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	65.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	28.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	8.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	13.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	85.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	32.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	26.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	13.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	13.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	13.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	13.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	65.10		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	36.75		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	23.50		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	75.00		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.34		
<i>shuma</i>			<i>leke</i>			

PREVENTIV KABINA 20

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Gjolene 2, me transformator Sn =50 kVA , Fideri 3 , N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	32.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,840.0		
3	MK - 10/22	Demontim traverse te vogla	cope	32.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	7.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	42.90		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	7.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	38.87		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.02		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	2.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	15.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	6.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	186.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	224.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,163.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	37.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	14.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	20.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	56.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	44.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	32.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	330.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	30.00		
2	MK - 35/70	FV. Tirantues abonenti 4 x(16-95)mm ²	cope	23.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	44.00		

5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	4.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	23.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	16.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	1.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.88		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	2.88		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	9.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	55.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	22.50		
4	MK-31/61	F.V.Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	18.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	9.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	9.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	9.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllle	9.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1 ton, teleskopik per h > 7 m (1,05 ore/shtyllle)	ore	40.95		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	22.05		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	14.15		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	42.90		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.00		
shuma			leke			

PREVENTIV KABINA 21

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Kajan 1, me transformator Sn =100 kVA , Fideri 7 , N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	26.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,120.0		
3	MK - 10/22	Demontim traverse te vogla	cope	26.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	4.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	54.19		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	4.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	49.12		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.54		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	23.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	8.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	146.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	220.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	223.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	261.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	836.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	48.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	17.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	20.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	26.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	46.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	68.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	40.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	945.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	180.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	69.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	126.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	24.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	69.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	31.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	4.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	9.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	65.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	22.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	18.00		
5	MK - 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	9.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	9.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	9.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	9.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	49.35		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	32.55		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	20.55		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	54.19		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.48		
shuma			leke			

PREVENTIV KABINA 22

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Kajan 2, me transformator Sn =100 kVA , Fideri 7 , N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	32.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,840.0		
3	MK - 10/22	Demontim traverse te vogla	cope	32.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	5.00		
7	MK - 16	Drejtim shtylle betoni	cope	1.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	65.32		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	5.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	59.28		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	3.02		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	1.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	25.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	11.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	30.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	128.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	139.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	229.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	309.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,310.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	56.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	27.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	18.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	34.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	68.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	84.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	52.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	1,170.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	150.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	83.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	156.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	20.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	83.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	41.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	8.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.92		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.92		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	12.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	75.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	30.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	24.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	12.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	12.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	12.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	12.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	61.95		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	37.80		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	24.05		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	65.32		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.71		
shuma			leke			

PREVENTIV KABINA 23

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Kosove 1, me transformator Sn =100 kVA , Fideri 7, N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	43.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	5,160.0		
3	MK - 10/22	Demontim traverse te vogla	cope	43.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	5.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	81.29		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	5.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	73.90		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	3.70		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	3.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	28.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	16.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	20.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	40.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	4.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	4.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	12.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	4.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	371.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	147.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	369.00		
3	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	539.00		
4	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,109.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	73.00		
6	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	37.00		
7	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	34.00		
8	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	54.00		
9	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	68.00		
10	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	116.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	76.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	1,215.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	690.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	104.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	162.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	92.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	104.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	45.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	8.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	4.48		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	4.48		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	16.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	110.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	40.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	32.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	16.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	16.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	16.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	4.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	16.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	81.90		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	46.20		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	29.70		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	81.29		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.28		
shuma			leke			

PREVENTIV KABINA 24

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Kosove 2, me transformator Sn =100 kVA , Fideri 7 , N/St Kajan

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	22.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	2,640.0		
3	MK - 10/22	Demontim traverse te vogla	cope	22.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	1.00		
5	MK - 16	Drejtim shtylle betoni	cope	1.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	65.97		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	1.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	60.08		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.95		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	2.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	22.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	15.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	30.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	236.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	442.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	188.00		
3	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	287.00		
4	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	992.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	42.00		
6	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	36.00		
7	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	36.00		
8	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	24.00		
9	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	556.00		
10	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	76.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	48.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	795.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	30.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	54.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	106.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	4.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	54.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	26.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	8.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	11.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	60.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	27.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	22.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	11.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	11.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	11.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	11.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	52.50		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	38.85		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	25.00		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	65.97		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.86		
shuma			leke			

PREVENTIV KABINA 25

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Mamel 1 me transformator Sn =50 kVA , Fideri 6 , N/St Nr:1

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtylle	shtyll	36.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,320.00		
3	MK - 10/22	Demontim traverse te vogla	cope	36.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	18.09		
3	2-262/4	Shtrese betoni C 16/20	m ³	4.46		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	20.06		
5	Mk-8	F.V Shtylla Druri te impenjuara 8ml, 2.4kN ml (me krahe)	cope	23.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	2.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV.Shttrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme.vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	25.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	115.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	213.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	277.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,168.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	53.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	5.00		
8	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	8.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	28.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	54.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	68.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	36.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	675.00		
3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	45.00		
4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	90.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	45.00		

7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	25.00		
8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	2.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek.` 0.75 m ²	m ³	2.00		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	2.00		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	9.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	55.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	22.50		
4	MK-31/61	F.V.Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	18.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	9.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	9.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	9.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablove dhe kokave te kablove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	9.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	47.25		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	9.00		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	4.46		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	18.09		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.28		
shuma			leke			

PREVENTIV KABINA 26

**Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Mamel 2 me transformator Sn =50 kVA , Fideri 6 ,
N/St Nr:1**

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtylle	shtyll	33.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	3,960.00		
3	MK - 10/22	Demontim traverse te vogla	cope	33.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	12.21		
3	2-262/4	Shtrese betoni C 16/20	m ³	2.23		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	14.78		
5	Mk-8	F.V Shtylla Druri te impenjuara 8ml, 2.4kN ml (me krahe)	cope	17.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	1.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV.Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme.vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	115.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	128.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	289.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	837.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	43.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	3.00		
8	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	6.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	22.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	46.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	36.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	24.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	435.00		
3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	29.00		
4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	58.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	29.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	25.00		

8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	2.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.40		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	2.40		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	F.V. Konektor izolues linje (16-95/16-95)	cope	8.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	55.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	20.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	16.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	8.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	8.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	8.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	8.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1.05 ore/shtylle)	ore	39.90		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	6.15		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	2.23		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	12.21		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	0.98		
shuma			leke			

PREVENTIV KABINA 27

**Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Mamel 3 me transformator Sn =50 kVA , Fideri 6 ,
N/St Nr:1**

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	10.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	1,200.00		
3	MK - 10/22	Demontim traverse te vogla	cope	10.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	4.61		
2	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	4.61		
3	Mk-8	F.V Shtylla Druri te impenjuara 8ml, 2.4kN ml (me krahe)	cope	8.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	5.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	10.00		
3	4-141/a7.0	FV.Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	1.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	1.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme.vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	3.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	1.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	95.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	291.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	16.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	6.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	16.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	20.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	20.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	150.00		
3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	10.00		
4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	20.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	10.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	11.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.00		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	2.00		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	2.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	15.00		

3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	5.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	4.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	2.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	2.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm² M12	cope	2.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablove dhe kokave te kablove	cope	1.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	2.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	13.65		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	2.40		
3	3-392/An50	Transport materiale me auto deri ne 10 km	ton	0.25		
shuma			leke			

PREVENTIV KABINA 28

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Mamel 5 me transformator Sn =50 kVA , Fideri 6 , N/St Nr:1

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	45.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	5,400.00		
3	MK - 10/22	Demontim traverse te vogla	cope	45.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	21.24		
3	2-262/4	Shtrese betoni C 16/20	m ³	6.77		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	21.06		
5	Mk-8	F.V Shtylla Druri te impenjuara 8ml, 2.4kN ml (me krahe)	cope	24.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	2.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	2.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	370.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	615.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,171.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	56.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	5.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	50.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	52.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	44.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	32.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	330.00		
3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	22.00		
4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	44.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	22.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	16.00		
8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	1.00		

B/6 - PUNIME CIVILE					
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.00	
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	2.00	
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ					
1	MK-35/70	F.V. Konektor izolues linje (16-95/16-95)	cope	8.00	
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	60.00	
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	20.00	
4	MK-31/61	F.V.Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	16.00	
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	8.00	
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	8.00	
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	8.00	
B/6 - KOLAUDIME					
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00	
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	8.00	
B/7- TRANSPORT					
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	54.60	
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	11.40	
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	6.77	
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	21.24	
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.34	
shuma			leke		

PREVENTIV KABINA 29

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Petresh 1 me transformator Sn =100 kVA , Fideri 13 , N/St Nr:1

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	34.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,080.00		
3	MK - 10/22	Demontim traverse te vogla	cope	34.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	30.14		
3	2-262/4	Shtrese betoni C 16/20	m ³	24.87		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	5.52		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	5.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	8.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	7.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	242.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	326.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	353.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	254.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	549.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	45.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	12.00		
8	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	28.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	28.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	28.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	56.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	32.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	510.00		
3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	34.00		
4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	68.00		

6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	34.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	19.00		
8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	4.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.40		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	2.40		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	7.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	50.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	17.50		
4	MK-31/61	F.V.Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	14.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	7.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	7.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	7.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	7.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	44.10		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	17.25		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	24.87		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	30.14		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.54		
shuma			leke			

PREVENTIV KABINA 30

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Petresh 2 me transformator Sn =180 kVA , Fideri 13 , N/St Nr:1

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	48.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	5,760.00		
3	MK - 10/22	Demontim traverse te vogla	cope	48.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	51.31		
3	2-262/4	Shtrese betoni C 16/20	m ³	45.55		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	4.03		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	2.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	22.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	9.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	30.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetblokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	621.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	181.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	301.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	451.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,040.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	68.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	25.00		
8	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	50.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	40.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	52.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	104.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	64.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	1,200.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	60.00		
3	MK - 35/70	FV.Tirantues abONENTI 4 x(16-95)mm ²	cope	82.00		

4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	160.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	8.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	82.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	35.00		
8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	7.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.88		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	2.88		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	10.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	70.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	25.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	20.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	10.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	10.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	10.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	10.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	58.80		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	33.15		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	45.55		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	51.31		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.41		
shuma			leke			

PREVENTIV KABINA 31

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Shemhill me transformator Sn =180 kVA , Fideri 13, N/St Nr:1

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	36.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,320.00		
3	MK - 10/22	Demontim traverse te vogla	cope	36.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	42.90		
3	2-262/4	Shtrese betoni C 16/20	m ³	38.87		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.02		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	22.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	6.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	20.00		
3	4-141/a7.0	FV.Shttrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme.vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	100.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	155.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	322.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	297.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	815.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	50.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	10.00		
8	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	20.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	30.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	50.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	68.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	40.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	990.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	30.00		
3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	67.00		
4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	132.00		

5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	4.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	67.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	37.00		
8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	3.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.00		
2	3-88/a	Hedhje, rrafshim, mbushje dhe me krah, kategoria III	m ³	2.00		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	13.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	80.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	32.50		
4	MK-31/61	F.V.Elektroda tokezimi, "X"50x50x5mm L=1.5m e galvanizuar	cope	26.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	13.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	13.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	13.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	13.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1 ton, teleskopik per h > 7 m (1,05 ore/shtyllle)	ore	51.45		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	29.40		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	38.87		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	42.90		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.52		
shuma			leke			

PREVENTIV KABINA 32

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Polis Vogel 1 me transformator Sn =180 kVA , Fideri 2 , N/St Fiber

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	75.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	9,000.00		
3	MK - 10/22	Demontim traverse te vogla	cope	75.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	71.02		
3	2-262/4	Shtrese betoni C 16/20	m ³	58.92		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	12.39		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	11.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	22.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	15.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	30.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetblokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	903.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	582.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	429.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	603.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,553.00		
6	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x16 mm ²	ml	245.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	81.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	41.00		
8	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	74.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	50.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	80.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	120.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	72.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	1,275.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	90.00		

3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	88.00		
4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	170.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	12.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	88.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	47.00		
8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	10.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	3.20		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.20		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	12.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	90.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	30.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	24.00		
5	MK - 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	12.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	12.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	12.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	12.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	88.20		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	42.15		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	58.92		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	71.02		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	3.73		
<i>shuma</i>			<i>leke</i>			

PREVENTIV KABINA 33

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Polis Vogel 2 me transformator Sn =100 kVA , Fideri 2, N/St Fiber

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	65.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	7,800.00		
3	MK - 10/22	Demontim traverse te vogla	cope	65.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	80.32		
3	2-262/4	Shtrese betoni C 16/20	m ³	69.35		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	9.52		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	7.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	31.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	15.00		
B/3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	30.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetblokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B/4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	251.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	421.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	415.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	768.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,325.00		
6	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x16 mm ²	ml	135.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	72.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	27.00		
8	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	36.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	52.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	70.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	80.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	40.00		
B/5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	735.00		
3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	49.00		

4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	98.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	49.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	26.00		
8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	6.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.20		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	3.20		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	15.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	95.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	37.50		
4	MK-31/61	F.V. Elektroda tokezimi, "X" 50x50x5mm L=1.5m e galvanizuar	cope	30.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	15.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	15.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	15.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllle	15.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1 ton, teleskopik per h > 7 m (1,05 ore/shtyllle)	ore	73.50		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	50.40		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	69.35		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	80.32		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.54		
shuma			leke			

PREVENTIV KABINA 34

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Paper Sallak 2 me transformator Sn =50 kVA , Fideri Bishqem , N/St Cerrik

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	56.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	6,720.00		
3	MK - 10/22	Demontim traverse te vogla	cope	56.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	2.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	29.97		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	2.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	17.21		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	17.33		
5	Mk-8	F.V Shtylla Druri te impenuara 8ml, 2.4kN ml (me krahe)	cope	19.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	9.00		
7	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	2.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtrim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	227.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	226.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	214.00		
4	MK-43/102.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	650.00		
5	MK-43/101.C	FV.Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,334.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	67.00		
7	MK-35/70	FV.Qafore linje me dy krah per D=220	cope	5.00		
8	MK-35/70	FV.Tirantues linje 4x(70-95)mm ²	cope	24.00		
9	MK-35/70	FV.Tirantues linje 4x(35-50)mm ²	cope	44.00		
10	MK-35/70	FV.Tirantues linje 4x(25-16)mm ²	cope	62.00		
11	MK-35/70	F V.Konektor izolues linje (16-95/16-95)	cope	44.00		
12	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	28.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV.Kabell koaksial TU Cu 2x6 mm2 (1x6/6)mm ²	ml	495.00		

3	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	33.00		
4	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	66.00		
6	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	33.00		
7	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	22.00		
8	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	1.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	2.40		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	2.40		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	14.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	105.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	35.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	28.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	14.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	14.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	14.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	14.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	68.25		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	19.35		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	17.21		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	29.97		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.00		
shuma			leke			

PREVENTIV KABINA 35

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Blate , me transformator Sn =180 kVA , Fideri Shales , N/St Cerrik

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	56.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	6,720.0		
3	MK - 10/22	Demontim traverse te vogla	cope	56.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	5.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	86.44		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	5.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	78.09		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	4.17		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	47.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	8.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	30.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	237.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	212.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	407.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	535.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,395.00		
6	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x16 mm ²	ml	445.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	73.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	15.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	24.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	44.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	82.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	88.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	64.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	1,800.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	120.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	124.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	240.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	16.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	124.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	58.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	9.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	4.48		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	4.48		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	18.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	105.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	45.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	36.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	18.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	18.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	18.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	18.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	79.80		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	57.75		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	36.15		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	86.44		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.62		
shuma			leke			

PREVENTIV KABINA 36

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Sopi Gelqeres , me transformator Sn =100 kVA , Fideri Shales , N/St Cerrik

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	55.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	6,600.0		
3	MK - 10/22	Demontim traverse te vogla	cope	55.00		
4	MK - 17	Shkulje shtylle b.a.c me vinc	cope	2.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	68.70		
2	MK - 1/1	Ngritje shtylle betoni me vinc per vendosje ne grope	cope	2.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	62.05		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	3.33		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	40.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	6.00		
B3 - KABLLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtylle	ml	30.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtylle 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B4 - KABLLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	275.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	214.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	295.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	655.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	805.00		
6	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x16 mm ²	ml	425.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	63.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	14.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	26.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	42.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	60.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	88.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	40.00		
B5 - KABLLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	975.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	65.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	130.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	65.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	35.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	5.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.92		
2	3-88/a	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	3.92		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	15.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	95.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	37.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	30.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	15.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	15.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	15.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	15.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	65.10		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	48.30		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	30.20		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	68.70		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	2.15		
shuma			leke			

PREVENTIV KABINA 37

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Xibrake Qender 1 , me transformator Sn =320 kVA , Fideri Shales , N/St Cerrik

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	90.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	10,800.0		
3	MK - 10/22	Demontim traverse te vogla	cope	90.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	3.00		
B/2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	114.99		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	3.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	104.12		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	5.44		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	58.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	15.00		
B/3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	20.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	40.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	4.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ²	cope	4.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	12.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	4.00		
B/4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	674.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	415.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	446.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	725.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,543.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	91.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	46.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	72.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	64.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	82.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	136.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	72.00		
B/5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	3,090.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	480.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	222.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	412.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	64.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	222.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	77.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	13.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	4.48		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	4.48		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	19.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	105.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	47.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	38.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	19.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	19.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	19.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	4.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	19.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	102.90		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	76.65		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	48.20		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	114.99		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	3.80		
<i>shuma</i>			<i>leke</i>			

PREVENTIV KABINA 38

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Xibrake 2 , me transformator Sn =50 kVA , Fideri Shales , N/St Cerrik

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	37.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	4,440.0		
3	MK - 10/22	Demontim traverse te vogla	cope	37.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	3.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	60.48		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	3.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	54.82		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	2.83		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	27.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	9.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	15.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	30.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	3.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	3.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	9.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	3.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	156.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	148.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	300.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	315.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	640.00		
6	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x16 mm ²	ml	190.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	39.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	20.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	14.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	32.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	40.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	80.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	32.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	585.00		

2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	60.00		
2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	41.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	78.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	8.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	41.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	23.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	6.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TIJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	9.00		
2	MK-55/144	F.V Litar çeliku St/Zn Ø 12 mm(fleksibel)	ml	55.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	22.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	18.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	9.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	9.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	9.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kabllave dhe kokave te kabllave	cope	3.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtylle	9.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtylle)	ore	47.25		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	37.80		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	23.85		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	60.48		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.39		
shuma			leke			

PREVENTIV KABINA 39

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Gjyrale 1 , me transformator Sn =160 kVA , Fideri Shales , N/St Cerrik

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	84.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	10,080.0		
3	MK - 10/22	Demontim traverse te vogla	cope	84.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	5.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	62.25		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	5.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	56.25		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	3.00		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	32.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	6.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	20.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	40.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	4.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	4.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	12.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	4.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	542.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	443.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	551.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	877.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	1,353.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	100.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	15.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	60.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	60.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	66.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	124.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	64.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	1,980.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	210.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	139.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	264.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	28.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	139.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	77.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	6.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	3.92		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.92		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	17.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	135.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	42.50		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	34.00		
5	MK- 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	17.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	17.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	17.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	4.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	17.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	101.85		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	39.90		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	25.00		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	62.25		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	3.45		
<i>shuma</i>			<i>leke</i>			

PREVENTIV KABINA 40

Emërtimi i preventivit : Rrjet TU me kablo me vetembajtje ABC Kabina Gjyrale 2 , me transformator Sn =180 kVA , Fideri Shales , N/St Cerrik

Nr	Analiza	Emertimi i materialit	Njesia	Sasia	Çmimi	Vlera
B1 - DEMONTIME						
1	MK -16/32	Zgjidhja e telit TU ne qafat e izolatoreve per nje shtyll	shtyll	46.00		
2	24/45D-25/49D	Ulja dhe mbledhja e telit me krah me seksion deri 70 mm ²	ml	5,520.0		
3	MK - 10/22	Demontim traverse te vogla	cope	46.00		
4	MK - 17	Shkulje shtyll b.a.c me vinc	cope	1.00		
B2 - SHTYLLA						
1	3-498/b	Germim gropa shtyllash, toke e forte kat IV, ~2.5m, sip tab 1.5m ²	m ³	41.61		
2	MK - 1/1	Ngritje shtyll betoni me vinc per vendosje ne grope	cope	1.00		
3	2-262/4	Shtrese betoni C 16/20	m ³	37.71		
4	2-261	Mbushje me rere per fiksimin e shtyllave b/a	m ³	1.95		
5	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 6kN (me makineri)	cope	20.00		
6	MK-1	F.V. Shtylla betonarme te centrifuguara 9 ml, 15kN (me makineri)	cope	6.00		
B3 - KABLO XLPE TU 0,6/1 kV +AKSESORE (DALJET E PARA)						
1	MK-42/98.1	FV. kabell TU fuqie XLPE AL-4x95mm ² ne toke	ml	10.00		
2	MK-42/98.2	FV. kabell TU fuqie XLPE AL-4x95mm ² ne shtyll	ml	20.00		
3	4-141/a7.0	FV. Shtirim shirit sinjalizimi per kablo 20kV	ml	5.00		
4	MK-44/112	FV. Terminal per kabell fuqie TU , me 4 deje 4x70 - 4x120 mm ²	cope	2.00		
5	MK-46/126	FV. Terminal tu 0.4kV per kalim nga kablli pvc ne kabell abc mm ² (cope	2.00		
6	MK- 29/57 An	FV. Fasheta metalike. jashteme. vetbllokuese 0.25x12x1200mme per fiksimin e kabllit ne shtyll 0.25x12x1200 mm	cope	6.00		
7	MK - 35/70 An	FV. Mbrojtese kablli (Tub i galvanizuar " 3" per mbrojtjen e kabllit) L=2.5ml	cope	2.00		
B4 - KABLO ALUMINI ME VETEMBAJTJE TIP " ABC "+AKSESORE						
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x95 mm ²	ml	194.00		
1	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x70 mm ²	ml	241.00		
2	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x50 mm ²	ml	187.00		
3	MK-43/102.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x35 mm ²	ml	415.00		
4	MK-43/101.C	FV. Kablo TU me vetmbajtje "ABC" Al-4x25 mm ²	ml	936.00		
5	MK-35/70	FV. Qafore linje me dy krah per D=150	cope	57.00		
6	MK-35/70	FV. Qafore linje me dy krah per D=220	cope	14.00		
7	MK-35/70	FV. Tirantues linje 4x(70-95)mm ²	cope	24.00		
8	MK-35/70	FV. Tirantues linje 4x(35-50)mm ²	cope	30.00		
9	MK-35/70	FV. Tirantues linje 4x(25-16)mm ²	cope	54.00		
10	MK-35/70	F V. Konektor izolues linje (16-95/16-95)	cope	88.00		
11	MK-35/70 An	FV. Koke fundore 16-95mm ²	cope	48.00		
B5 - KABLO TU PER FURNIZIMIN E ABONENTIT+ AKSESORE						
1	MK-43/100.C	FV. Kabell koaksial TU Cu 2x6 mm ² (1x6/6)mm ²	ml	1,470.00		
2	MK-43/101.C	F.V Kabell Cu 4x10mm ² me izolac. PVC - 0.6/1kV i abonentit	ml	390.00		

2	MK - 35/70	FV.Tirantues abonenti 4 x(16-95)mm ²	cope	111.00		
3	MK - 35/70	FV. Konektore abonenti 16-95/1.5-10mm ²	cope	196.00		
5	MK - 35/70	FV.Konektor abonenti 35-70/16-25mm ²	cope	52.00		
4	MK-17/34 An	F.V Up fiksus metalik Ø12+ganxhe me forme sy hapur	cope	111.00		
5	MK-35/70	F.V Qafore abonenti D = 150 mm	cope	50.00		
6	MK-35/70	F.V Qafore abonenti D = 220 mm	cope	6.00		
B/6 - PUNIME CIVILE						
1	3-46/1	Germim kanalesh ne toke te forte, me krahe, me sek. ` 0.75 m ²	m ³	3.36		
2	3-88/a	Hedhje,rrafshim,mbushje dheu me krah, kategoria III	m ³	3.36		
B/5- TOKEZIMI I PERSERITUR I NEUTRIT DHE AKSESORET E TLJ						
1	MK-35/70	FV. Konektor izolues linje (16-95/16-95)	cope	10.00		
2	MK-55/144	F.V Litar çeliku St/Zn Φ 12 mm(fleksibel)	ml	70.00		
3	MK-55/143	F.V Shirit Tokezimi 40x4mm	ml	25.00		
4	MK-31/61	F.V.Elektroda tokezimi,"X"50x50x5mm L=1.5m e galvanizuar	cope	20.00		
5	MK - 35/70	FV. Morset univers. shkeputes Tokz Ø 9-16 mm	cope	10.00		
6	3-Çm-156	F.V Bullon St/Zn M12x40 dado/rondele suste/rondele drejte	cope	10.00		
7	L6-107	F.V. kapikorda te xinguara 95 mm ² M12	cope	10.00		
B/6 - KOLAUDIME						
1	L6 - 403	Kenotronimi i kablllove dhe kokave te kablllove	cope	2.00		
2	L6 - 402	Kolaudim i rezistences se tokezimit	shtyllë	10.00		
B/7- TRANSPORT						
1	MN-3-Çm-46	Sherbim vinc kulle 0.5-1ton, teleskopik per h > 7 m (1,05 ore/shtyllë)	ore	58.80		
2	3-Çm -17/An	Autovinxh 5 ton per ngritjen e zbritjen e shtyllave ne auto	ore	27.30		
3	3.An50	Transport element betoni dhe b/a me auto deri 10 km	ton/km	17.20		
4	3 - 158/5a	Transport dheu me auto deri 5.0 km (auto vetshkarkuese)	m ³	41.61		
5	3-392/An50	Transport materiale me auto deri ne 10 km	ton	1.81		
shuma			leke			