

PREVENTIV PUNIMESH

OBJEKTI: SISTEMIM - ASFALTIM RRUGA BELSH - STANAJ

BASHKIA BELSH

Nr.	NR.AN	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	VLERA
I						
PUNIME GERMIMI						
1	An/M_3	Skarifikim shtrese asfalti me makineri	m ²	1,757.815		
2	3.110/a	Germim dheu me ekskavator zingjir 1.0 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	9,885		
3	An.164/1a	Mbushje me material rrethanor te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	772		
4	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	9,885		
Shuma I						
II						
PUNIME NE TRUPIN E RRUGES						
1	An_01	Mbushje, profilim me zhavor	m ³	1,944.4		
2	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m ²	12,985		
3	3.212/b	Shtrese stabilizant t=10cm	m ²	12,985		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m ²	13,998		
5	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	13,998		
6	An_02	Mbushje dhe nivelim bankine	m ²	4,312		
Shuma II						
III						
TOMBINO RRETHORE d=40-80						
1	3.110/a	Germim dheu me ekskavator zingjir 1.0 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	100		
2	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	100		
3	An-9/M_3	Mbushje me zhavorr pas mureve	m ³	30		
4	3.243	Beton C16/20 per hyrje daljet e portaleve	m ³	20		
5	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	20		
6	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	30		
7	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	m	8		
8	An_03	Shpim me sistem makinerie e drejtuar me lazer per realizim mikrotuneli me Ø (250-1000)mm	ml	10		
Shuma III						
IV						
PUNIME ME KANALE DHE KUNETA						
1	3.243	Struktura monolite betoni C 16/20 (kanale + kunete)	m ³	65		
2	3.183/a	Shtrese zhavor lumi t=10cm	m ²	550		
Shuma IV						

V		PUNIME ME SINJALISTIKEN				
1	An124/M_3	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm, Akrelike	ml	6,500		
2	An105/M_3	Tabela trekendore e vogel me A = 60	cope	2		
3	An103/M_3	Tabele rrethi "ndalim" normal me D = 60	cope	2		
		Shuma V				
		SHUMA I ÷ V				
		T.V.SH. 20 %	20%			
		SHUMA TOTALE				

Shenime: Cmimet e preventivit jane ne baze manualit te cmimeve te vitit 2015.

Preventivues :

“ERALD-G”SH.P.K

Ing. Gezim Islami