



**REPUBLIKA E SHQIPERISE**  
**BASHKIA KAMEZ**

**PREVENTIV**

**OBJEKTI : Ndertim Rruga Isa Boletini ,Paskuqan 1 , Bashkia Kamez**

**( Lt = 505 ml, B = 6 m, basf= 4.5 m,(1 x 0.5 ) kunete, ( 1x1 m), Trotuare**

<b>A</b>	<b>An.</b>	<b>Emertimi i Punimeve</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
<b>I PUNIME GERMIMI</b>						
1	3.139	Germim Dheu me Eskavator Kt III	m <sup>3</sup>	750		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	750		
3	An.	Spostim Shtyllash Elektrike ( komplet me Kabllo )	cope	6		
<b>SHUMA I</b>						
<b>II PUNIME NE RRUGE</b>						
1	An-8	Mbushje me çakell shkembor	m <sup>3</sup>	500		
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	2272		
3	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	2272		
4	3.222/2	Shtrese binderi 1x6 cm	m <sup>2</sup>	2272		
5	3.226/1	Shtrese asfaltobetoni 1x4cm	m <sup>2</sup>	2272		
6	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m <sup>3</sup>	120		
7	An.	Ngritje pusete+kapak gize	cope	5		
<b>SHUMA II</b>						
<b>III PUNIME BORDURE + KUNETE</b>						
1	2.262/4	Shtrese betoni c 16/20 Kunete betoni	m <sup>3</sup>	25.25		
2	3.617	F.V. Bordura Betoni 15x25	ml	1010		
3	2.262/4	Shtrese betoni c 16/20 poshte bordures 0.03 m3/ml	m <sup>3</sup>	30.3		
<b>SHUMA III</b>						
<b>IV PUNIME NE KUB</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	240		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	240		
3	3/353	Mbushje me çakell shkembor	m <sup>3</sup>	120		
4	3.an/1t	F.V. Tuba i brinjzuar Ø 315	ml	500		
5	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	14		
<b>SHUMA IV</b>						
<b>V PUNIME NE KANALIZIME TE UJRAVE TE ZEZA</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
1	3.89/1	Germim dheu me eskavator goma 0.25 m3 , ne kanale gjersi deri 2 m, toke e zakonshme e shkarkime ne mjet	m <sup>3</sup>	75		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	75		
3	An /21 Man 2	Puseta Shkarkimi b/a 80x80 cm , h deri 2 m me kapak gize	cope	3		

4	3.An/21t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	120		
6	an-8	Mbushje me çakell shkembor	m <sup>3</sup>	139.2		
<b>SHUMA V</b>						
<b>VI</b>	<b>PUNIME TROTUARE( 1 X1 )</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	150		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	150		
3	3/353	Mbushje me çakell shkembor	m <sup>3</sup>	150		
5	3.208	Shtrese çakelli T=10cm	m <sup>2</sup>	425		
7	2.109/2	Beton C12/15 per trotuar	m <sup>3</sup>	45.0		
<b>SHUMA VI</b>						
<b>VII</b>	<b>PUNIME MURE MBAJTESE E PRITese</b>					
<b>Nr.</b>			<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	65		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	65		
3	3.243	Beton C 16/20 per mure mbajtese e pritese	m <sup>3</sup>	98		
4	An-8	Mbushje me Çakull pas mureve	m <sup>3</sup>	45		
5	3.654	Furnizim vendosje tuba drenazhi O 100	ml	12		
6	3.211	Shtrese Cakulli mbeturine nen mure t=20 cm	m <sup>2</sup>	50		
7	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.35		
<b>SHUMA VII</b>						
<b>VIII</b>	<b>PUNIME PER NDRIÇIMIN</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	500		
5	3.652	F.V Tuba HDPE d=200 mm per shtyllat	ml	14		
6	3.an/ksh	F.V Elektroda tokezim 50x3 mm komplet l=150m	cope	14		
9	An	F.V kabell tokezimi 1x3.5mm	ml	25		
11	An-22/1	F.v puseta betoni me kapak gize 40x40 h=100cm	cope	14		
13	2.109/2	Beton C12/15 per inkastrim shtylle	m <sup>3</sup>	3.2		
14	An.	F.V kasete shperndarese	cope	1		
15	3.139	Germime dheu me ekskavator me goma	m <sup>3</sup>	50		
16	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	50		
17	2.261	Mbushje me rere	m <sup>3</sup>	20		
18	An-8	Mbushje me cakull shkembor (kanal)	m <sup>3</sup>	42		
<b>SHUMA VIII</b>						
<b>X</b>	<b>PUNIME PER SINJALISTIKEN</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Çmimi</b>	<b>Vlera</b>
1	An151	Vizime me boje bikomponente ( Gjatesi x 3 ane x 10 cm = totali m2)	m <sup>2</sup>	101		
2	An138	Vizime me boje bikomponente paste per kembesore	m <sup>2</sup>	12		
3	An155	F.V. Tabela sinjalistike rrugore	cope	6		
<b>Shuma X</b>			<b>leke</b>			
<b>XI</b>	<b>PUNIME PRISHJE</b>					
1	An-49	Prishje struktura prej betoni + transport	m <sup>3</sup>	98.0		
2	2.426/2	Prishje mur tulle , guri ose blloqe + transport	m <sup>3</sup>	356.9		
<b>Shuma XI</b>			<b>leke</b>			
<b>SHUMA A ( I-II+ .. +XI</b>						
<b>TVSH 20%</b>						

<b>TVSH TOTALE</b>				
--------------------	--	--	--	--

V.O. Preventivi eshte hartuar ne baze te Vkm nr. 629 date 15.07.2015 + analizat perkatese

PREVENTIVUES :

Ing. Hajredin Murgu

Drejtore Projekteve dhe Investimeve

Ing. Flora MUÇA

Drejtor i Pergjithshem I.P.SH.P.

Elvis Gjika

**MIRATOI**  
**Rakip SULI**

---

**K R Y E T A R**