

**MIRATOHET  
KRYETAR  
TONIN MARINAJ**

**PREVENTIV PUNIMESH PA CMIME**

**Objekti : " SISTEMIM ASFALTIM I RRUGËS "LAGJE E RE-NDRECAJ, BAJZË "**

<b>Nr</b>	<b>Nr AN</b>	<b>EMERTIMI I PUNIMEVE</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Cmimi</b>	<b>Vlera</b>
		<b>I.PUNIME NE RRUGE</b>				
1	3.89/a + 3.158/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet + Transport dheu me auto deri 5 km	m <sup>3</sup>	246		-
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	1,100		-
3	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m <sup>3</sup>	51		-
4	3.212/b	Shtrese stabilizanti 10cm per rrugen	m <sup>2</sup>	1,600		-
5	3.212/a	Shtrese stabilizanti t=5cm	m <sup>2</sup>	190		-
6	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m <sup>2</sup>	1,280		-
8	3.240	Struktura monolite betoni C 12/15 (kunete)	m <sup>3</sup>	5.9		-
		<b>SHUMA</b>				-
		<b>TVSH 20%</b>				-
		<b>TOTALI</b>				-

**PREVENTIVOI  
"Novatech Studio"shpk  
Ing.Emil Nova**