

## **PREVENTIV**

### **MIRATOHET KRYETARI I BASHKISE RAHIM SPAHIU**

**OBJEKTI : RIKONSTRUKSION I SHKOLLES 9 - VJEÇARE**

**FSHATI MUSTAFE**

**NJESIA ADMINISTRATIVE ARRAS**

<b>Nr.</b>	<b>Nr.An</b>	<b>EMERTIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>ÇMIMI</b>
<b>A</b>		<b>PUNIME PRISHJE</b>			
1	An.	Prishje çatie vendi mbuluar me tjegulla marsel.	m <sup>2</sup>	132	
2	An/1	Heqje dyer + transport	m <sup>2</sup>	18.4	
3	An/3	Prishje suvatimi ne mure+tavane+trans mbet.	m <sup>2</sup>	92	
4	2.426/3	Prishje shtresa betoni poshte pllakave te dysh.	m <sup>3</sup>	20.4	
5	An/4	Prishje shtrese me pllaka + transport mbeturin.	m <sup>2</sup>	408	
		<b>SHUMA A:</b>			
<b>B</b>		<b>PUNIME GERMIMI</b>			
1	2,1	Germim dheu me krah,dhe transport me karroce dore deri 10 ml, kat III	m <sup>3</sup>	5.2	
2	2,1/a	Germim dheu me krah, prapa shkolles seksion i detyruar per kanal , toke e zakonshme	m <sup>3</sup>	5.4	
3	2.15/a	Germim dheu me krah, kanal kuz, dhe ujesjellsi.	m <sup>3</sup>	87.4	
		<b>SHUMA B:</b>			
<b>C</b>		<b>PUNIME BETONI</b>			
1		Shkalle beton C-16/20	m <sup>3</sup>	1.3	
2		Mure Betoni per kanal C-12/15, mbrapa shkolles	m <sup>3</sup>	4.1	
		<b>SHUMA C:</b>			
<b>D</b>		<b>PUNIME SUVATIMI + SHTRESA</b>			
1	2.300.	Suvatim solete h-4m,me drejtues me krah	m <sup>2</sup>	8.4	
2	2.310.	Suva brenda mure tulle h-4m, me krah, llac perzier M25	m <sup>2</sup>	22	
3	2.262/4	Shtrese betoni C 16/20, per nivelim, t=5cm	m <sup>3</sup>	20.4	
4	2.267/1	Shtrese me pllaka porcelani importi	m <sup>2</sup>	408	
5	2.264	Shtrese me pllaka granili shkallet e jashtme	m <sup>2</sup>	15,4	
6	2.324/a	Plintuse pllake grez	ml	365	
7	2.350.	Suva xokoli me granil e cemento te zakon. me spruco.	m <sup>2</sup>	42	
8	2,355/b	Suva e zakonshme fasade, ne mure tulle h = 8 m	m <sup>2</sup>	36	
		<b>SHUMA D:</b>			

<b>E</b>		<b>PUNIME ÇATIE</b>			
1	2,219	Ndertim çati vendi e zakonshme me lende te rrumbullaket mbuluar me tjegulla marseleze	m <sup>2</sup>	132	
2	2.209	Ulluk shkarkimi vertikal me llamarine xingato, dhe diameter ø100 mm	ml	43	
	2.212/a	Ulluk shkarkimi horizontal me PVC 33cm	ml	14	
2	2,206	Kasete shkarkimi me llamarine xingato	cope	6	
		<b>SHUMA E:</b>			
<b>F</b>		<b>PUNIME DYER - DRITARE</b>			
1	2.394/a	F.V. dyer te brendeshme tambur.te rimesuara.	m <sup>2</sup>	14.4	
2	2.395/a	F,V. Dere e jashtme druri	m <sup>2</sup>	4	
3	An. Mn.2	F.V. Porte metalike dekorative	m <sup>2</sup>	4,5	
		<b>SHUMA F:</b>			
<b>I</b>		<b>PUNIME KANALIZIMI</b>			
1	2491/e	F.V.Tub+rakorderi ujes. PE d=50 mm, PN-16	ml	196	
2	2.523/1	F.V. tuba pvc ø200mm te brinjezuar	ml	120	
3	2.258/2	Shtrese rere poshte tubit kuz ,ne kanal t= 10 cm	m <sup>3</sup>	6	
4	An19	Pusete shkarkimi b/a, 80x80 cm , h= 100cm	cope	3	
		<b>SHUMA I:</b>			
		<b>PUNIME SHERBETIM + BOJATISJE</b>			
1	2,404	Boje hidroplastike (per muret e jashteme)	m <sup>2</sup>	546	
2	2,399	Sherbetisje e bojatisje me gelqere brenda	m <sup>2</sup>	1 648	
		<b>SHUMA J:</b>			
		<b>SHUMA A+B+C+D+E+F+I+J:</b>			
		<b>Fond rezerve 3%</b>			
		<b>SHUMA:</b>			
		<b>Tvsh 20 %</b>			
		<b>TOTALI:</b>			

**PREVENTIVOI:  
ING. BEDRI SHEHU**







