



REPUBLIKA E SHQIPËRISË
BASHKIA VLORE
NJESIA ADMINISTRATIVE QENDER

MIRATOHET

KRYETARI
Dritan LELI

PREVENTIV

Objekti : "RIKONSTRUKSIONI I RRUGES SE FSHATIT KERKOVE"

Nr	Nr.anal	Pershkrimi i Punimeve	Njesia	Sasia	Cmimi	Vlefte
	I	<i>Punime germimi</i>				
1	3.89/a	Germim dheu me eskavator me goma 0,25m ³ kanale me gjeresi deri 2m, toke e zak, kat.III , shkarkim ne mjet	m ³	710		
2	3.87/b	Germim dheu me eskavator me goma 0,25m ³ kanale me gjeresi deri 2m, toke e zak, kat.III , shkarkim ne toke	m ³	120		
3	3.158/2a	Transport dheu deri ne 2 km	m ³	710		
		SHUMA I				
	II	<i>Punime ne trupin e rruges</i>				
1	An	Skarifikim shtrese asfalti me makineri	m ²	220		
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri	m ²	610		
2	An.164/1b	Mbushje me çakell e gur gurore ne trupin e rruges perhapur e ngjeshur me makineri	m ³	120		
3	3.222/2	Shtrese binderi me granil gur kave, 6 cm me makineri	m ²	8920		
4	3.226/1	Shtrese asfaltobetoni me granil gur kave, 4 cm me makineri	m ²	8920		
5	3.212/b	Shtrese stabilizanti 10cm per bankinat dhe sheshet	m ²	2400		
6	3.244/1	Struktura te holla monolite betoni C20/25 (kuneta)	m ³	12		
7	3.365	Tombino me tuba betoni Ø600, mbi shtrese betoni komplet	ml	24		
8	3.366	Tombino me tuba betoni Ø800, mbi shtrese betoni komplet	ml	48		
9	3.323	Mur guri mbajtes e themele llac cimento M.50	m ³	84		
		SHUMA II				
	III	<i>Punime te ndryshme</i>				

1	3.245	Struktura monolite betoni C- 25/30 (veshje kanali)	m3	6		
2	2.182	Konstruksione metalike te thjeshta (zgare metalike)	ton	0.6		
		SHUMA III				
		SHUMA I+ II+III				
		T V SH 20 %				
		TOTALI				

PREVENTIVOI : ing.Edmond BEQIRI
Liç.K.0147/5