

RRUGA NE FSHATIN XHERIE, CERRIK
GJATESIA E RRUGES L=4195.5 ml.

Nr.	Nr.An.	Emertimi i Punimeve	Njesia	Sasia	Volume pune	Grafiku
1	2	3	4	5	Brenda 20 diteve nga lidhja e kontrates	Muaji Mars 20 dite kohezzgatje
1.-Punime Germimi dhe Mbushje ne Rruge					0	0
1	3.104/b	Germim dheu seksion i lire me eskavator 0.5 m ³ me gjeresi b>2m, kat.IV, shkarkim ne mjet	m ³	14374	14374	0
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	13216	13216	0
3	An.164/1a	Mbushje me material me te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	1158	1158	0
		Shuma 1			0	0
2.-Punime Shtresash ne Rruge					0	0
3	3.212/b	Shtrese stabilizant t=10cm, per bankine	m ²	4195.5	3775.95	419.6
4	3.212/b	Shtrese stabilizanti, t=10 cm, perhapur dhe ngjeshur me makineri	m ²	18879.7	16991.73	1888.0
		Shuma 2			0	0
3.- Ndertim VEPRRA ARTI					0	0
1	3.105/a	Germim dheu me eskavator zingjir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	49.7	49.7	0
2	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	18	18	0
3	3.364	Tombino me tuba betoni Ø 500, mbi shtrese betoni	ml	18	18	0
4	2.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	18	18	0
5	3.243	Struktura monolite betoni C 16/20, per portale dhe puseta	m3	63.4	63.4	0
6	3.183/a	shtrese zhavorr lumi t=10cm	m2	620	620	0
7	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	49.7	49.7	0
		Shuma 3				
		Shuma (1+3)				
		TVSH 20 %				
		Shuma Totale				