



REPUBLIKA E SHQIPERISE

BASHKIA PRRENJAS

PREVENTIV

MIRATOHET
KRYETARI BASHKISE
NURI BELBA



Objekti :Rikonsonstruksion i kanaleve ujitëse Bashkia Prrenjas

Investitori:Bashkia Prrenjas

Nr.	Nr.an	Emertimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Kanali Bregu i Bogdanit Kovanik Segmenti 1,2				
		<i>Segmenti 1</i>				
1	3.59/a	Germim themel I vecuar , gropa sip 10-30 m ² toke ebute me h-1.5 m	m ³	30		
2	3.An/4t	F V Tuba te brinjezuara HDPE SN--8 D-600 mm ,segmenti 1	ml	24		
3	3.331	Gabiona me rrjete teli te zinkuar e gure kave 1x1x1	m ³	28		
4	An-9	Mbushje me zhavor pas mureve	m ³	15		
5	2.262/4	Shtrese betoni C-16/20 (beton mbi gabionat)	m ³	3		
6	2.19	Hedhje rrafshim mbushje dheu me krah kat-III(mbulim tubacioni me dhe)	m ³	7		
7	2.447	Kallepe per mure b/a	m ²	12		
		<i>Segmenti 2</i>				
1	3.An/4t	F V tuba te brinjezuara HDPE SN- 8 me D-600 mm	ml	56		
2	2.426/5	Prishje mure betoni	m ³	10		
3	3.59/a	Germim themel I vecuar , gropa sip 10-30 m ² toke e bute me h-1.5 m	m ³	33		
4	3.331	Gabiona me rrjete teli te zinkuar e gure kave	m ³	24		
5	2.262/4	Shtrese betoni C-16/20(mbi gabionat per rrugice pas kanalit)	m ³	1.5		
6	2.121/1	Brez b/arme C 16/20 H~ 8 m (mbi gabionat)	m ³	2		
7	An	F V Tubo HDPE SN 8 ME D-250 mm (kanali I peshkut)	ml	18		
8	An.124/3a	Germim shkemb seksion I lire me mina te vogla me eskavator 1 m ³ + trasport	m ³	10		
9	3.59/a	Germim themel I vecuar , gropa sip 10-30 m ² toke e bute me h-	m ³	13		
10	2.19	Hedhje rrafshim mbushje dheu me krah kat-III(mbulim tubacioni me dhe , tubacioni 60 mm)	m ³	15		
		Shuma A				
	B	Rikonstruksion i kanalit ujites " Kanali i mesit " Skenderbej				

Ing. Kastriot Bexheti
Projektim - Zhelimit
Mbikqyrje - Kontrollim
Ekspertizim

Handwritten signature

		Segmenti " Livadhi Bogdanit "				
1	3.17	pa hedhje .	m ³	30		
2	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	36		
3	2.19	Hedhje rrafshim mbushje dheu me krah kat-III(mbulim tubacioni me dhe)	m ³	30		
		Shuma B				
		C Segmenti Prroi " i Llapushes " "Kanali i mesit "				
1	3.17	Germim dheu ne seksion te lire me krah ne toke te bute Kad I -II pa hedhje .	m ³	50		
2	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	72		
3	An.124/3a	Germim shkemb seksion I lire me mina te vogla me eskavator 1 m ³ + trasport .	m ³	20		
4	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubacioni me dhe)	m ³	42		
		Shuma C				
		D Segmenti " Prroi i Rires " " Kanali i mesit "				
1	3.17	Germim dheu ne seksion te lire me krah ne toke te bute Kad I -II pa hedhje .	m ³	20		
2	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	18		
3	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubacioni me dhe)	m ³	30		
		Shuma D				
		E Rikonstruksionb I kanalit ujites lagje " Gega " Rrajce Sutaj Njesia Adm Rrajce Bashkia Prrenjas				
6	2.47/an	Germim shkemb mesataar me çekiq me eskavator me zinxhir .	M ³	40		
7	2.262/4	Shtrese betoni C 16/20 (betonim kanali)	m ³	22		
8	An-57	F V Tuba metalike me d-219 mm (per kalim uji terthor rruges	ml	39		
9	2.448	Kallepe per mure b/a	m ²	12		
10	2.52/2	Mur guri themel e xogel me llaç te perzier M-250	M ³	12		
11	2.258	N/shtrese zhavori (shtrim I ruges)	m ³	40		
		Shuma D				
		F Rikonstr I kanalit ujites lagjia "Rreze "Rrajce Sutaj Njesia Rrajce Bashkia Prrenjas.				
1	2.48/an	Germim shkemb I forte me eskavator me zinxhir	m ³	40		
2	2.262/4	Shtrese betoni C-16/20 (betonim kanali)	m ³	15		
3	2.52/2	Mur guri themel e xogel me llaç te perzier M-250	m ³	26.5		
4	2.262/4	Shtrese betoni C-16/20 (betonim brez betoni mbi murin e gurit)	m ³	2		
5	2.554	Tombino betoni Ø-400 mm	ml	5		
6	2.37/2a	Trasport materiale ndertimi dheu me auto deri 2 km	m ³	30		
		Shuma F				
		G Rikonstruksion I kanalit vadites lagje collaku Sutaj (Segmenti 1)				

Ing. Kastriot Begaj
 Projektim - Zbatim
 Mbikqyrje - Kolaudim
 Ekspert - Zjarrfikes

Handwritten signature

1	3.59/a	Germim themel I vecuar , gropa sip10-30m ² toke e forte me h-1.5 m	m ³	30		
2	2.262/4	Shtrese betoni C-16/20 (betonim kanali)	m ³	11		
3	2.262/4	Shtrese betoni C-16/20 (betonim dy puseta 60x60x40 cm)	m ³	2		
4	2.554	Tombino betoni Ø-400 mm	ml	6		
5	2.167	F V Hekur betoni periodik > 12 mm (Ø-12 mm mbi tombino)	ton	0.141		
6	2.262/4	Shtrese betoni C-16/20 (betonim mbi tombio per ure kalimi)	m ³	2.5		
7	2.37/2a	Trasport materiale ndertimi dheu me auto deri 2 km	m ³	30		
8	2.19	Hedhje mbushje dheu me krah kad--III(mbulim tombino me dhe)	m ³	3		
Shuma G						
H Rikonstruksion I kanalit vadites lagje collaku Sutaj (Segmenti 2)						
1	2.1a	Germim dheu me krah e trasport me karroce dore 10 ml Kad IV	m ³	10		
2	3.An/1t	F V Tubo te brinjezuar HDPE SN- 8 ME D-315 MM	ml	18		
3	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe	m ³	10		
4	2.262/4	Shtrese betoni C-16/20 (betonim dy puseta 60x60x40 cm)	m ³	2		
Shuma H						
I Rikonstruksion kanali ujites lagje Collaku Rrajce Fushe (segmenti 1)						
1	2.1a	Germim dheu me krah e trasport me karroce dore 10 ml Kad IV	M ³	10		
2	2.262/4	Shtrese betoni C-16/20 (betonim anesor I murit me tr 10 cm)	m ³	4.5		
3	2.262/4	Shtrese betoni C-16/20 (betonim kanali)	m ³	8.5		
4	2.1/a	Germim dheu me krah e trasport me karroce dore 10 ml Kad IV	m ³	3		
5	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	6		
6	2.37/2a	Trasport materiale ndertimi dheu me auto deri 2 km	m ³	20		
Shuma I						
K Rikonstruksion kanali ujites lagje Collaku Rrajce Fushe (segmenti 2) vazhdim						
1	3.2	Prerje e bimeve te vogla me Ø 10 cm	m ²	200		
2	2.1a	Germim dheu me krah e trasport me karroce dore 10 ml Kad IV	m ³	60		
3	2.262/4	Shtrese betoni C-16/20 (betonim kanali)	m ³	19.5		
4	2.166	F V Hekur beton me Ø 6- 10 mm (Ø 8 mm) per betonim kanali .	ton	0.268		
5	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	18		
6						
7	An-8	Mbushje me cakel pas mureve	m ³	25		
8						
9						

Ing. Kastriot Begaj
 Projektim - Zbatim
 Mbikqyrje - Kolaudim
 Ekspert - Zharrfikes




10	3.68/b	Germim themel e (gropa) sip 10-30 m ² shkemb I bute me h=2.5 m me makineri.	m ³	3		
11	2.262/4	Shtrese betoni C-16/20 (betonim muri prite betoni)	m ³	2		
12	2.167	FV Hekur beton periodik me Ø > 10 mm Ø 12 mm per murin e betonit	ton	0.85		
13						
		Shuma K				
	L	Rikonstruksion kanali ujites lokal " Alliu " Arat e " Faces " Poçivall Rrajce Fushe Njesia Rrajce				
1	3.2	Prerje e bimeve te vogla me Ø 10 cm	m ²	200		
2	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ²	m ³	50		
3	2.262/4	Shtrese betoni C-16/20 (betonim kanali ujites me gjatesi 230 ml)	m ³	25.3		
4	2.262/4	Shtrese betoni C-16/20 (betonim dy puseta ujembledhese me permasa 0.60 x0.60x.40 cm)	m ³	1		
5	3.An/1t	F V Tubo te brinjezuara HDPE SN- 8 ME D-315 mm	ml	12		
6	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	3		
7	2.166	F V Hekur beton me Ø 6- 10 mm (Ø 10 mm) per betonim mbi tubot HDPE SN -8 D-315 mm	ton	0.186		
8	2.262/4	Shtrese betoni C-16/20 (betonim mbi tubot HDPE SN--8 me D-315 mm me tr betonit 20 cm)	m ³	4		
9	2.448	Kallepe per mure b/a	m ²	40		
		Shuma L				
	M	Tek Tubiku Rrajce Fushe Njesia Adm Rrajce Bashkia Prrenjas				
1	3.An/1t	F V Tubo te brinjezuara HDPE SN- 8 ME D-315 mm	ml	44		
		Shuma M				
	N	Rikonstruksion I kanalit ujites Lagje ' COKA ' Rrajce Fushe ,Njesia Adm Rrajce Bashkia Prrenjas.				
1	3.2	Prerje e bimeve te vogla me Ø 10 cm	m ²	200		
2	2.426/3	Prishje shtresa betoni	m ³	5		
3	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ²	m ³	31		
4	3.59/a	Germim themel I vecuar , gropa sip10-30m ² toke e forte me h-1.5 m	m ³	13		
5	2.262/4	Shtrese betoni C-16/20 (betonim kanali me gjatesi 185 ml	m ³	21		
6	2.37/2a	Trasport materiale ndertimi dheu me auto deri 2 km	m ³	50		
		Shuma N				
	O	Rukonstruksion i kanalit ujites tek " Ura e Dashit Rrajce Fushe "Njesia Adm.Rrajce Bashkia Prrenjas				
1	3.59/a	Germim themel I vecuar , gropa sip10-30m ² toke e forte me h-1.5 m	m ³	20		

Ing. Kastriot Begaj
 Projektim - Zbatim
 Mbikqyrje - Kolaudim
 Ekspert - Zjarrfiks

Cherref

2	2.426/3	Prishje shtresa betoni	m ³	5		
3	2.262/4	Shtrese betoni C-16/20 (betonim kanali me gjatesi 78 ml	m ³	8.5		
4	2.37/2a	Trasport materiale ndertimi dheu me auto deri 2 km	m ³	25		
Shuma O						
P Rikonstruksion I kanalit ujites " Lëmi i Hanit " Skenderbe Njesia Adm, Rrajce Bashkia Prrrenjas.						
1	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ²	m ³	10		
2	An	F V Tubo te brinjezuar HDPE SN- 8 me D-250 mm	ml	60		
3	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	10		
4	2.262/4	Shtrese betoni C-16/20 (betonim pusete 1(nje)pusete me permasa 0.60 x 0.60 x 0.40 cm	m ³	0.5		
Shuma P						
R Rikonstruksion I kanalit ujites Fshati Kotodesh tek "TYLBJA " Njesia Adm.Rrajce Bashkia Prrrenjas.						
1	3.An/3 t	F V Tuba te brinjezuar HDPE SN--8 D-500 mm ,segmenti 1	ml	30		
2	2.19	Hedhje mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	15		
3	2.262/4	Shtrese betoni C-16/20 (betonim pusete 1 pusete me permasa 0.60 x 0.60 x 0.40 cm	m ³	0.3		
Shuma R						
Q Rikonstruksion I kanalit ujites " Mulliri Belbes" Qukes Shkumbin " Njesia Adm Qukes Bashkia Prrrenjas.						
1	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ²	m ³	31		
2	2.262/4	Shtrese betoni C-16/20 (betonim kanali me permasa me permasa 0.60 x 0.60 x 0.40 cm	m ³	22.5		
3	2.37/2a	Trasport materiale ndertimi dheu me auto deri 2 km	m ³	31		
Shuma "Q "						
S Rikonstruksion kanale ujites fshati Karkavec Njesia Adm . Qukes Bashkia Prrrenjas						
	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ² (300 ml vetem pastrim me permasa 0.30x 0.30 cm)	m ³	40		
	3.59/c	Germim themel I vecuar , gropa sip10-30m ² toke e forte me h-1.5 m(52 ml per betonim kanali me permasa 0.30 x0.30 cm	m ³	10		
	2.262/4	Shtrese betoni C-16/20 (betonim kanali me permasa 0.30 x 0.30 cm (me L--62 ML)	m ³	7		
	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	66		
	2.19	Hedhje mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	60		
	2.262/4	Shtrese betoni C-16/20 (betonim mbi tubat per kalime)	m ³	12		
Shuma S pa t v sh						

Ing. Kastriot Begaj
 Projektim - Zbatim
 Mëkqyrje - Kolaudim
 Ekspert - Zierrikes

(Signature)

T		Rikonstruksion I kanalit ujtes " Radigoz "Njesia Adm Stravaj Bashkia Prrenjas.				
1	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ² (70 ml pastrim per vndosjen e tubacioneve)	m ³	20		
2	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	66		
3	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	20		
4	3.59/a	Germim themel I vecuar , gropa sip10-30m ² toke e forte me h-1.5 m(Hapje themeli per gabionat me permasa 1.0 x 0.60 cm)	m ³	10		
5	3.331	Gabiona me rrjete teli te zinkuar e gure kave 1x1x1	m ³	30		
6	2.121/1	Brez b/arme C 16/20 H~ 8 m (mbi gabionat)	m ³	2.5		
7	An-9	Mbushje me zhavor pas mureve	m ³	15		
		Shuma T				
U		Rikonstruksion I kanalit ujtes Nr 1 Qukes Shkumbin Njesia Adm.Qukes Bashkia Prrenjas				
1	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ² (20 ml pastrim per vndosjen e tubacioneve d- 500 mm)	m ³	9		
2	3.An/3 t	F V Tuba te brinjezuar HDPE SN--8 D-500 mm ,segmenti	ml	18		
3	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	9		
		Shuma U				
V		Rikonstruksion I kanalit ujtes nr2 Qukes Shkumbin Njesia Adm Qukes Bashkia Prrenjas				
1	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ² (13 ml pastrim per vndosjen e tubacioneve d- 400 mm)	m ³	7		
2	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	12		
3	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	7		
		Shuma V				
X		Rikonstruksion I kanalit 2 perballe Tunelit Bushtrice Qukes shkumbin Njesia Adm Qukes Bashkia Prrenjas				
1	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ² (25 ml pastrim per vndosjen e tubacioneve d- 400 mm)	m ³	13		
2	3.An/2t	F V Tuba te brinjezuar HDPE SN--8 D-400 mm	ml	24		
3	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	12		
		Shuma X				
Y		Rikonstruksion I kanalit ujtes nr 2 Qukes Shkumbin vazhdim Njesia Adm Qukes Bashkia Prrenjas				
1	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ² (25 ml pastrim per vndosjen e tubacioneve d- 400 mm)	m ³	20		

Ing. Kastriot Begaj
 Projektim - Zbatim
 Mëkqyrje - Kolaudim
 Ekspert - Zërfikues

Handwritten signature

2	An.124/3a	Germim shkambi mesatar seksion I lire me mina te vogla me eskavator 1m ³ + trasport	m ³	39		
3	3.An/2t	F V Tuba te brinjezuara HDPE SN--8 D-400 mm	ml	24		
4	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	20		
5	2.262/4	Shtrese betoni C-16/20 (betonim I hyrjes te ujit ne tubacione)	m ³	2		
		Shuma Y				
	Z	Rikonstrukcion I kanalit ujites ne vendin quajtur " PARASPUAR" Rrajce Fushe ,Njesia Adm .Rrajce Bashkia Prrenjas.				
1	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ² (35 ml pastrim per vendosjen e tubacioneve d- 315 mm)	m ³	8		
2	3.An/1t	F V Tubo te brinjezuara HDPE SN- 8 ME D-315 mm	ml	36		
3	2.19	Hedhje mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	8		
4	2.262/4	Shtrese betoni C-16/20 (betonim mbi tubot HPDE SN-8 me d-315 mm)	m ³	3.2		
5	2.262/4	Shtrese betoni C-16/20 (betonim tre puseta ujembledhese me permasa 0.60 x0.60x.40 cm)	m ³	1.6		
6	2.166	F V Hekur beton me Ø 6- 10 mm (Ø 10 mm) per betonim mbi tubot HDPE SN -8 D-315 mm	ton	0.25		
		Shuma Z				
	ZH	Rikonstrukcion kanali ujites Qukes tek Heci Njesia Qukes Bashkia Prrenjas				
1	249.1/1j	F V Tuba e rakorderi ujesjells PE d-160 mm t-17.9 mm PN20	ml	317		
2	3.44/1	Germim kanalesh ne toke te bute me krah , me seksion deri 0.75 m ² (13 ml pastrim per vendosjen e tubacioneve d- 400 mm)	m ³	96		
3	2.19	Hedhje rrafshim mbushje dheu me krah kad--III(mbulim tubo me dhe)	m ³	96.38		
		Shuma Z pa t v sh				
		Shuma A+B+C+D+E+F+G+H+I+K+L +M +N + O+ P + R+Q+ S+ T+ U + V+ X +Y+Z+ZH pa T V S H				
		TVSH	%	20		
		Shuma Totale me T V S H				

PROJEKTUESI

Ing. Kastriot Bekaj (Kastriot Bekaj)

Projektim - Zbatim
Mhikqyrje - Kolaudim
Ekspert - Zjarrfshes

(Signature)