

TABELE PERMBLEDHESE (Permiresimi banesave egzistuese per komunitetet e varfera dhe te pa favorizuara)

Nr.	Emer & Mbiemer	Propozimi
1	ALI AGAJ + ARTAN AGAJ	Objekt dy familjar
2	THOMA AGARAJ	Objekt nje familjar (1+1)
3	MENO KOJDHELAI	Rikon. objekt ekzistues
4	SERVET ISLAMAJ	Objekt nje familjar (1+1)
5	RIZA MUSTA	Rik. Ob. Ekz.
6	BASHKIME SALAJ	Rik. Ob. Ekz.
7	DEMIR HALILAJ	Rik. Ob. Ekz.
8	PASHO FILAJ	Rik. Ob. Ekz.
9	AFRIM ISLAMAJ	Rik. Ob. Ekz.
10	LEONARD XHELAI	Rik. Ob. Ekz.
11	RAJMONDA KACANI	Rik. Ob. Ekz.
12	VALENTINA BOMBAJ	Rik. Ob. Ekz.
13	ALUSH DALIPAJ	Rik. Ob. Ekz.
14	PANDELI HAMETAJ	Rik. Ob. Ekz.
15	ZANI KAHARAJ	Rik. Ob. Ekz.
16	JETNOR MUCAJ	Rik. Ob. Ekz.
17	TEFERI KARABINA	Rikon. objekt ekzistues
	SHUMA PA TVSH	Leke
	TVSH 20 %	Leke
	SHUMA PA TVSH	Leke

Pergatiti:

ING. Klevis BEDINAJ

ARK. Tea HAXHIAJ

TOP. Agim VEIZAJ

MIRATOI

Pellumb BINAJ



PREVENTIVI I PUNIMEVE (FONDI I EMERGJENCES)

OBJEKTI: "BANESE 1 KAT, DY FAMILJARE", Z. ARTAN AGAJ DHE Z. ALI AGAJ, RROMES

Nr.	Nr. An.	Pershkrimi i punimeve	Njesia	Sasia
A. PUNIME PRISHJE E PASTRIM I SHESHIT TE NDERTIMIT TE BANESE				
1	2.426/1	Prishje mur tulle/guri me pastrim, perfshi gjithë elementet e tjere te objektit ekzistues	m ³	92
SHUMA A			Leke	
B. PUNIME NDERTIMI				
1. PUNIME DHEU				
1	2.28+2.37/5a	Germim dheu me makineri per themele etj + transport 5km	m ³	38
2	2.258	Nenshtresa e shtresa zhavori	m ³	40
Shuma 1			Leke	
2. PUNIME BETONI DHE BETONI TE ARMUAR				
1	2.262/3	Shtrese betoni C 12/15	m ³	3.0
2	2.116/1	Trare themeli monolit b/a C - 16/20	m ³	30
3	2.117/1	Kollona, parete b/arme dhe shkalle monolite C - 16/20, h ~ 4 m	m ³	3.2
4	2.119/1	Trare e arkitrare b/a C - 16/20, h ~ 4 m	m ³	7
5	2.262/4	Shtrese betoni C 16/20	m ³	9
6	2.166	F.V hekur betoni periodik me d=6-10mm	ton	0.8
7	2.167	F.V hekur betoni periodik me d >10mm	ton	2.2
Shuma 2			Leke	
3. PUNIME MURATURE DHE TAVANI				
1	2.70/2	Mur me tulle te lehtesuara deri 3m me llaç perzier M25	m ³	21
2	2.108/a	Ndetim muri me knauf t=10cm me dy shtresa	m ²	51
Shuma 3			Leke	
4. PUNIME ÇATIE OSE TARACE				
1	2.219	Çati vendi zakonshme HD-8m, mbuluar, tjegulla marseleze	m ²	115
2	2.209	Ulluk shkarkimi vertikal Ø 100 mm	ml	21
3	2.212	Ulluk shkarkimi horizontal 33 cm	ml	46
4	2.206	Kasete shkarkimi	cope	7
5	An. 2	Membranc per izolimin e kondesatit dhe avujve e pozicionuar poshte tjcggullave	m ²	115
Shuma 4			Leke	
5. PUNIME SHITRESA DHE HIDROIZOLIMI				
1	2.262/3	Shtrese betoni C 12/15, per nivelim	m ³	8.6
2	2.267/b	Shtrese me pllaka grez importi	m ²	72
3	2.326	Veshje me pllake majolike	m ²	18.55
4	2.273/5	Shkalle, davancale dhe pragje dritare + dyer mermeri t=3cm	m ²	28
5	2.324a	Plintuse pllake grez	ml	78
Shuma 5			Leke	
8. PUNIME BOJATISJE				
1	2.404/1	Lycrje me boje hidroplastike importi cilesi e I-re	m ²	520
Shuma 8			Leke	
SHUMA B {1+8}			Leke	
C. PUNIME ELEKTRIKE				
1	2.490/f	F.V Kasete plastike KE me 36 modular (vende)	cope	1
2	2.490/1	F.V Automat termo/el.manj. diferencial 2P 220V, 32A, dl=0.03A	cope	1
3	2. a-120	Llampe sinjalizimi 220V; 1.2w	cope	1
4	2. a-108	Automat magneto-termik 380V, 25A, 4P	cope	14
5	2.485/d	F.V. Prize "Schucko" 16A dy module te bardha	cope	20
6	2.487/d	F.V kuti suport pllaket 4 modular Gevis	cope	20
7	480/5	Tub PVC fleksibel vetshuares dj=32m/m	ml	30
8	480/3	Tub PVC fleksibel vetshuares dj=25m/m	ml	240
9	480/2	Tub PVC fleksibel vetshuares dj=20m/m	ml	300
10	2.481/1	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*1.5 mm ²	ml	980
11	2.481/2	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*2.5 mm ²	ml	840
12	2.481/3	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*4 mm ²	ml	240
13	2.481/4	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*6 mm ²	ml	20
14	Ref. 2.481/5	F.V. Kabell FG7OR, S=5*10mm ² (Furnizim Kuadro)	ml	60
15	2.485/2	F.V. Frut çeles 1 polarc, 1modular, 10A, 250V	cope	12
16	2.487	F.V Kutiderivacioni plastike	cope	8
17	2. a-130	Ndricues tip plafoniere, me llampe fluoreshente 40w,	cope	12
SHUMA C			Leke	
E. PUNIME HIDRAULIKE				
1. SISTEMI I SHKARKIMEVE				
1	2.513	F.V pilete dyshemeje Ø 30 mm	cope	2

PREVENTIVI I PUNIMEVE (FONDI I EMERGJENCES)

OBJEKTI: "BANESË 1 KAT, DY FAMILJARE", Z. ARTAN AGAJ DHE Z. ALI AGAJ, RROMES

Nr.	Nr. An.	Pershkrimi i punimeve	Njesia	Sasia
2	2.501	F.V WC allafrenga importi	cope	2
3	2.495	F.V lavaman porcelani importi me mishclator	cope	2
4	An - 18	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	1
5	2.519	Tub kanalizimi pvc Ø 90 mm	ml	30
Shuma 1			Leke	
2. SISTEMI I FURNIZIMIT ME UJE				
1	2.491/1f	F.V Tuba e rakorderi ujesjellesi PE d=63mm, t = 7.1 mm, PN 20	ml	30
2	An 153	F.V Tuba e rakorderi PPR Pn 16 f = 50 mm	ml	40
3	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10	ml	20
4	2.494/2	F.V saracineska bronzi Ø 1 " = 25 mm	cope	4
Shuma 2			Leke	
SHUMA E (1+2)			Leke	
TOTAL (A+B+C+D+E)			Leke	
FONDI REZERVE 3 %			Leke	
SHUMA NETO (Leke)				
T.V.SH 20% (Leke)				
SHUMA TOTALE (Leke)				

Pergatiti:

ING. Klevis BEDINAJ

ARK. Tea HAXHIAJ

TOP. Agim VEIZAJ

MIRATOI

Pellumb BINAJ



PREVENTIVI I PUNIMEVE (FONDI I EMERGJENCES)

OBJEKTI: "BANESË 1 KAT, NJE FAMILJARE", Z. THOMA AGARAJ, KROPISHT

Nr.	Nr. An.	Pershkrimi i punimeve	Njesia	Sasia
6	2.487/d	F.V kuti suport pllaket 4 modular Gevis	cope	12
7	480/5	Tub PVC fleksibel vetshuares dj=32m/m	ml	20
8	480/3	Tub PVC fleksibel vetshuares dj=25m/m	ml	140
9	480/2	Tub PVC fleksibel vetshuares dj=20m/m	ml	150
10	2.481/1	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*1.5 mm ²	ml	480
11	2.481/2	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*2.5 mm ²	ml	440
12	2.481/3	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*4 mm ²	ml	130
13	2.481/4	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*6 mm ²	ml	20
14	Ref. 2.481/5	F.V. Kabell FG7OR, S=5*10mm ² (Furnizim Kuadro)	ml	60
15	2.485/2	F.V. Frut celes 1 polare, 1modular, 10A, 250V	cope	6
16	2.487	F.V Kutiderivacioni plastike	cope	4
17	2. a-130	Ndricues tip plafoniere, me llampe fluoreshente 40w,	cope	6
		SHUMA C	Leke	
E. PUNIME HIDRAULIKE				
1. SISTEMI I SHKARKIMEVE				
1	2.513	F.V pilete dyshemeje Ø 30 mm	cope	1
2	2.501	F.V WC allafrenga importi	cope	1
3	2.495	F.V lavaman porcelani importi me mishelator	cope	1
4	An - 18	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	1
5	2.519	Tub kanalizimi pvc Ø 90 mm	ml	30
		Shuma 1	Leke	
2. SISTEMI I FURNIZIMIT ME UJE				
1	2.491/1f	F.V Tuba e rakorderi ujesjellesi PE d=63mm, t = 7.1 mm, PN 20	ml	20
2	An 153	F.V Tuba e rakorderi PPR Pn 16 f = 50 mm	ml	25
3	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10	ml	12
4	2.494/2	F.V saracineska bronzi Ø 1 " = 25 mm	cope	2
		Shuma 2	Leke	
		SHUMA E (1+2)	Leke	
		TOTAL (A+B+C+D+E)	Leke	
		FONDI REZERVE 3 %	Leke	
		SHUMA NETO (Leke)		
		T.V.SH 20% (Leke)		
		SHUMA TOTALE (Leke)		

Pergatiti:

ING. Klevis BEDINAJ

ARK. Tea HAXHIAJ

TOP. Agim VEIZAJ

MIRATOI

Pellumb BINAJ



PREVENTIVI I PUNIMEVE (FONDI I EMERGJENCES)

OBJEKTI: "RIKONSTRUKSION BANESË EKZISTUESE 1 KAT", Z. MENO KOJDHELAJ, TREBLOVE

Nr.	Nr. An.	Pershkrimi i punimeve	Njesia	Sasia
E. PUNIME HIDRAULIKE				
1. SISTEMI I SHKARKIMEVE				
1	2.513	F.V pilete dyshemcje Ø 30 mm	cope	1
2	2.501	F.V WC allafrenga importi	cope	1
3	2.495	F.V lavaman porcelani importi me mishelator	cope	1
4	An - 18	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	1
5	2.519	Tub kanalizimi pvc Ø 90 mm	ml	30
Shuma 1			Leke	
2. SISTEMI I FURNIZIMIT ME UJE				
1	2.491/1f	F.V Tuba e rakorderi ujesjellesi PE d=63mm, t = 7.1 mm, PN 20	ml	20
2	An 153	F.V Tuba e rakorderi PPR Pn 16 f = 50 mm	ml	25
3	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10	ml	12
4	2.494/2	F.V saracineska bronzi Ø 1 " = 25 mm	cope	2
Shuma 2			Leke	
SHUMA E (1+2)			Leke	
TOTAL (A+B+C+D+E)			Leke	
FONDI REZERVE 3 %			Leke	
SHUMA NETO (Leke)				
T.V.SH 20% (Leke)				
SHUMA TOTALE (Leke)				

Pergatiti:

ING. Klevis BEDINAJ

ARK. Tea HAXHIAJ

TOP. Agim VEIZAJ

MIRATOI

Pellumb BINAJ



PREVENTIVI I PUNIMEVE (FONDI I EMERGJENCES)

OBJEKTI: "BANESË 1 KAT, NJE FAMILJARE", Z. SERVET ISLAMAJ, TREBLOVE

Nr.	Nr. An.	Pershkrimi i punimeve	Njesia	Sasia
A. PUNIME PRISHJE E NGRITJE KANTIERI				
3	2.426/1	Prishje mur tulle/guri me pastrim, perfshi gjithë elementet e tjere te objektit ekzistues	m ³	45
SHUMA A			Leke	
B. PUNIME NDERTIMI				
1. PUNIME DHEU				
1	2.28+2.37/5a	Germim dheu me makineri per themele etj + transport 5km	m ³	30
2	2.258	Nenshtresa e shtresa zhavori	m ³	24
Shuma 1			Leke	
2. PUNIME BETONI DHE BETONI TE ARMUAR				
1	2.262/3	Shtrese betoni C 12/15	m ³	2.4
2	2.116/1	Trare themeli monolit b/a C - 16/20	m ³	22
3	2.117/1	Kollona, parcte b/arme dhe shkalle monolite C - 16/20, h - 4 m	m ³	2.5
4	2.119/1	Trare e arkitrare b/a C - 16/20, h - 4 m	m ³	4
5	2.262/4	Shtrese betoni C 16/20	m ³	5
6	2.166	F.V hekur betoni periodik me d=6-10mm	ton	0.5
7	2.167	F.V hekur betoni periodik me d >10mm	ton	1.6
Shuma 2			Leke	
3. PUNIME MURATURE DHE TAVANI				
1	2.70/2	Mur me tulle te lehtesuara deri 3m me llaç perzier M25	m ³	13
2	2.108/a	Ndetim muri me knauf t=10cm me dy shtresa	m ²	29
Shuma 3			Leke	
4. PUNIME ÇATIE OSE TARACE				
1	2.219	Çati vendi zakonshme HD-8m, mbuluar, tjegulla marseleze	m ²	69
2	2.209	Ulluk shkarkimi vertikal Ø 100 mm	ml	12
3	2.212	Ulluk shkarkimi horizontal 33 cm	ml	33
4	2.206	Kascte shkarkimi	cope	4
5	An. 2	Membrane per izolimin e kondesatit dhe avujve e pozicionuar poshte tjegullave	m ²	69
Shuma 4			Leke	
5. PUNIME SHITRESA DHE HIDROIZOLIMI				
1	2.262/3	Shtrese betoni C 12/15, per nivelim	m ³	5.0
2	2.267/b	Shtrese me pllake grez importi	m ²	43
3	2.326	Vcshje me pllake majolike	m ²	15
4	2.273/5	Shkalle, davancale dhe pragje dritare + dyer mermeri t=3cm	m ²	17
5	2.324a	Plintuse pllake grez	ml	39
Shuma 5			Leke	
6. PUNIME SUVATIMI, TAVANI DHE VESHJE				
1	2.310	Suva brenda mur tulle h=4m me krah, llaç perzier M 25	m ²	110
2	2.297/a	Tavan me kartonxhes	m ²	43
3	2.358/c	Veshje muri brenda me polisterol te thjeshte t=5cm + rrjete + suva.	m ²	70.33
Shuma 6			Leke	
SHUMA B {1+8}			Leke	

PREVENTIVI I PUNIMEVE (FONDI I EMERGJENCES)

OBJEKTI: "BANESË 1 KAT, NJE FAMILJARE", Z. SERVET ISLAMAJ, TREBLOVE

Nr.	Nr. An.	Pershkrimi i punimeve	Njesia	Sasia
C. PUNIME ELEKTRIKE				
1	2.490/f	F.V Kasete plastike KE me 36 modular (vende)	cope	1
2	2.490/1	F.V Automat termo/el.manj. diferencial 2P 220V, 32A, dl=0.03A	cope	1
3	2. a-120	Llampe sinjalizimi 220V;1.2w	cope	1
4	2. a-108	Automat magneto-termik 380V,25A, 4P	cope	8
5	2.485/d	F.V. Prizc "Schucko" 16A dy module te bardha	cope	12
6	2.487/d	F.V kuti suport pllaket 4 modular Gevis	cope	12
7	480/5	Tub PVC fleksibel vetshuares dj=32m/m	ml	20
8	480/3	Tub PVC fleksibel vetshuares dj=25m/m	ml	140
9	480/2	Tub PVC fleksibel vetshuares dj=20m/m	ml	150
10	2.481/1	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*1.5 mm ²	ml	480
11	2.481/2	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*2.5 mm ²	ml	440
12	2.481/3	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*4 mm ²	ml	130
13	2.481/4	F.V. Percjelles T.U. izolim PVC, Tip NO7V K, S=1*6 mm ²	ml	20
14	Ref. 2.481/5	F.V. KABEL FG70R, S=5*10mm ² (Furnizim Kuadro)	ml	60
15	2.485/2	F.V. Frut çeles 1 polare, 1modular, 10A, 250V	cope	6
16	2.487	F.V Kutiderivacioni plastike	cope	4
17	2. a-130	Ndricues tip plafoniere, me llampe fluoreshente 40w,	cope	6
SHUMA C			Leke	
E. PUNIME HIDRAULIKE				
1. SISTEMI I SHKARKIMEVE				
1	2.513	F.V pilete dyshemeje Ø 30 mm	cope	1
2	2.501	F.V WC allafrenga importi	cope	1
3	2.495	F.V lavaman porcelani importi me mishelator	cope	1
4	An - 18	Pusetc shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	1
5	2.519	Tub kanalizimi pvc Ø 90 mm	ml	30
Shuma 1			Leke	
2. SISTEMI I FURNIZIMIT ME UJE				
1	2.491/1f	F.V Tuba e rakorderi ujesjellesi PE d=63mm, t = 7.1 mm, PN 20	ml	20
2	An 153	F.V Tuba e rakorderi PPR Pn 16 f = 50 mm	ml	25
3	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10	ml	12
4	2.494/2	F.V saracineska bronzi Ø 1" = 25 mm	cope	2
Shuma 2			Leke	
SHUMA E (1+2)			Leke	
TOTAL (A+B+C+D+E)			Leke	
FONDI REZERVE 3 %			Leke	
SHUMA NETO (Leke)				
T.V.SH 20% (Leke)				
SHUMA TOTALE (Leke)				

Pergatiti:

ING. Klevis BEDINAJ

ARK. Tea HAXHIAJ

TOP. Agim VEIZAJ



MIRATOI

Pellumb BINAJ

