

2  
1

## PREVENTIV PUNIMESH

Objekti: ASFALTIM RRUGE TE BRENDESHME KOCUL, BASHKIA SELENICE

Investitor: BASHKIA SELENICE

| Nr.   | Analize   | Emertimi i Punimeve  | Njesia         | Sasia                          |
|---|-----------|--|----------------|--------------------------------|
| <b>A- PUNIME NDERTIMI DHE SISTEMIMI TE RRUGES</b> |           |  |                |                                |
| <b>A Punime Germimi dhe Mbushje ne Rruge</b>      |           |  |                |                                |
| 1   | 3.179     | Ndertim kasonete ne toke mesatare  | m <sup>2</sup> | 10,250                         |
| 2   | 3.158/5a  | Transport dheu me auto deri ne 5 km  | m <sup>3</sup> | 3,075                          |
| <b>B Punime Shtresa rrugore</b>                   |           |  |                |                                |
| 1   | 3.211     | Shtrese cakelli mbeturine kave shtresa t=20cm, perhapur e ngjeshur me makineri   | m <sup>2</sup> | 20,500.0                       |
| 2   | 3.229/2   | Shtrese binderi me zall lavatrice,6cm,me makineri  | m <sup>2</sup> | 7,175.0                        |
| 3   | 3.233/1   | Shtrese asfaltobetoni me zall lavatrice,4cm,me mak   | m <sup>2</sup> | 7,175.0                        |
| 4   | 3.212/b   | Shtrese stabilizant t=10cm per bankinat + rruga  | m <sup>2</sup> | 13,340.0                       |
| <b>C Vepra arti te vogla + Kanale anesore</b>     |           |  |                |                                |
| 1   | 3.87/a    | Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke | m <sup>3</sup> | 548.0                          |
| 2   | An.164/1a | Mbushje me cakelli e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri                                      | m <sup>3</sup> | 35.0                           |
| 3   | 3.363     | Tombino me tuba betoni Ø 400, mbi shtrese betoni   | m              | 15.0                           |
| 4   | 3.245/1   | Struktura te holla monolite betoni C 25/30   | m <sup>3</sup> | 8.4                            |
| 5   | 3.287     | F V hekur betoni i zakonshem Ø 6 ~ 10mm  | ton            | 0.8                            |
| <b>D Vijezi me dhe sinjalistika</b>               |           |  |                |                                |
|   | An125     | Vijezi shirita gjatesor dhe anesor me gjeresi 12 cm, Termoplastike (sprajt)  | ml             | 3,980.0                        |
|   | An145     | Boje termoplastike (sprajt)  | m <sup>2</sup> | 16.0                           |
|   | An158     | FV tabela te ndryshme rrugore D=60cm   | cope           | 8.0                            |
|   |           |  |                | SHUMA I=(A+B)                  |
|   |           |  |                | FONDI REZERVE (2) = (1) * 0 %  |
|   |           |  |                | SHUMA (3) = (1) + (2)          |
|   |           |  |                | T.V.SH. (4) = (1) * 20 %       |
|   |           |  |                | SHUMA E PERGJITHSHME (3) + (4) |

Projektues : C.E.C GROUP shpk

Pergatiti : ~~Andren Mbrice~~

