

PREVENTIV ZBATIMI

OBJEKTI:

PROJEKT ZBATIMI SISTEMIM ASFALTIM I RRUGES SOPOT LOTI II , NJESIA ADMINISTRATIVE ZERQAN ,
BASHKIA BULQIZE

Gjatesia L = 786 ml

Nr.	Nr. Analize	Emertimi i punimeve	Njesia	Sasia	Cmimi	Vlera
1 PUNIME NE RRUGE						
1	3.2	Prerje bime te vogla deri Φ 10cm,L=1475m,B=10m	m ²	62		-
2	3.160/a	Germim e transport dheu kat III-te me skreper, L=100m dhe V=6~6.5m ³	m ³	1,115		-
3	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	197		-
4	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	337		-
Shuma 1						-
2 PUNIME SHITRESASH NE RRUGE						
1	An-8	Mbushje me cakell t = 15 cm	m ³	486		-
2	3.47/1b	Shtrese me material rrethanor per bankine t=20cm	m ³	160		-
3	3.212/b	Shtrese stabilizant t=10cm	m ²	3,240		-
4	3.229/1	Shtrese binderi me zall lavatrice,5cm,me makineri	m ²	3,240		-
5	3.233/1	Shtrese asfaltbetoni me zall lavatrice,4cm,me mak	m ²	3,240		-
6	An151	Vizime me boje bikomponente	m ²	192		-
7	An155	F V tabela rrugore te ndryshme D=90cm	cope	6		-
Shuma 2						-
3 PUNIMET E VEPRAVE TE ARTIT						
A Kalim me tub celiku Φ 323.8/3.6 mm						
1	3.87/a	Germim dheu me ekskavator goma 0.15 m ³ , ne themele, toke zak, kategoria III, me shkarkim ne toke	m ³	8		-
2	3.243	Struktura monolite betoni C 16/20 + shtres kanali (Beton per Hyrje dalje tub celiku)	m ³	12.0		-
3	2.a60/1	F.V. Tub celiku Φ 355.2/3.6 mm (P.s=31.251 kg/ml),L= 14 m	kg	438		-
4	An-8	Mbushje me cakell	m ³	1		-
5	An3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret	ml	65		-
Shuma A						-
G Ndertim Mure Butobetoni C 12/15 20% gur						
1	3.87/a	Germim dheu me ekskavator goma 0.35~0.40m ³ , ne themele, toke zak, kat III, me shkarkim ne toke	m ³	75		-
2	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal)	m ³	26.0		-
3	3.237	Struktura monolite b/betoni C 12/15 me 20% gur	m ³	35		-
4	2.258	Nenshtrese zhavori	m ³	6		-
Shuma G						-
SHUMA						-
T.V.SH 20%						-
SHUMA TOTALE						-

V.O . Cmimet jane bere ne baze te vkm 619 date 15.07.2015

PREVENTIVUES:
Ing.Hajredin MURGU