

**BASHKIA MAT****MIRATOHET
KRYETARI****AGRON MALAJ****PREVENTIVI PARAPRAK I PUNIMEVE****OBJEKTI: STUDIM - PROJEKTIM
 "RIKUALIFIKIM URBAN I BLOKUT LAGJA E RE" (PJESOR)****FAZA: PROJEKT ZBATIM (L= 840 ml total, 190 ml me 5m gjeresi, 170 ml me 4 ml gjerese, tjetra 3 ml) pa trotuare**

PUNIME NE RRUGE						
Nr.	Analize	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
A-1. Punime Prishjeje dhe Çmontimi						
1	2.426/5	Prishje struktura betoni + transport	m ³	35		
2	2.426/2	Prishje mur tulle, guri ose bloqe + transport	m ³	18		
3	Analize	Spostim Linje Tensioni (nentokesore)	ml	65		
4	Analize	Spostim Linje Tensioni (ajrore) perfshi shtyllat	ml	185		
Shuma A-1						
A-2. Punime ne Trup te Ruges						
1	3.89/b +3.158/5a	Germim me makineri , toke zakonshme + transport 5km	m ³	4,520		
2	3.45/1+3.158/ 5a	Germim me krahe, toke e zakonshme + transport 5km	m ³	85		
3	3.198	Cilindrim kasonete me rul	m ²	4,250		
4	Man.3 An	Prerje asfalti ekzistues	ml	25		
5	3.210	Shtrese çakelli , t=15cm, perhapur e ngjeshur makineri	m ²	2,145		
6	3.211	Shtrese çakelli, t=20cm, perhapur e ngjeshur makineri	m ²	1,854		
7	3.212/b	Shtrese stabilizanti 10cm	m ²	2,294		
8	3.212/b	Shtrese stabilizanti 15cm	m ²	950		
9	3.229/2	Shtrese binderi 6cm	m ²	950		
10	3.226/1	Shtrese asfaltobetoni 4cm	m ²	950		
11	3.222/1	Shtrese binderi 5cm	m ²	2,294		
12	3.224/1	Shtrese asfaltobetoni 3cm	m ²	2,294		
Shuma A-2						
A-3. Punime ne Bordura, Mure, Kuneta,						
1	3.89/b +3.158/5a	Germim me makineri , toke zakonshme + transport 5km	m ³	320		
2	3.45/1+3.158/ 5a	Germim me krahe, toke e zakonshme + transport 5km	m ³	20		
3	Analize	Shtrese zhavori, t=25cm perhapur e ngjeshur me makineri	m ²	950		
4	3.617/1	F.V. Bordure betoni M-250 15x30cm	ml	752		
5	Analize	F.V. Bordure betoni M-250 10x20cm	ml	1,096		
6	3.244	F.V. Beton M-250 per bordura, kanale, kuneta, trotuare etj	m ³	45		
7	3.238	F.V. Beton M-100 per fiksimin e bordurave	m ³	84		
Shuma A-3						
SHUMA A						

B		PUNIME NE VEPRA ARTI			
Nr.	B-1	Pershkrimi i Punimeve	Njesia	Sasia	
1	3.159/a+3.158/5a	Germim me makineri + transport materiali	m ³	63	
2	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	21	
3	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	ml	4	
4	3.369	Tombino me tuba betoni Ø 1500, mbi shtrese betoni	ml	6	
5	3.624	Lyerje me dy duar me prajmer (te nxehte)	m ²	55	
6	3.245	F.V. Beton C25/30	m ³	41	
7	3.244	F.V. Beton C20/25	m ³	19	
8	3.239	F.V. Beton C7/10	m ³	8	
9	3.289	F.V. Hekur betoni periodik, Ç - 5, Ø > 12mm	ton	9	
		SHUMA B			

B		PUNIME NE RRJETIN E KANALIZIMEVE			
B-2 Punime ne Rrjetin K.U.SH.					
1	3.89/a+3.158/5a	Germim dheu me ekskavator 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet + Transport dheu me auto deri 5 km	m ³	420	
2	3.45/1+3.158/5a	Germim me krahe, toke e zakonshme + transport 5km	m ³	15	
3	2.261	Shtrese rere	m ³	110	
4	2.258	Nenshtrese zhavori	m ³	130	
5	3.An/3t	F.V. Tuba te brinjezuar HDPE SN8 Dn=500 mm	ml	50	
6	3.An/2t	F.V. Tuba te brinjezuar HDPE SN8 Dn=400 mm	ml	12	
7	3.An/1t	F.V. Tuba te brinjezuar HDPE SN8 Dn=315 mm	ml	716	
8	Analize	F.V. Tuba te brinjezuar HDPE SN8 Dn=250 mm	ml	210	
9	Analize	Ndertim puseta betoni D 1.0 m; H (1.5-2.5)m + kapak gize	cope	1	
10	2.An-23	Puseta b/a shiu (40x60)cm me kapak gize	cope	58	
		Shuma C			
		SHUMA B			

C		PUNIME NE SINJALISTIKE RRUGORE				
Nr.	Analize	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
1	3.An151	Vizime me boje bikomponente (gjeresi 10cm + kembesore)	m ²	260		
2	3.An158	F.V. Tabela rrugore te ndryshme D=60cm	cope	18		
3	3.An157	F.V. Tabela rrugore treguese 60x20cm	cope	2		
SHUMA C						
SHUMA A-F						-
FOND REZERVE 5%						-
SHUMA						-
T.V.SH. 20%						-
VLERA TOTALE						-