



### PREVENTIV ZBATIMI

**Objektit: REHABILITIMI I EMERGJENCES CIVILE Ndërtim Ure Perroi I Sules, Fshati Gerbllesh, NJ.A. Ndroq**

Nr	Anal	Emertimi i Punimeve	Njesia	Sasia
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m3	185
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	185
3	An-8	Mbushje me cakell	m3	175
4	3.248	Struktura monolite betoni me çakell C 30/37,tombino	m3	13.5
5	3.247	Struktura monolite betoni me çakell C 25/30,sperona,portale,soleta rakorduese	m3	20.7
6	3.24	Beton themeli C 12/15,shtresa e tominove	m3	4.5
7	3.288	F V hekur betoni i zakonshem Ø > 12mm per tombino box+sperona	ton	5.32
8	3.624	H / Izolim me emulsion, 2 duar bitum per tombino box	m2	43
9	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	40