

Preventiv

OBJEKTI: Rikonstruksion Rruga "Milan Shuflaj", Bashkia Shkoder (faza e dyte Pr.360 - Pr.436)

Nr.	Analiza	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (lek)	SHUMA (lek)
A		PUNIME PRISHEJE DHE EVIDENTIMTE MBETJEVE				
1	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5km	m3	210.0		0.0
					Shuma A	0.0
B		PUNIME PER NDERTIMIN E RRUGES				
1	3.89/b	Germim dheu me eskavator goma 0.25m3, ne kanale gjeresi >2m, toke zakonshme kategoria III, me shk ne mjet	m ³	100.0		0.0
2	3.An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri (Shtresa e rruges t=20cm)	m3	68.0		0.0
3	3.212/b	Shtrese stabilizant t=10cm	m2	300.0		0.0
4	3.221/1	Shtrese binderi me granil me gur kave.4cm,me makineri	m2	278.0		0.0
5	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	278.0		0.0
6	3.243	Strukture monolite betoni C 16/20 (t=10cm,per trotuarin)	m ³	8.0		0.0
7	3.243/1	Struktura monolite te holla betoni C16/20(kuneta)	m ³	4.00		0.0
8	2.258	Shtrese zhavor lumi t=10cm	m ³	8.0		0.0
9	3.617	F V bordura betoni 15x25cm	ml	166.0		0.0
					Shuma B	0.0
C		PUNIME PER KANALIZIMET E UJRAVE TE BARDHA DHE TE ZEZA				
1	3.379	Ndertim drenazhi, mbushje me rere natyrale(Rere nen dhe mbi tubacione PE + kompaktesim)	m ³	2.0		0.0
2	3.378	Ndertim drenazhi, mbushje me zhavor prodhuar mak(Zhavorr ne kanale)	m ³	60		0.0
3	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	160		0.0
4	An-23	Pusete b/a shiu 40 x 60 cm, h = 100 cm, me kapak gize	cope	3.0		0.0
5	An	F.V. Tub d= 200mm per lidhjet me banesa	ml	30.0		0.0
6	An-20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	3.0		0.0
7	3.139	Germim dheu me ekskavator goma 0.35-0.40 m ³ , ne themele, toke zak, kategoria III, me shkarkim ne toke	m ³	100		0.0
					Shuma C	0.0
D		PUNIME ELEKTRIKE DHE TEKNOLOGJIKE				
1	3. An/53	FV shtylla metalike per ndricim, H=7m	cope	18		0.0
2	An.4	FV ndricues rrugor Led ,4800lm, 4000 K	cope	18		0.0
3	3.An/ksh	F.V. krah shtylla metalike KRH - MSI 1500/1500/10	cope	18		0.0
4	3.An/57b	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	3		0.0
5	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	3		0.0
6	An-(M3)	F V kuader komandimi komplet me santeri+fotoelement	cope	1.0		0.0
7	An.2	F.V. Kabell XYMM 0.6/ 1KV. 3x1.5mm2	ml	150		0.0
8	An.3	F.V. Kabell FG7OR 0.6/ 1KV. 4x 6mm2	ml	540		0.0
9	3.654/1	Furnizim, vendosje tuba plastmasi ø 80	ml	89		0.0
10	3.379	F.V. Rere nen dhe mbi tubacione PE + kompaktesim	m ³	4		0.0
11	4.150/7	F.V. percjelles CU te veshur per tokezmin	ml	9		0.0
12	An.7	F.V. Tuba metalik D=110mm	cope	5.0		0.0
					Shuma D	0.0

E		PUNIME PER SINJALISTIKEN				
1	An151	Boje bikomponente	m ²	18.0		0.0
2	An99	Tabele sinjalizimi	cope	3.0		0.0
3	An57 (M-3)	Sinjale "emër rruge" LxH e vogël 60x20	cope	1.0		0.0
					Shuma E	0.0
		SHUMA (A - E)				0.0
		FONDI REZERVE 5%				0.0
		SHUMA 1				0.0
		TVSH 20%				0.0
		SHUMA TOTALE				0.0

Per: "C.E.C GROUP" shpk

Ing. Vangjush MBRICE

Ing. Anduen MBRICE