

PREVENTIV TOTAL

Objekti: Ndertim ,Sistemim ,Asfaltim I Rrugeve te Brendshme ,Bashkia Belsh

Nr	Nr. an.	EMERTIMI I PUNIMEVE	Njesi	Sasi	Cmim	Vlere
		I-PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	11,509.00		-
2	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	563.00		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	728.82		-
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	11,343.18		-
		SHUMA I				-
		II-PUNIME SHTRESASH				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	14,389.71		-
2	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	24,337.00		-
3	3.212/b	Shtrese stabilizant t=10cm	m2	29,512.00		-
4	An	Shtrese binderi me gur gave 6 cm(miks)	m2	17,850.00		-
5	An	Shtrese stabilizant t=6 cm per bankine	m2	9,207.00		-
		SHUMA II				-
		III-PUNIME BETONI + VEPRA ARTI				
1	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal+ kunete + mure)	m3	460.68		-
2	3.183/a	Shtrese zhavor lumi t=10cm	m2	478.00		-
3	An-9	Mbushje me zhavorr pas mureve, per tombino	m3	500.00		-
4	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	220.00		-
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	73.00		-
		SHUMA III				-
		SHUMA I-III				-
		Fondi rezerve 3%				-
		SHUMA				-
		TVSH 20%				-
		SHUMA ME TVSH				-

PROJEKTUES

NOVATECH STUDIO sh.p.k

PREVENTIV

Objekti: Ndertim ,Sistemim ,Asfaltim I Rrugeve te Brendshme ,Bashkia Belsh

Rruga Idriz

Nr	Nr. an.	EMERTIMI I PUNIMEVE	Njesi	Sasi	Cmim	Vlere
		I-PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	-		-
2	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	-		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	-		-
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	-		-
		SHUMA I				-
		II-PUNIME SHITESASH				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	568.00		-
2	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	-		-
3	3.212/b	Shtrese stabilizant t=10cm	m2	5,175.00		-
4	An	Shtrese binderi me gur gave 6 cm(miks)	m2	5,175.00		-
5	An	Shtrese stabilizant t=6 cm per bankine	m2	1,725.00		-
		SHUMA II				-
		III-PUNIME BETONI + VEPRARTI				
1	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal+ kunete + mure)	m3	71.00		-
2	3.183/a	Shtrese zhavor lumi t=10cm	m2	75.00		-
3	An-9	Mbushje me zhavorr pas mureve, per tombino	m3	78.00		-
4	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	35.00		-
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	12.00		-
		SHUMA III				-
		SHUMA I-III				-
		Fondi rezerve 3%				-
		SHUMA				-
		TVSH 20%				-
		SHUMA ME TVSH				-

PROJEKTUES

NOVATECH STUDIO sh.p.k

PREVENTIV

Objekti: Ndertim ,Sistemim ,Asfaltim I Rrugeve te Brendshme ,Bashkia Belsh

Rruget Qafshkalle 1, Qafshkalle 2, Qafshkalle 3

Nr	Nr. an.	EMERTIMI I PUNIMEVE	Njesi	Sasi	Cmim	Vlere
		I-PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	5,393.00		-
2	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	204.00		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	108.00		-
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	5,489.00		-
		SHUMA I				-
		II-PUNIME SHTRESASH				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	4,615.34		-
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	10,087.00		-
3	3.212/b	Shtrese stabilizant t=10cm	m2	10,087.00		-
4	An	Shtrese binderi me gur gave 6 cm(miks)	m2	5,725.00		-
5	An	Shtrese stabilizant t=6 cm per bankine	m2	3,362.00		-
		SHUMA II				-
		III-PUNIME BETONI + VEPRA ARTI				
1	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal+ kunete + mure)	m3	138.00		-
2	3.183/a	Shtrese zhavor lumi t=10cm	m2	146.00		-
3	An-9	Mbushje me zhavorr pas mureve,per tombino	m3	152.00		-
4	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	67.00		-
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	22.00		-
		SHUMA III				-
		SHUMA I-III				-
		Fondi rezerve 3%				-
		SHUMA				-
		TVSH 20%				-
		SHUMA ME TVSH				-

PROJEKTUES

NOVATECH STUDIO sh.p.k

PREVENTIV

Objekti: Ndertim ,Sistemim ,Asfaltim I Rrugeve te Brendshme ,Bashkia Belsh

Rruga Lokalitet

Nr	Nr. an.	EMERTIMI I PUNIMEVE	Njesi	Sasi	Cmim	Vlere
		I-PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	1,211.00		-
2	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	104.00		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	3.82		-
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,311.18		-
		SHUMA I				-
		II-PUNIME SHITESASH				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	2,000.00		-
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	3,000.00		-
3	3.212/b	Shtrese stabilizant t=10cm	m2	3,000.00		-
4	An	Shtrese binderi me gur gave 6 cm(miks)	m2	1,900.00		-
5	An	Shtrese stabilizant t=6 cm per bankine	m2	900.00		-
		SHUMA II				-
		III-PUNIME BETONI + VEPRA ARTI				
1	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal+ kunete + mure)	m3	70.00		-
2	3.183/a	Shtrese zhavor lumi t=10cm	m2	74.00		-
3	An-9	Mbushje me zhavorr pas mureve, per tombino	m3	78.00		-
4	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	34.00		-
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	11.00		-
		SHUMA III				-
		SHUMA I-III				-
		Fondi rezerve 3%				-
		SHUMA				-
		TVSH 20%				-
		SHUMA ME TVSH				-

PROJEKTUES

NOVATECH STUDIO sh.p.k

PREVENTIV

Objekti: Ndertim ,Sistemim ,Asfaltim I Rrugeve te Brendshme ,Bashkia Belsh

Rruga Grekan

Nr	Nr. an.	EMERTIMI I PUNIMEVE	Njesi	Sasi	Cmim	Vlere
		I-PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m³, ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	1,844.00		-
2	3.87/a	Germim dheu me ekskavator goma 0.25 m³, ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	81.00		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	72.00		-
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,853.00		-
		SHUMA I				-
		II-PUNIME SHITESASH				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	3,206.37		-
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	4,450.00		-
3	3.212/b	Shtrese stabilizant t=10cm	m2	4,450.00		-
4	An	Shtrese binderi me gur gave 6 cm(miks)	m2	2,315.00		-
5	An	Shtrese stabilizant t=6 cm per bankine	m2	1,335.00		-
		SHUMA II				-
		III-PUNIME BETONI + VEPRA ARTI				
1	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal+ kunete + mure)	m3	55.00		-
2	3.183/a	Shtrese zhavor lumi t=10cm	m2	58.00		-
3	An-9	Mbushje me zhavorr pas mureve, per tombino	m3	61.00		-
4	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	27.00		-
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	9.00		-
		SHUMA III				-
		SHUMA I-III				-
		Fondi rezerve 3%				-
		SHUMA				-
		TVSH 20%				-
		SHUMA ME TVSH				-

PROJEKTUES

NOVATECH STUDIO sh.p.k

PREVENTIV

Objekti: Ndertim ,Sistemim ,Asfaltim I Rrugeve te Brendshme ,Bashkia Belsh

Rruga Deshiran /Bakall

Nr	Nr. an.	EMERTIMI I PUNIMEVE	Njesi	Sasi	Cmim	Vlere
		I-PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	1,547.00		-
2	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	121.00		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	214.00		-
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,454.00		-
		SHUMA I				-
		II-PUNIME SHITESASH				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	2,800.00		-
2	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	4,500.00		-
3	3.212/b	Shtrese stabilizant t=10cm	m2	4,500.00		-
4	An	Shtrese binderi me gur gave 6 cm(miks)	m2	1,605.00		-
5	An	Shtrese stabilizant t=6 cm per bankine	m2	1,000.00		-
		SHUMA II				-
		III-PUNIME BETONI + VEPRA ARTI				
1	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal+ kunete + mure)	m3	82.00		-
2	3.183/a	Shtrese zhavor lumi t=10cm	m2	87.00		-
3	An-9	Mbushje me zhavorr pas mureve,per tombino	m3	91.00		-
4	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	40.00		-
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	13.00		-
		SHUMA III				-
		SHUMA I-III				-
		Fondi rezerve 3%				-
		SHUMA				-
		TVSH 20%				-
		SHUMA ME TVSH				-

PROJEKTUES

NOVATECH STUDIO sh.p.k

PREVENTIV

Objekti: Ndertim ,Sistemim ,Asfaltim I Rrugeve te Brendshme ,Bashkia Belsh

Rruga Shkoza

Nr	Nr. an.	EMERTIMI I PUNIMEVE	Njesi	Sasi	Cmim	Vlere
		I-PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	1,514.00		-
2	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	53.00		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	331.00		-
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,236.00		-
		SHUMA I				-
		II-PUNIME SHTRESASH				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	1,200.00		-
2	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	2,300.00		-
3	3.212/b	Shtrese stabilizant t=10cm	m2	2,300.00		-
4	An	Shtrese binderi me gur gave 6 cm(miks)	m2	1,130.00		-
5	An	Shtrese stabilizant t=6 cm per bankine	m2	885.00		-
		SHUMA II				-
		III-PUNIME BETONI + VEPRA ARTI				
1	3.244/1	Struktura te holla monolite betoni C 20/25 (kanal+ kunete + mure)	m3	44.68		-
2	3.183/a	Shtrese zhavor lumi t=10cm	m2	38.00		-
3	An-9	Mbushje me zhavorr pas mureve, per tombino	m3	40.00		-
4	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	17.00		-
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	6.00		-
		SHUMA III				-
		SHUMA I-III				-
		Fondi rezerve 3%				-
		SHUMA				-
		TVSH 20%				-
		SHUMA ME TVSH				-

PROJEKTUES

NOVATECH STUDIO sh.p.k