

PREVENTIVI

Rikonstruksioni i Pallatit Nr. 21

VLERESUAR SIPAS VKM Nr. 629 Dt.05.11.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
I PUNIME PRISHJE						
1	An	Prishje/kruarje/pastrim suvatimi tavan + mure te brendeshme	m ²	730,00		
2	2.426/3	Prishje shtresa betoni (tarace)	m ³	70,56		
3	2.426/1	Prishje mur tulle me pastrim	m ³	1,00		
4	2.426/3	Prishje shtresa betoni (shtresa ,pllakat e dyshemese ,korrimano)	m ³	3,60		
5	an 2.324b	Prishje Plintuse pllake grez	ml	325,00		
6	An2.405	Cmontim pragje dyer, dritare, shkalle, me pllake granili te armuar	m ²	105,00		
SHUMA I						-
II PUNIME NE TARRACA						
1	2.239/a	Shtrese termoizoluese me polisterol t=10 cm	m ²	670,00		
2	3.243/1	Struktura te holla monolite betoni C 16/20 t=40mm	m ³	26,80		
3	2,197	Hidroizolim me emulsion bitumi dhe 2 k katrama	m ²	750,00		
4	2,200	Shtrese lluster cemento 1:2 t = 20 mm	m ²	697,00		
5	2,209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	133,00		
6	2,206	Kasete shkarkimi me llamarine xingat	cope	3,00		
7	2,212	Ulluk shkarkimi horizontal me llamarine xingat 33cm	ml	45,00		
8	2,203	Veshje kornize llamarine xingat	m ²	91,00		
SHUMA II						
III PUNIME SHTRESASH SUVATIMI DHE MURE						
1	2,310	Suva brenda mur tulle h~4m me krah dhe tavane, llaç perzier M 25	m ²	570,00		
2	2,300	Suva solete ~ 4 m me drejtues, me krah	m ²	160,00		
3	2.267/1	Shtrese me pllaka porcelanat importi	m ²	90,00		
4	2.324b	Plintuse grez h = 10 cm	ml	325,00		
5	2,273	Shtrese pllaka mermeri t=3cm	m ²	105,00		
6	2.273/4	Shtrese me pllaka mermeri t=2cm "JANINA"	m ²	25,00		
7	3.243/1	Struktura te holla monolite betoni C 16/20	m ³	3,60		
8	2.70/2	Mur me tulle te lehtesuara dopio deri 3m me llaç perzier M25	m ³	1,00		
9	2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suva	m ²	1540,00		

10	2,334	Suva e zakonshme fasade mur tulle mbi 8m lartesi	m ²	407,00		
11	2.386/2	Dyer te blinduara importi.	m ²	9,00		
12	2.375/1	F.V dritare d/alumini plastike me dopio xham	m ²	35,00		
SHUMA III						
IV	PUNIME INSTALIME ELEKTRIKE					
1	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	249,90		
2	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	220,00		
3	2.485/5	F.V Çeles 2 polar 220V 10A "Gevis"	cope	15,00		
4	2.a-132	Ndricues tavanor fluoeshente 1x40w	cope	24,00		
5	480/3	FV.Tub pvc Ø 25	ml	630,00		
6	2,487	F.V Kutiderivacioni plastike	cope	15,00		
7	An	Brand (BE) Apartment Outdoor Station + Bazamentet	Cope	3,00		
8	An	Brand (BE) IP Indoor Monitor 7 inch	Cope	18,00		
9	An	Brand (BE) Network Power Supply for IP System 6-Channel	Cope	3,00		
10	An	Ushqyes 24V	Cope	3,00		
11	An	Brand (BE) Switch 8-Port Gigabit	Cope	3,00		
12	An	FV Brand (BE) Kabllo Cat6 cmimi per 1 meter linear	ml	210,00		
SHUMA IV						
V	PUNIME BOJATISJE					
1	2.404/1	Boje hidroplastike cilesi e larte	m ²	2590,00		
SHUMA V						
SHUMA TOTALE E OBJEKTIT I-V						

PREVENTIVI

ikonstruksioni godines se Ish Bankes se Shtetit

VLERESUAR SIPAS VKM Nr. 629 Dt.05.11.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
I	PUNIME PRISHJE					
1	An	Prishje/kruarje/pastrim suvatimi tavan + mure te brendeshme dhe te jashtme	m ²	526,00		
2	2.426/3	Prishje shtresa betoni (tarace)	m ³	10,00		
3	an	Ç'montim dyer/dritare, metalike, d/alumin dhe druri	m ²	120,00		
SHUMA I						
II	PUNIME NE TARRACA					
4	2,196	Hidroizolim me emulsion bitumi dhe 1 k katrama(riparime)	m ²	180,00		
5	2,209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	90,00		

SHUMA II						
III	PUNIME SHITRESASH SUVATIMI DHE MURE					
6	2,334	Suva e zakonshme fasade mur tulle mbi 8m lartesi	m ²	739,00		
7	2.375/1	F V dritare d/alumini plastike me dopio xham	m ²	120,00		
SHUMA III						
IV	PUNIME BOJATISJE					
8	2.404/1	Boje hidroplastike cilesi e larte	m ²	739,00		
SHUMA IV						
SHUMA TOTALE E OBJEKTIT I-V						

NR.	PREVENTIVI PERMBLEDHES	Vlera
1	Rikonstruksioni i Pallatit Nr. 21	
2	Rikonstruksioni i Godines se Ish Bankes	
TOTALI PA TVSH		
TVSH 20 %		
TOTALI ME TVSH		