

PREVENTIV I PUNIMEVE

Emërtimi i Objektivit: "RIKONSTRUKSIONI I PALESTRES SE SHKOLLES 9- VJEÇARE "QYBRA SOKOLI"" QYTETI PREENJAS  
Autor i projektit: PF ENEA MANOKU

Nr.	An.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
<b>A. PUNIME NE SISTEMIMIN E JASHEM</b>						
<b>1.PUNIME GERMIMI</b>						
1	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m3	20.0		
2	2.37/5a	Trasport materiale ndertimi dheu me auto deri 5 km	m3	20.0		
<b>2.PUNIME MURATURE GURI DHE PLLAKA</b>						
1	2.52/2	Mur guri themel e xogel me llaç te perzier M-25	m3	78.0		
2	3.620	Trotuar, me 6 cm beton, me pllaka	m2	156.0		
3	3.616	F V bordura betoni 12x25 cm	ml	100.0		
4	2.258/2	Shtrese zhavori ne teritorin e ndertesave	m3	31		
					<b>SHUMA A</b>	
<b>B. PUNIME PER PALESTREN</b>						
<b>1.PUNIME PRISHJE</b>						
1	2.426/3	Prishje shtresa betoni+trasport (shtresa ekzsituose e pllakave)	m3	6		
<b>2.PUNIME SHITRESASH + DYER DRITARE</b>						
1	2.276	Shtrese parket druri+bordura+nen struktura i pershtatshem per ambiente sportive	m2	503.0		
2	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k katrama (parketi)	m2	554		
3	2.262	Shtrese betoni C 6/10	m3	6		
4	2.267/b	Shtrese me pllaka grez importi 60 x 60 cm	m2	100.0		
5	2.267/a	Shtrese me pllaka grez porcelanato + veshje	m2	290.0		
6	2.196/b	Hidroizolim me nje shtrese mapej	m2	40.0		
7	2.273	Shtrese pllaka mermeri t=2cm	m2	39.1		
8	2.404	Boje hidroplastike	m2	200		
9	2.404/1	Boje hidroplastike importi cilesi e I-re	m2	1,026		
10	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k katrama (taraca)	m2	156.9		
11	2.256/b	Mbulim çatie me sanduic	m2	129.0		
12	2.375/a	Dritare d/alumini dyfish xham	m2	55.9		
13	2.395/a	Dere d/alumini pa xham me mbushje d/alumini	m2	9.5		
14	2.388/1	F.V dyer te brendeshme tamburate te rimesuara	m2	9.9		
15	2.86	Mure me tulla me 6 vrima. M - 15 t = 12cm	m3	6.0		
16	2.331	Suva e zakonshme fasade mur tulle h ~ 8 m	m2	200.0		
<b>3.VENDOSJE ULLUQE VERTIKAL DHE HORIZONTAL</b>						
1	2.209	Ulluk shkarkimi vertikal me llamarin xingato me Ø 100 mm	ml	8.0		
2	2.206	Kasete shkarkimi me llamarin xingato	cop	2.0		
<b>4.PUNIME ELEKTRIKE</b>						
<b>RRJETI ELEKTRIK I NDRICIMIT TE PALESTRES</b>						
1	2.a-117	FV Zile esinjalizuese per mbarimin e ores te mesimit	cope	1.0		
2	2.485/5	FVÇelesa ndricimi 1 polar In 16A	cope	3.0		
3	2.485/5	FVÇelesa ndricimi deviat In 16A	cope	3.0		
4	2.481/1	F V Percjelles TU Izolim p v c Tip petashuk 3*15	ml	50.0		
5	2.481/1	FV Percjelles TU, izolimP V C Tip NO7V-KS=1*1.5	ml	50.0		
6	An-32	F V Tub flesibel P V C Ø 20 mm Tip I rende	ml	50.0		
7	2.487/d	F V Kuti Suportpllaket 4 modular Gevis	cope	3.0		
8	An-29	FVSuport 3 Mod	cope	3.0		
9	AN-30	F V pllake 3 mod	cope	3.0		
10	AN-31	FV Tapa	cop	3.0		
11	2-a 138	Ndricues fluoreshent 2x40 Wip 40	cop	12.0		
12	An-37	Pika e lidhjes me energji elektrike	lek	1.0		
<b>RRJETI ELEKTRIK I GODINES SE SHERBIMEVE</b>						
13	2.a-117	Sirene e jashteme	cop	2.0		
14	2.485/5	FV Çeles 2 polar 220 V 10 A"GEVIS"	cop	33.0		
15	2.481/1	FV Percjelles PV-500 Ø 1.5m²	ml	200.45		
16	2.481/1	FV Percjelles PV-500 Ø 1.5m²	ml	100.0		
17	An -32	Tub fleksibel P V C Ø 20 mm Tip I rende	ml	100.0		
18	2.487/d	F V Kuti Suport pllakat4 modular Gevis	cop	12.0		
19	An-29	F V Suport 3 3 mod	cop	12.0		
20	An-30	F V pllake 3 mod	cop	12.0		
21	An-31	F V Tapa	cop	12.0		
22	An-35	F V plafonier ne holle Led 3600	cop	10.0		
<b>5.PUNIME HIDRO</b>						
1	2.495	F.V lavaman porcelani importi me mishelator	cope	4		
2	2.501	F.V WC allafrenga importi	cope	2		

3	2.515	F.V pilete dyshemeje Ø 50 mm	cope	10		
4	2.508	F.V bolier 100 l importi	cope	6		
5	An	F.V grup dushi	cope	6		
		<b>6.PUNIME MOBILIMI</b>				
1	An	FV Kosh basketbolli me konstruksion metalik dhe rrjeta	cope	2		
2	An	FV Rrjete volejbolli me koloncina metalike, 2 jastek sportiv, 1 kaluc, 6 varese rrobash, 6 perde me tubo metalik, 4 kosha per tualetet	cope	1		
						<b>SHUMA B</b>
		<b>TOTALI A+B</b>				
		<b>Fond rezerve</b>				
		<b>TOTALI PA TVSH</b>				
		<b>TVSH 20%</b>				
		<b>TOTALI ME TVSH</b>				

PUNOI: PF ENEA MANOKU