

PREVENTIV

OBJEKTI: Sistemim i rrugeve te brendeshme me beton Lagjia nr.3 , Lagjia nr.1

INVESTITOR: Bashkia Sarande

Nr.	NR.ANALIZE	Emërtimi i punimeve	Njësia	Sasia	Çmimi	Vlefte
		Sistemim i rrugeve te brendeshme me beton				
A		Rr.13 BILBILENJT (B=5m , L=230 ml)				
1		Rrafshim ,nivelim , skarifikim t=10cm	m2	500		0
2		Shtrese stabilizant t=10cm	m2	400		0
3		Shtrese betoni M-200 t=15cm ne rruge	m3	173		0
4		F V Zgare Çeliku Ø 4 mm	m2	1150		0
5		Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri , b=2x0.5m , per bankinat anesore te betonit	m2	297		0
		Shuma 1				0
B		Rruge te brendshme Lugu i Dardhes (B=3m , L=442 ml)				
1		Rrafshim ,nivelim , skarifikim t=10cm	m2	1325		0
2		Shtrese stabilizant t=10cm	m2	1325		0
3		Shtrese betoni M-200 t=15cm ne rruge	m3	200		0
4		F V Zgare Çeliku Ø 4 mm	m2	1325		0
5		Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri , b=2x0.5m , per bankinat anesore te betonit	m2	426		0
		Shuma 2				0
C		Sistemim i hapesires mbrapa shtepise se ofiverave				
1		Germim dheu me eskavator me goma	m3	20		0
2		Shtrese stabilizant t=10cm	m2	200		0
3		Shtrese betoni M-200 t=15cm ne rruge	m3	24		0
4		F V Zgare Çeliku Ø 4 mm	m2	200		0
		Shuma 3				0
		Shuma 1-2-3				0
		T.V.SH		20%		0
		Totali				0

Preventivoi

Miratoi