

PREVENTIV I PUNIMEVE

Objekti: SISTEMIM I RRUGEVE TE BRENDSHME, FSHATI TERBAC, BASHKIA HIMARE

Investitori: Bashkia Himare

| Nr. | Nr.An | Pershkrimi i punimeve | Njesia | Sasia | Cmimi | Vlera |
|-----|----------|---|----------------|-------|-------|-------|
| | | PUNIME DHERASH NE RRUGE | | | | |
| 1 | 3.89/b | Germim dheu me mjet, toke e zak, kat III, me shkarkim ne mjet | m ³ | 369 | | |
| 3 | An164/1a | Mbushje me material te germuar me makineri | m ³ | 200 | | |
| 4 | 2.37/5a | Transport materiale ndertimi, dheu auto deri 5 km | m ³ | 169 | | |
| | | SHUMA I | | | | |
| | | PUNIME SHITESASH NE RRUGE | | | | |
| 1 | 3.205/2 | Shtrese zhavorri 20 cm | m ² | 2400 | | |
| 2 | 3.210. | Shtrese cakulli 15 cm | m ² | 2400 | | |
| 3 | 3.212/b | Shtrese stabilizanti 10 cm | m ² | 2400 | | |
| 4 | 3.244 | Shtrese betoni C20/25 15cm | m ³ | 360 | | |
| 5 | An.1 | Zgare metalike e elektrosalduar | m ² | 2400 | | |
| | | SHUMA II | | | | |
| | | KONSTRUKSIONE METALIKE PER URAT E KEMBESOREVE | | | | |
| 1 | 2.181 | Konstruksione metalike te perbera | ton | 1.8 | | |
| 2 | 3.415/3 | Ura druri. Hapesire kalimi me derrasa, 5 cm | m ² | 30 | | |
| 3 | 2.37/5b | Transport materiale me kafshe, deri 5.0 km | Ton | 2 | | |
| | | SHUMA III | | | | |
| | | KONSTRUKSIONE METALIKE PER URAT E KEMBESOREVE | | | | |
| 1 | 3.355 | Tombino me tuba betoni ø 400 | ml | 10 | | |
| | | SHUMA IV | | | | |
| | | SHUMA I - IV | | | | |
| | | T.V.SH= 20% | | | | |
| | | SHUMA TOTALE | | | | |

Punoi: