

PREVENTIV PUNIMESH PA CMIME

OBJEKTI: SISTEMIM ASFALTIM RRUGA GJURAJ KOPLIK I SIPERM

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
PUNIME NE TRUP TE RRUGES						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , toke zak, kategoria III, me shk ne mjet	m ³	560	-	-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	560	-	-
3	3.2	Prerje bime te vogla ø-10cm	m2	2,100	-	-
4	2.426/3	Prishje shtresa betoni	m3	12	-	-
5	2.426/2	Prishje mur blloqe betoni	m3	10	-	-
6	3.212/b	Shtrese stabilizanti 10cm per rrugen	m ²	2,495	-	-
7	3.205/2	Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri	m2	2,495.0	-	-
8	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	2,165.0	-	-
9	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m2	2,650.0	-	-
10	3.240	Struktura monolite betoni C 12/15 (kuneta)	m3	55.6	-	-
11	3.243	Struktura monolite betoni C 16/20 (bordura,trot)	m3	147	-	-
12	3.205	Shtrese zhavori lumi t=10cm, perhapur e ngjeshur me makineri (trotuare)	m2	890	-	-
VEPRA ARTI						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , toke zak, kategoria III, me shk ne mjet	m ³	12.0	-	-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	12.0	-	-
3	AN.	Ndertim zgare b/a L=600cm B=60cm H=var.	cope	1	-	-
4	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	5	-	-
SHUMA						
TVSH 20%						
TOTAL						

**PREVENTIVOI
"Novatech Studio" shpk
Ing.Emil Nova**