

PREVENTIV I PUNIMEVE NDERTIMORE

**RIKONSTRUKSIONI DHE ARREDIMI I ZYRAVE NJESIVE
ADMINISTRATIVE TE BASHKISE BERAT, AMBIENTIT TE PRITJES SE
DELEGACIONEVE TE HUAJA DHE SALLES SE MBLEDHJES.**

Objekti :

Investitor :

Bashkia BERAT

Nr	Nr.Anal	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
----	---------	---------------------	--------	-------	-------	-------

Objekti : **RIKONSTRUKSIONI NJESIA ADMINISTRATIVE ROSHNIK - BERAT**

b-Punime bojatisje						
1	2.404/1	Boje hidroplastike importi cilesi e l-re	m2	400		-
c-Punime elektrike						
1		Riparime elektrike	cope	1		-
	shuma					-

Objekti : **RIKONSTRUKSIONI NJESIA ADMINISTRATIVE SINJE**

a-Punime suvatimi e shtresash						
1	2.310	Suvatim mure tulle	m2	20		-
b-Punime bojatisje						
1	2.404/1	Boje hidroplastike importi cilesi e l-re	m2	870		-
c-Punime elektrike						
1		Riparime elektrike	cope	1		-

Objekti : **RIKONSTRUKSIONI NJESIA ADMINISTRATIVE VELABISHT**

a-Punime suvatimi e shtresash						
1	2.310	Suvatim mure tulle	m2	30		-
b-Punime suvatimi e veshje me pllaka						
1	2.297/b	Tavan i varur me pllaka gipsi 60x60cm	m2	7		-
c-Punime bojatisje						
1	2.404/1	Boje hidroplastike importi cilesi e l-re	m2	560		-
d-Punime elektrike						
1		Riparime elektrike	cope	1		-

Objekti : **RIKONSTRUKSIONI NJESIA ADMINISTRATIVE RAJONI Nr: 1 - BERAT**

c-Punime bojatisje						
1	2.404/1	Boje hidroplastike importi cilesi e l-re	m2	340		-

Objekti : **RIKONSTRUKSIONI NJESIA ADMINISTRATIVE RAJONI Nr: 2 dhe 3 - BERAT**

c-Punime bojatisje						
1	2.404/1	Boje hidroplastike importi cilesi e l-re	m2	80		-

1-Punime prishje , Transporti						
1	2.426	Prishje mur tulle pa pastrim	m ³	15.5		-
2	2.426/4	Prishje soleta b/a (per hapjen e shkalles qe do dale ne tarraces)	m ³	1.2		-
3	2.426/3	Prishje shtresa betoni (shtresa e varfer dyshemeje)	m ³	15		-
4	2.37/3b	Transport materiale ndertimi, dheu me auto deri 8.0 km	m ³	31.7		-
2-Punime te Brendshme Ndertimore						
1	2.264	Shtrese lluster cimento 1:2	m ²	25		-
2	2.276	Shtrese parketi	m ²	140		-
3	2.267/a	Shtrese me pllaka grez porcelanato	m ²	135		-
4	2.300	Suva solete h ~ 4 m me drejtues, me krah	m ²	25		-
5	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	45		-
6	2.324/b	Plintuse grez importi, h = 10 cm	ml	35		-
7	2.328	Patinim muri allçi (stuko)	m ²	400		-
8	2.297/a	Tavan me kartonxhes	m ²	200		-
3-Punime Arredimi te Brendshem						
1	An.1	Veshje muri me Mdf Rimeso Lisi	m ²	150		-
2	An.2	Punim Tavani Dekorativ Druri Tradicional Berati me gdhendje	m ²	43		-
3	An.4	Tavoline xhami mbledhje	Cope	1		-
4	An.5	Tavoline salla mbledhjeve	Cope	1		-
5	An.6	Tavoline per takim	Cope	1		-
6	An.7	Mobilje Raft	ml	3		-
8	An.9	Mobilje Ndarje Ambjentesh	ml	3.8		-
9	An.10	Mobilje rafti tek NHS	ml	1.5		-
10	An.11	Karrige	Cope	1		-
11	An.12	Karrige salla mbledhjeve	Cope	16		-
12	An.13	Karrige tip 1	Cope	8		-
13	An.14	Karrige tip 2	Cope	2		-
14	An.15	Karrige transparente (xhami - plastike)	Cope	6		-
15	An.16	Karrige sekretaria	Cope	1		-
16	An.17	Karrige pritje	Cope	4		-
17	An.18	Piktura Druri te gedhendura	Cope	14		-
4-Punime Dyer dhe Dritare						
1	2.375/a	Dritare d/alumini dyfish xham.	m ²	28		-
2	An.1	F V dyer te brendeshme druri importi cilesi e l-re.	m ²	20		-
5-Punime bojatisje						
1	2.404/1	Boje hidroplastike importi cilesi e l-re	m ²	500		-
6-Punime Hekuri						
1	2.181	Konstruksione metalike te perbera (shkalle)	ton	1.1		-
2	2.182	Konstruksione metalike te thjeshta (Mbulesa ne Tarrace)	ton	0.85		-
3	2.22	Çati me kapriate metalike me HD 10~12m	m ²	80		-
4	2.256/b	Mbulim çatie me panele sandwich	m ²	80		-
5	2.239/a	Shtrese termoizoluese me polisterol t=10 cm	m ²	80		-
6	An.1	F.V hekur betoni	kg	385		-
6-Punime Beton Arme						
1	2.117/1b	Beton arme C-25/30 Kollona	m ³	2		-
2	2.119/1a	Beton arme C-25/30 Trare	m ³	1.35		-
7-Punime Tarrace / Hidroizolimi						
2	2.2	Shtrese lluster cimento 1:2, t = 20 mm	m ²	500		-
3	2.239/a	Shtrese termoizoluese me polisterol t=10 cm	m ²	500		-
4	2.297/a	Tavan me kartonxhes	m ²	80		-
5	2.291	Bordura trotuari 25x12cm te derdhura ne vend (Per sistemimin e Tarraces)	ml	170		-
8	2.267/a	Shtrese me pllaka grez porcelanato (Dalja ne Tarrace e Mbuluar)	m ²	10		-
10	2.266/1	Shtrese me pllaka granili me boje 30x30 cm	m ²	20		-
9-Punime Elektrike						

1. Rruge Kalimet					
1	An.1	F.V. Kanaline e birezuar Zn 200x75	ml	40	-
2	An.2	FV. Aksesore per kanaline Zn 200x75 (Kthesa, Kryqezime, Reduktoore , Nderrim plani ,kapak aksesoresh etj sipas rastit)	cope	7	-
3	An.3	FV. Separator H75	ml	40	-
4	An.4	FV. Aksesore fiksimi me varje (kompletuar me 2cp prizhonier te filetuar M8 , 0.4m profil Zn55x18 ,6cp dado m8 , 6 cp	cope	28	-
5	480/3	F.V Tub fleksibel PVC,djegje pa flake dhe emetim gazi, Ø25mm me aksesore	ml	200	-
6	480/2	F.V Tub fleksibel PVC,djegje pa flake dhe emetim gazi, Ø20mm me aksesore	ml	380	-
7	An.5	F.V Kuti shpemdarese C5 150x110x70 IP40 per instalim jashte murit .	cope	15	-
					-

2. Kabllot					
1	An.6	F.V Kabell FG16OR16 S=5x10mm2	ml	100	-
2	An-4,11	F.V Kabell FG16OR16 S=3x6mm2	ml	20	-
3	An.7	F.V Kabell FG16OR16 S=5x2.5mm3	ml	30	-
4	An-4,18	F.V Kabell FG16OM16 S=3x1.5mm2	ml	100	-
5	An-4,17	F.V Kabell FG16OM16 S=3x2.5mm3	ml	150	-
6	An.8	F.V Percjelles S=1x2.5mm2	ml	600	-
7	An.9	F.V Percjelles S=1x1.5mm2	ml	1100	-
-					
3. Pajisjet					
1	2.487/a	F.V. Kuti, kapak, suport per celesa e priza 3-module, per instalim brenda murit .	cope	9	-
2	An.10	F.V. Kuti, kapak, suport per celesa e priza 4-module, per instalim brenda murit .	cope	12	-
3	2.485/d	F.V Prize Shuko 2P+T 16A	cope	37	-
4	An.11	F.V Prize Shuko 2P+T 16A te kuqe	cope	8	-
5	An.12	F.V Torrete e automatizuar per ne tavoline	cope	2	-
6	An.13	F.V Torrete ne dysHEME 12M	cope	2	-
7	An.14	F.V Spote gipsi edhe llamba	cope	153	-
8	An.15	F.V Shirit LED 14.4 W/m 24V	ml	100	-
9	An.16	F.V Transformator 230/24V 250W	cope	7	-
12	2.485/3	F.V Celes 1P 10 A , 1 modul, per instalim brenda murit	cope	15	-
-					
4. Rrjeti kompjuterik dhe TV-TVSAT					
1	An.19	F.V. Kablo rrjeti kompjuterik, Tip FTP-cat6e	ml	500	-
2	An.20	F.V. Priza rrjeti kompjuterik tip RJ-45, cat 6e, FTP , per instalim ne mur	cope	16	-
3	An.21	F.V. Prize Tv	cope	1	-
4	An.22	F.V. Kabell koaksial	ml	40	-
-					
5. Rack Data Pajisje					
1	An.23	F.V. Rack 15U	cope	1	-
2	An.24	F.V. Patch panel me 24 porta RJ-45, FTP cat 6e	cope	1	-
3	An.25	F.V. Patch guide	cope	1	-
4	An.26	F.V. Grup ventilatoresh me 1 FAN per rack + Panel Komandimi Ventilator 19"	cope	1	-
5	An.27	F.V. Patch corda me FTP-cat-6 me dy koka konektoriale, L=2 m	cope	1	-
6	An.28	F.V. Suport 8 priza PDU 19" 1HE 16A	cope	1	-
-					
6. Kuadrot					
1	An-1.b-1	Kuadri Tensionit Te Ulet(KK)	cope	1	-
2	An.29	UPS 1F 3KVA	cope	1	-
-					
				Shuma totale	-
				Shuma totale	-
				T.V.Sh 20%	-
				Shuma totale	-

Preventivoi: Ark. Luciano Bojaxhi
Ark. Erida Nasufi
Ark. Iris Hoxhallari

Miratoi
KRYETARI
Ervin DEMO