



BASHKIA SELENICE

MI  
K  
Z.PËI  
VKT \_\_\_\_\_

**PREVENTIV PUNIMESH**  
**OBJEKTI: "TRAJTIM RRESHKITJE RRUGE ,FSHATI PESHKEPI ,BASH**

Nr	Nr.man	EMERTIMI I PUNIMEVE	NJESIA	SASIA
<b>I-PUNIME PER PRISHJE</b>				
1	An	Skarifikim shtrese asfalti me makineri	m2	422
<b>SHUMA I</b>				
<b>II-PUNIME GERMIMI</b>				
1	3.104/b	Germim dheu me ekskavator zingjir, 0.5 m <sup>3</sup> , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet	m3	680
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	680
<b>SHUMA II</b>				
<b>III-PUNIME PER GABIONE,TOMBINO</b>				
1	3.183/c	Shtrese zhavor lumi t=20cm	m2	6
2	2.519	Tub Ø 90 mm per kullimin e ujrave ne mure	ml	4
3	3.353	Mbushje me material shkembor(Pas mureve)	m3	59
4	2.262/4	Shtrese betoni C 16/20	m3	1
5	3.244	Struktura monolite betoni C 20/25(PER PORTALIN E TOMBINOS)	m3	5
6	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	9
7	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m3	506
8	3.333	Gabiona me rrjete teli te zinguar, gure kave 1x1x2 m	m3	770
<b>SHUMA III</b>				
<b>IV-PUNIME SHTRESASH</b>				
1	3.198	Cilindrim kasonete me rul	m2	425
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	425
3	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	425
4	3.212/b	Shtrese stabilizant t=10cm	m2	425
5	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	340
6	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m2	340
<b>SHUMA IV</b>				
<b>V-PUNIME TE NDRYESHME+SINJALISTIKA</b>				
1	3.212/b	Shtrese stabilizant t=10cm (BANKINE)	m2	85
2		Vijezim shirita gatesor dhe anesor me gjeresi 12 cm.	ml	170
		Gardrail- N2 anesore me 2 valez. ne 1 ane, W4 + aksesorit	ml	52
<b>SHUMA V</b>				

*[Handwritten signature]*



		SHUMA I-V		
		Fond rezerve 5%		
		SHUMA		
		T.V.SH. 20%		
		TOTALI		

PREVENTIVUES

Shoqeria "ENGINEERING CONSULTING GROUP" sh.p.k

Ing.Ermir ÇUPI



REPUBLIC