

PREVENTIV

Objekti: "Sistemimi I shtratit te perroit ne Goricen e Madhe per mbrojtjen e fshatit nga permbytja"

Nr	NrAN	EMERTIMI PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
I.PUNIME PERKANALIN						
1	3.2	Prerje bime te vogla ø-10cm	m ²	312.0		
2	2.426/3	Prishje struktura betoni	m ³	85.0		
3	3.95/a	Germim dheu me ekskavator zingjir 0.25m ³ , ne kanale gjeresi deri 2m, tokezak, kategoria III, meshknetoke	m ³	2,804.0		
4	3.45/1	Germim kanalesh ne toke te zakonshme, me krahe, me seksionderi 0.75m ²	m ³	112.0		
5	An.1	Mbushje, rafshim, ngjeshje me material te germuar me pare per vepren	m ³	962.0		
6	2.37/3a	Transport mbetje ndertimi, dheu me autoderi 3.0km	m ³	1,898.0		
7	An	Mbushje me zhavor	m ³	835.0		
8	An	Mbushje me cakell	m ³	125.0		
9	3.244	Struktura monolite betoni C20/25 per kanale	m ³	1,025.0		
10	3.287	FV hekur betoni periodik Ø6-10mm	ton	81.9		
11	3.288	FV hekur betoni periodik Ø>12mm	ton	146.3		
Shuma I						
TVSH 20%						
SHUMA IMETVSH						
II.PUNIME PER UREN						
1	3.95/a	Germim dheu me ekskavator zingjir 0.25m ³ , ne kanale gjeresi deri 2m, tokezak, kategoria III, meshknetoke	m ³	55.0		
2	An	Mbushje me zhavor	m ³	37.0		
3	An	Mbushje me cakell	m ³	125.0		
4	3.245	Struktura monolite betoni C25/30 per uren	m ³	80.0		
5	3.288	FV hekur betoni periodik Ø>12mm	ton	11.3		
Shuma II						
III.PUNIME PER PRITALUMORE						
1	3.95/a	Germim dheu me ekskavator zingjir 0.25m ³ , ne kanale gjeresi deri 2m, tokezak, kategoria III, meshknetoke	m ³	5.0		
2	3.331	Gabiona me rrjete te lite zinguar, gurekave 1x1x1m	m ³	5		
3	3.332	Gabiona me rrjete te lite zinguar, gurekave 1x1x1.5m	m ³	7.3		
4	3.333	Gabiona me rrjete te lite zinguar, gurekave 1x1x2m	m ³	10		
5	3.241	Struktura te holla monolite betoni C12/15	m ³	3		
Shuma III						

		Shuma(II+III)				
		TVSH20%				
		SHUMA(II+III)METVSH				
		SHUMA(I+II+III)METVSH				