

P R E V E N T I V
OBJEKTI:URBANIZIMI I BLOKUT TE BANIMIT NE DUSHK SEKTOR
NJESIA ADMINISTRATIVE DUSHK
BASHKIA LUSHNJE

1.RRUGA BASHKIMI L=370ml B=4ml ASFALLT + 2X0.5 KUNETA +TROTUARE 1.5ml NE NJEREN ANE						
Nr analiz	EMERTIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera	
I-PUNIME NE RRUGE						
1	2.426/2	Prishje mur blloqe betoni	m ³	150		
2	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	185		
3	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	1870		
4	3.212/b	Shtrese stabilizanti t=10cm	m ²	1870		
5	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m ²	1500		
6	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	1500		
7	2.262/4	Shtrese betoni C 16/20 t=10 cm (kunete)	m ³	45		
8	3.617/2	F.v bordura 15*35 cm	ml	255		
9	2.262/3	Shtrese betoni C 12/15(per jastek nen bordure t=10cm)	m ³	10		
10	An/164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	56		
					Shuma I	
II-PUNIME NDRICIMI						
1	3.654	F.V Tuba Plastik Ø100	ml	374		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	13		
3	3.59/a	Germim themel i vecuar, gropa sip. 10-30 m ² , toke te bute me h=1.5 m	m ³	3.25		
4	2.262/3	Shtrese betoni C 12/15 per fiksimin e shtylles metalike	m ³	3.25		
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	13		
6	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	13		
7	AN	FV Ndricules LED 100W	cope	13		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	13		
9	4.142/3.15	F.V.kablo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm ²	ml	130		
10	4.131/3.7	F.V.ne toke kablo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm ²	ml	374		
11	An	F V kuader komandimi komplet me santeri+fotoelement	cope	1		
					Shuma II	
III-PUNIME K.U.B						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	187		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	187		
3	2.258	Shtrese zhavori nen tubo t=20cm	m ³	37.4		
4	2.523/1	F.V Tuba PVC f=200 mm te brinjezuar	ml	85		
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	374		
6	An-22/1	Pusete b/a shiu 40 x 40, h = 100 cm, me kapak gize cdo25m	copë	34		
7	2.575	F.v p. kontrolli 100x100x150 cdo 50 m	copë	9		
8	An/164/1b	Mbushje kanali me cakull + ngjeshje	m ³	187		
					Shuma III	
IV-TABELA RRUGORE E VIJEZIME						
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	14		
2	An151	Vizime me boje bikomponente	m ²	70		
3	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	1112		
					Shuma IV	

V-PUNIME TROTUARI						
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri(50cm)	m3	255		
2	3.212/b	Shtrese stabilizant t=10cm	m2	383		
4	2.262/3	Shtrese betoni C 12/15	m ³	38.3		
3	2.266/1	Shtrese pllaka granil me boje 30x30cm	m2	383		
					Shuma V	
VI-PUNIME MURI RRETHUES						
1	2.109/2	Themel e xokol betoni C - 12/15	m3	46		
2	2.88	Mur me blloqe betoni t=20cm deri 3m me llaç perzier M 15	m3	41		
3	2.121/1	Brez b/a C 16/20, h ~ 8 m +koloneta	m3	11		
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	1.5		
5	AN	Zgare metalike per rrethim h=1ml	m2	255		
					Shuma VI	
					SHUMA 1	
2.RRUGA LEMIT L=195ml +120ML DEGEZIMI MAJTAS B=3.5ml ASFALLT + 0.5 KUNETE NE NJEREN ANE						
Nr analiz	EMERTIMI I PUNIMEVE		Njesia	Sasia	Çmimi	Vlera
I-PUNIME NE RRUGE						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	138		
2	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	1380		
3	3.212/b	Shtrese stabilizanti t=10cm	m ²	1380		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m ²	1,163.0		
5	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	1,163.0		
6	2.262/4	Shtrese betoni C 16/20 t=10 cm (kunete)	m ³	35		
7	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	48		
					Shuma I	
II-PUNIME NDRIÇIMI						
1	3.654	F.V Tuba Plastik Ø100	ml	315		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	11		
3	3.59/a	Germim themel i vecuar, gropa sip. 10-30 m ² , toke te bute me h=1.5 m	m ³	2.8		
4	2.262/3	Shtrese betoni C 12/15 per fiksimin e shtylles metalike	m ³	2.8		
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	11		
6	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	11		
7	AN	FV Ndricues LED 100W	cope	11		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	11		
9	4.142/3.15	F.V.kabllo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm2	ml	110		
10	4.131/3.7	F.V.ne toke kabllo Cu fuqie ÷1000V, me izolim gome e mbulesese plastmasi, te armuar, 4x25mm2	ml	315		
					Shuma II	
III-PUNIME K.U.B						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	49		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	49		
4	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	195		
5	An-22/1	Pusete b/a shiu 40 x 40, h = 100 cm, me kapak gize cdo20m	copë	12		
6	An/164/1b	Mbushje kanali me cakull + ngjeshje	m ³	97.5		
					Shuma III	
IV-TABELA RRUGORE E VIJEZIME						
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	8		
2	An151	Vizime me boje bikomponente	m ²	30		
3	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	750		
					Shuma IV	

					SHUMA 2		
3.RRUGA PUNISHTJA L=130ml dhe Degezimi L=65ml B=4ml ASFALLT + 2X0.5 KUNETA							
Nr analiz	EMERTIMI I PUNIMEVE			Njesia	Sasia	Çmimi	Vlera
I-PUNIME NE RRUGE							
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet		m ³	98		
2	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri		m ²	975		
3	3.212/b	Shtrese stabilizanti t=10cm		m ²	975		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri		m ²	780		
5	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri		m ²	780		
6	2.262/4	Shtrese betoni C 16/20 t=10 cm (kunete)		m ³	20		
7	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri		m ³	137		
						Shuma I	
II-PUNIME NDRIÇIMI							
1	3.654	F.V Tuba Plastik Ø100		ml	195		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm		cope	8		
3	3.59/a	Germim themel i vecuar, gropa sip. 10-30 m ² , toke te bute me h=1.5 m		m ³	2		
4	2.262/3	Shtrese betoni C 12/15 per fiksimin e shtylles metalike		m ³	2		
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm		cope	8		
6	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10		cope	8		
7	AN	FV Ndricules LED 100W		cope	8		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm		cope	8		
9	4.142/3.15	F.V.kabllo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm ²		ml	80		
10	4.131/3.7	F.V.ne toke kabllo Cu fuqie ÷1000V, me izolim gome e mbulesse plastmasi, te armuar, 4x25mm ²		ml	225		
						Shuma II	
III-PUNIME K.U.B							
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet		m ³	57		
2	3.158/4a	Transport dheu me auto deri 4.0 km		m ³	57		
3	2.258	Shtrese zhavori nen tubo t=20cm		m ³	25.5		
5	2.523	F.V tubo PVC φ200		ml	50		
6	3.An/3t	F V tuba te brinjezuar HDPE SN8 d=500 mm		ml	160		
7	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm		ml	65		
8	An-22/1	Pusete b/a shiu 40 x 40, h = 100 cm, me kapak gize cdo25m		copë	14		
9	2,575	F.v p. kontrolli 100x100x150 cdo 50 m		copë	7		
10	An/164/1b	Mbushje kanali me cakull + ngjeshje		m ³	112.5		
						Shuma III	
IV-TABELA RRUGORE E VIJEZIME							
1	An155	F V tabela rrugore te ndryshme D=90cm		cope	6		
2	An151	Vizime me boje bikomponente		m ²	30		
3	An152	Vizime me boje bikomponente me gjeresi 15 cm		ml	675		
						Shuma IV	
						SHUMA 3	
4.RRUGA PAVARSIA L=181ml B=3.5ml ASFALLT + 0.5 KUNETE NE NJEREN ANE							
Nr analiz	EMERTIMI I PUNIMEVE			Njesia	Sasia	Çmimi	Vlera
I-PUNIME NE RRUGE							
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet		m ³	73		
2	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri		m ²	724		
3	3.212/b	Shtrese stabilizanti t=10cm		m ²	724		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri		m ²	634		
5	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri		m ²	634		
6	2.262/4	Shtrese betoni C 16/20 t=10 cm (kunete)		m ³	15		

7	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	21		
					Shuma I	
II-PUNIME NDRIÇIMI						
1	3.654	F.V Tuba Plastik Ø100	ml	181		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	6		
3	3.59/a	Germim themel i vecuar, gropa sip. 10-30 m ² , toke te bute me h=1.5 m	m ³	1.5		
4	2.262/3	Shtrese betoni C 12/15 per fiksimin e shtylles metalike	m ³	1.5		
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	6		
6	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	6		
7	AN	FV Ndricules LED 100W	cope	6		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	6		
9	4.142/3.15	F.V.kablo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm ²	ml	60		
10	4.131/3.7	F.V.ne toke kablo Cu fuqie ÷1000V, me izolim gome e mbulesse plastmasi, te armuar, 4x25mm ²	ml	181		
					Shuma II	
III-PUNIME K.U.B						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	136		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	136		
3	2.258	Shtrese zhavori nen tubo t=20cm	m ³	18		
4	3.An /1t	F.v tubo PVC φ315mm per linja te jashtme	ml	181		
5	An-22/1	Pusete b/a shiu 40 x 40, h = 100 cm, me kapak gize cdo20m	copë	9		
6	2,575	F.v p. kontrolli 100x100x150 cdo 50 m	copë	1		
7	An/164/1a	Mbushje kanali me cakull + ngjeshje	m ³	73		
					Shuma III	
IV-TABELA RRUGORE E VIJEZIME						
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	5		
2	An151	Vizime me boje bikomponente	m ²	30		
3	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	543		
					Shuma IV	
					SHUMA 4	
5.RRUGA POLIKLINIKES L=242ml B=3.5ml ASFALLT +0.5 kUNETA NE NJEREN ANE TE RRUGES						
	Nr analiz	EMERTIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
I-PUNIME NE RRUGE						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	97		
2	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	968		
3	3.212/b	Shtrese stabilizanti t=10cm	m ²	968		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m ²	847		
5	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	847		
6	2.262/4	Shtrese betoni C 16/20 t=10 cm (kunete)	m ³	16		
7	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	45		
					Shuma I	
II-PUNIME NDRIÇIMI						
1	3.654	F.V Tuba Plastik Ø100	ml	242		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	9		
3	3.59/a	Germim themel i vecuar, gropa sip. 10-30 m ² , toke te bute me h=1.5 m	m ³	2		
4	2.262/3	Shtrese betoni C 12/15 per fiksimin e shtylles metalike	m ³	2		
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	9		
6	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	9		
7	AN	FV Ndricules LED 100W	cope	9		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	9		

9	4.142/3.15	F.V.kabllo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm2	ml	90		
10	4.131/3.7	F.V.ne toke kabllo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm2	ml	242		
					Shuma II	
III-PUNIME K.U.B						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	182		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	182		
3	2.258	Shtrese zhavori nen tubo t=20cm	m ³	24		
4	3.An /1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	242		
5	An-22/1	Pusetete b/a shiu 40 x 40, h = 100 cm, me kapak gize cdo20m	copë	13		
6	An/164/b	Mbushje kanali me cakull + ngjeshje	m ³	108		
					Shuma III	
IV-TABELA RRUGORE E VIJEZIME						
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	5		
2	An151	Vizime me boje bikomponente	m ²	30		
3	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	484		
					Shuma IV	
					SHUMA 5	
6.SEGMENTI I RRUGES GJELBERIMIT L=90ml B=4ml ASFALLT +0.5 KUNETA NE NJEREN ANE TE RRUGES						
	Nr analiz	EMERTIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
I-PUNIME NE RRUGE						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	41		
2	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	400		
3	3.212/b	Shtrese stabilizanti t=10cm	m ²	400		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m ²	360		
5	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	360		
6	2.262/4	Shtrese betoni C 16/20 t=10 cm (kunete)	m ³	6		
7	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	18		
					Shuma I	
II-PUNIME NDRIÇIMI						
1	3.654	F.V Tuba Plastik Ø100	ml	100		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	3		
3	3.59/a	Germim themel i vecuar, gropa sip. 10-30 m ² , toke te bute me h=1.5 m	m ³	0.75		
4	2.262/3	Shtrese betoni C 12/15 per fiksimin e shtylles metalike	m ³	0.75		
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	3		
6	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	3		
7	AN	FV Ndrices LED 100W	cope	3		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	3		
9	4.142/3.15	F.V.kabllo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm2	ml	30		
10	4.131/3.7	F.V.ne toke kabllo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm2	ml	100		
					Shuma II	
III-PUNIME K.U.B						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	20		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	20		
3	3.244	Struktura monolite betoni C 20/25 (VESHJE KANALI)	m ³	21		
4	3.244	Struktura monolite betoni C 20/25 (VESHJE KANALI)	m ³	6		
5	2.167	F V hekur betoni periodik Ø > 10 mm	ton	2.8		
					Shuma III	
IV-TABELA RRUGORE E VIJEZIME						
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	2		

2	An151	Vizime me boje bikomponente	m ²	8		
3	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	200		
					Shuma IV	
					SHUMA 6	
					SHUMA 1-6	
					Fond.Rez.5%	
					SHUMA	
					TVSH 20%	
					TOTALI	

Ing.Ariola Beqo
Ing.Ersi Veliu
Ing.Arben Muca
Ing.Garni Myzeqari
Ark.Alban Manoku

Sektori i Projektimit
Ark. Alban Manoku

Drejtoria e Planifikimit dhe Zhvillimit te Territorit
Ing.Mimoza Haxhiu