

PREVENTIV

Objekti : "Sistemim asfaltim rruga per tek varrezat Koplík "

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
PUNIME PER RRUGEN						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , toke zak, kategoria III, me shk ne mjet	m ³	172.00	-	-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	172.00	-	-
3	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	22	-	-
4	3.212/b	Shtrese stabilizanti 10cm per rrugen	m ²	715	-	-
5	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	715	-	-
6	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	572.0	-	-
7	3.240	Struktura monolite betoni C 12/15 kunete	m ³	14.0	-	-
8	3.An/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	6.5	-	-
Shuma 1					-	-
PUNIME PER PARKIMIN (20 m x 51 m)						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	179.64	-	-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	179.64	-	-
3	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	45	-	-
4	3.212/b	Shtrese stabilizanti 10cm per rrugen	m ²	1,020	-	-
5	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	1,020	-	-
6	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	1,020	-	-
Shuma 1					-	-
SHUMA					-	-
TVSH 20%					-	-
TOTAL					-	-

**PREVENTIVOI
"Novatech Studio"shpk
Ing.Emil Nova**