

**PREVENTIV**

**Objekti :Sistemim asfaltim rruga Pojate e Siperme**

<b>Nr</b>	<b>Nr AN</b>	<b>EMERTIMI I PUNIMEVE</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Cmimi</b>	<b>Vlera</b>
		<b>PUNIME NE TRUP TE RRUGES</b>				
1	3.89/a	Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m <sup>3</sup>	293.0	-	-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	293.0	-	-
3	3.212/b	Shtrese stabilizanti 10cm per rrugen	m <sup>2</sup>	853.0	-	-
4	3.205/2	Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri	m <sup>2</sup>	853.0	-	-
5	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m <sup>2</sup>	745.0	-	-
6	3.240	Struktura monolite betoni C 12/15 (kuneta)	m <sup>3</sup>	15.0	-	-
7	3.243	Struktura monolite betoni C 16/20 (bordura,trot)	m <sup>3</sup>	20.0	-	-
8	3.205	Shtrese zhavori lumi t=10cm, perhapur e ngjeshur me makineri (trotuare)	m <sup>2</sup>	80.0	-	-
9	3.237	Struktura monolite b/betoni C 12/15 me 20% gur	m <sup>3</sup>	15.0	-	-
		<b>VEPRA ARTI ( PUNIME PER UREN)</b>				
1	3.89/a	Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m <sup>3</sup>	12.0	-	-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m <sup>3</sup>	12.0	-	-
3	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	6.5	-	-
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.30	-	-
5	2.181	Konstruksione metalike te perbera	ton	1.2	-	-
6	2.401	Boje vaji siperfaqe metalik	m <sup>2</sup>	120.0	-	-
7	3.245	Struktura monolite betoni C 25/30	m <sup>3</sup>	25.0	-	-
8	M.2 An - 6	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	66.0	-	-
9	An99	Tabele rrethi "detyrim" e vogel me D = 40	cope	2.0	-	-
		<b>SHUMA</b>				-
		<b>TVSH 20%</b>				-
		<b>TOTAL</b>				-