

**PREVENTIV**

**MIRATOHET:  
KRYETARI I BASHKISE DROPULL  
DHIMITRAQ TOLI**

**OBJEKTI: "MBROJTJA NGA PERROI I SELOSE, DROPULL (FAZA E I)"**

Nr.	Nr.An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi(lek)	Vlera (lek)
<b>1.-Punime ne ure</b>						
1		Guardrail H4 anesore per ure me 3 vale ne 1 ane ,W5(elementi+ lart) + aksesoret	ml	30.00		-
					<b>SHUMA I</b>	-
<b>2.-PUNIME SHITESASH RRUGORE</b>						
1		Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk	m3	1,149.95		-
2		Germim shkemb mesatar me çekiq me ekskavator me zinxhir	m3	334.00		-
3		Transport dheu me auto deri 5.0 km	m3	1,483.95		-
4		Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m3	2,950.00		-
5		Shtrese stabilizant t=10cm	m2	2,950.00		-
6		Skarifikim shtrese asfalti me makineri	m2	100.00		-
7		Shtrese binderi me granil gur kave,5cm,me makineri	m2	2,950.00		-
8		Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m2	3,050.00		-
					<b>SHUMA II</b>	-
<b>3.-PUNIME NE MURET ANESORE</b>						
1		Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne kanale gjeresi > 2 m, prani uji, kategoria III, me shk	m3	4200		-
2		F V hekur betoni I zakonshem Ø 6 - 10 mm	ton	2		-
3		F V hekur beton I zakonshem Ø >12	ton	2		-
4		Struktura monolite betoni C 20/25	m3	66		-
5		Gabiona me rrjete teli te zinguar e gure kave 1x1x1	m3	320		-
6		Gabiona me rrjete teli te zing, gure kave 1x2x1.5m	m3	480		-
7		Gabiona me rrjete teli te zinguar, gure kave 1x2x2 m	m3	1280		-
8		Gabiona me rrjete teli te zinguar, gure kave 1x1x2 m	m3	320		-
9		Mbushje me zhavorr pas mureve	m3	620		-
					<b>SHUMA III</b>	-
		<b>SHUMA (1+2+3)</b>				-
		<b>Fond rezerve 5%</b>				-
		<b>SHUMA PA TVSH</b>				-
		<b>TVSH 20 %</b>	20%			-
		<b>Shuma Totale</b>				-
<p><b>PREVENTIVOI</b>  <b>Studio "ZENIT &amp; CO" SH.P.K</b>  <b>ADMINISTRATORI</b>  <b>Ing. ARQILE PERI</b></p>						