



GREEN MARKET BASHKIA - BERAT						
PREVENTIVI I PUNIMEVE						
Nr	Nr. i an.	Emertimi i Punimeve	Njësia	Sasia	Cmimi	Total
A-Punime per lirim dhe pastrimin e sheshit						
1	3.101/a	Germim dheu me ekskavator goma 0.50 m ³ , ne kanale gjeresi deri 2 m, toke zak, kat III, me shkarkim ne mjet	m ³	2,800		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	1,400		
3	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	1,400		
4	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	4000		
5	3.212/b	Shtrese stabilizant t=10 cm	m ²	4000		
6	3.222/1	Shtrese binderi me granil gur kave, 5 cm, me makineri	m ²	4000		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	4000		
E-Punime te Kullimit te ujrave siperfaqesore						
1	3.101/a	Germim dheu me ekskavator goma 0.50 m ³ , ne kanale gjeresi deri 2 m, toke zak, kat III, me shkarkim ne mjet	m ³	450		
2	An.9	Mbushje me zhavorr	m ³	150		
3	An - 22	Pusetet b/a shiu 40 x 40 cm, h = 100 cm, me kapak zgare hekuri	cope	12		
4	An	F.V tuba te brinjezuar HDPE SN8 d=200 mm	ml	180		
B-Punime per ndertimin e rruges						
1	3.245	Ndertim mure Struktura Monolite Betoni C25/30	m ³	47		
2	3.242	Struktura monolite betoni C 12/15	m ³	55		
3	3.288	F V hekur betoni I zakonshem Ø > 12mm/Steel bars Ø > 12mm	ton	1.30		
4	An-8	Mbushje me cakell pas mureve	m ³	50		
5	An-55	F.V tub drenazhi Ø150 mm	m	350		
D-Punime Trotuari dhe per Hapesirat						
1	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	400		
2	3.212/d	Shtrese stabilizant t=20 cm	m ²	400		
3	3.617/1	F V bordura betoni 15x30 cm	m	400		
4	3.243	Struktura monolite betoni C 16/20 (per kuneten dhe bordurat)	m ³	25		
5	An.3.27	Mbushje dhe pasurim me dhe vegjetal	m ³	18		
6	An164	F.V. Fidane Peme dekorative	cope	20		
E-Ndertimi i argjinatures						
1	3.101/a	Germim dheu me ekskavator zingjir 0.5 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria IV, me shk ne toke	m ³	700		
2	An 1	Mbushje e ngjeshje me dhe' e zhavor e argjinatures me shtresa cdo 20-30cm (analize per 1m3)	m ³	150		
3	3.161	Rrafshim skarpate ne germim, ekskavator 1 m ³	m ²	4000		
4	Anal. 2	F+v. tombino b/arme d=150cm	ml	20		
5	3.244	Beton C16/20 per tombinon, muret e shtresat, kalimi tubo 150cm	m ³	18		
6	3.97/b	Germim dheu me eskavator me zinxhir 0.25 m ³ per mbrojtjen	m ³	300		
7	Anal. 5	Mbushje + ngjeshje me dhe' e zhavor pas gabionave	m ³	200		
8	3.332	Gabiona me rrjete teli te zinguar, gure kave 1x1x1.5 m	m ³	140		
9	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m ³	140		
10	3.240	Struktura monolite betoni C 12/15 mbi Gabion	m ³	16		
G-Sinjalizimet dhe siguria rrugore						
1	An48	Tabele katrore normal me A=60	cope	2		
2	An100	Tabele rrethi "detyrim" normal me D = 60	cope	2		
3	An103	Tabele rrethi "ndalim" normal me D = 60	cope	2		
5	An121	Pervijues special pengesash per ishuj trafikue dhe ndares trafiku	cope	2		
6	An142	Boje bikomponente (sprajt) per kalimtare	m ²	20		
7	An64	Sinjalet e drejtim urban HxL normal 25x125	cope	2		
8	An122	Vijeze shirita gjatesor dhe anesor me gjeresi 12 cm. Bikomponente (sprajt)	m	300		
SHUMA 1+2+3+...8						
TVSH 20 %						
SHUMA TOTALE						

Hartoi :
Lucjano Bojaxhiu

MIRATOHET
KRYETARI I BASHKISE
ERVIN DEMO