



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

Ndertim rruget Blloku 2 Babrru Koder "Mihal Grameno", "Shtejfen Gjecovi", "Vojo Kusho", "Vicens Prenushi", "Pingul Konferenca e Mukjes" Ltot= 1131 ml

Objekti: Ndertim Rruga Mihal Grameno "Babrru Koder e Kuqe" B=7m ,(basf= 4.5 ml+ 1x0.5 kub+ 2x1.0 trotuar)

A		B=6 , asfalt 4.5+kunete 1x0.5 m + trotuare 1x1 m			L1=	300
		B=5 , asfalt 4.5+kunete 1x0.5 m +L3=60ml			L2=	234
	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	480.6		
2	3.158/5a	Transport dheu me auto 5km	m ³	480.6		
3	An. 8	Mbushje me çakell shkembor	m ³	264.3		
4	3.211	Shtrese çakelli T=20cm	m ²	2643		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2643		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	2643		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	2643		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	288.0		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	8.64		
10	An.	Ngritje pusete+kapak gize	cope	6		
11	An.	Spostim shtyllash	cope	8		
12	2/426/2	Prishje mure me blloqe + transport	m ³	240		
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	1368		
14	An.96	Tabele sinjalistike 60-90cm	cope	6		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	213.6		
2	3.158/5a	Transport çakelli me auto 5km	m ³	213.6		
3	3 An. 8	Mbushje me çakell shkembor	m ³	106.8		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	534		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	53.4		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	18.00		
SHUMA II						
III PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	120		
2	3.158/5a	Transport çakelli me auto 5km	m ³	120		
3	3 An. 8	Mbushje me çakell shkembor	m ³	60		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	300		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	7.00		
SHUMA III						
IV PUNIME TROTUAR(1x1 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	40.50		
2	3.158/5a	Transport dheu me auto 5km	m ³	40.50		
3	3 An. 8	Mbushje me çakell shkembor	m ³	40.50		
4	3.208	Shtrese çakelli T=10cm	m ²	270.0		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	255.0		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	600		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	18		
8	2.109/2	Shtrese betoni trotuari	m ³	27		

SHUMA IV						
V PUNIMET VEPRRA ARTI(MURE MBAJTESE)						
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	60		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	60		
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	120		
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.60		
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.7		
SHUMA IIV						
VI PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	300		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndrçimin	ml	300		
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	12		
4	3.139	Germime dheu me ekskavator me goma	m ³	60		
5	3.158/5a	Transport dheu me auto 5km	m ³	60		
6	2.261	Mbushje me rere	m ³	24		
7	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	36		
SHUMA VI						
SHUMA A						
OBJEKTI : Ndertim Rruga "Rruga Shtjefen Gjecovi", " Babrru qender , Bashkia Kamez L=175 m , B=5m , (basf= 4.5 ml+ 1x0.5 kunet						
B					L=	175
	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	157.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	157.5		
3	An. 8	Mbushje me çakell shkembor	m ³	78.75		
4	3.211	Shtrese çakelli T=20cm	m ²	787.5		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	787.5		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	787.5		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	787.5		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	65.63		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.64		
10	An.	Ngritje pusete+kapak gize	cope	3		
11	An.	Spostim shtyllash	cope	4.38		
12	2/426/2	Prishje mure me blloqe + transport	m ³	105		
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	525		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	70		
2	3.158/5a	Transport çakelli me auto 5km	m ³	70		
3	3 An. 8	Mbushje me çakell shkembor	m ³	35		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	175		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	8.75		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	5.00		
SHUMA II						
III PUNIME TROTUARE(0)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	350		
2	2/262/4	Beton per fiksime bordure C16/20	m ³	10.5		
SHUMA III						
IV PUNIME VEPRRA ARTI						

1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	35		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	35		
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	123		
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.61		
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.7		
		SHUMA IV				
V		PUNIME PER NDRICIMIN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	175		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	175		
3	An.	F.V kasete shperndarese	cope	1		
4	3.139	Germime dheu me ekskavator me goma	m ³	35		
5	3.158/5a	Transport dheu me auto 5km	m ³	35		
6	2.261	Mbushje me rere	m ³	14		
7	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	21		
		SHUMA V				
		SHUMA B				
OBJEKTI : Ndertim Rruga "Vojo Kushi " Fush-Kerçik , Bashkia Kamez						B=6m , (basf=
4.5 ml+ 1x0.5 kunet+ 2x0.75 trotuar)						
C		B=6 , asfalt 4.5+kunete 1x0.5 m + trotuare 1x1 m			L1=	232
		B=5 , asfalt 4.5+kunete 1x0.5 m			L2=	194
	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	354.3		
2	3.158/5a	Transport dheu me auto 5km	m ³	354.3		
3	An. 8	Mbushje me çakell shkembor	m ³	172.3		
4	3.211	Shtrese çakelli T=20cm	m ²	1723		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1723		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1723		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	1723		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	184.00		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4.60		
10	An.	Ngritje pusete+kapak gize	cope	7		
11	An.	Spostim shtyllash	cope	5.80		
12	2/426/2	Prishje mure me blloqe + transport	m ³	139.2		
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	1084		
14	An.96	Tabele sinjalistike 60-90cm	cope	8		
		SHUMA I				
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	170.4		
2	3.158/5a	Transport çakelli me auto 5km	m ³	170.4		
3	3 An. 8	Mbushje me çakell shkembor	m ³	85.2		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	426		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	11.6		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	8.00		
		SHUMA II				
III		PUNIME KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	276.9		
2	3.158/5a	Transport çakelli me auto 5km	m ³	276.9		
3	3 An. 8	Mbushje me çakell shkembor	m ³	138.45		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	426		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5.00		
		SHUMA III				

IV	PUNIME TROTUARE(1x1m)				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	58.00	
2	3.158/5a	Transport dheu me auto 5km	m ³	58.00	
3	3 An. 8	Mbushje me çakell shkembor	m ³	60.90	
4	3.208	Shtrese çakelli T=10cm	m ²	232.0	
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	406.00	
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	852	
7	2/262/4	Beton per fiksime bordure C16/20	m ³	25.56	
8	2.109/2	Shtrese betoni trotuari	m ³	23.2	

SHUMA IV

V	PUNIME VEPRRA ARTI (MURE MBAJTESE)		NJESIA	SASIA	
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	46	
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	46	
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	139	
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	6.96	
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.8	

SHUMA V

VI	PUNIME PER NDRICIMIN				
----	----------------------	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	426	
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	426	
3	3.an/1sh	F.V. Shtylla metalike konike ndriçimi H-9m PAICC-3	cope	12	
4	3.an/ksh	F.V. Krah shtylla metalike KRH-MSI 1500/1500/10	cope	12	
5	An	F.V Ndricues Led 94W	cope	12	
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen	cope	12	
7	An	F.V Elektroda tokezim komplet l=150m	cope	12	
8	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk)	ml	426	
9	An	F.V kabell tokezimi 1x3.5mmk	ml	18	
10	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	1	
11	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	12	
12	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1	
13	An.	F.V kuader komandimi per ndriçim rrugor	cope	1	
14	An.	F.V kasete shperndarese	cope	1	
14	3.139	Germime dheu me ekskavator me goma	m ³	85.2	
14	3.158/5a	Transport dheu me auto 5km	m ³	85.2	
14	2.261	Mbushje me rere	m ³	34.08	
14	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	51.12	

SHUMA VI

SHUMA C

OBJEKTI : Ndertim Rruga " Viçens Prenushi " Fush-Kerçik , Bashkia Kamez B=6m , (basf= 4.5 ml+ 1x0.5 kunet+ 1x1 trotuar)

D					L=	131
	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera

PUNIME NE RRUGE

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	117.9	
2	3.158/5a	Transport dheu me auto 5km	m ³	117.9	
3	An. 8	Mbushje me çakell shkembor	m ³	58.95	
4	3.211	Shtrese çakelli T=20cm	m ²	589.5	
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	589.5	
6	3.222/2	Shtrese binderi 1x6 cm	m ²	589.5	
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	589.5	
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	58.95	
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.47	
10	An.	Ngritje pusete+kapak gize	cope	7	
11	An.	Spostim shtyllash	cope	3.28	
12	2/426/2	Prishje mure me blloqe + transport	m ³	78.6	

13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	393		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	54.4		
2	3.158/5a	Transport çakelli me auto 5km	m ³	54.4		
3	3 An. 8	Mbushje me çakell shkembor	m ³	27.2		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	136		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	6.55		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	3.74		
SHUMA II						
III PUNIME KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	85.2		
2	3.158/5a	Transport çakelli me auto 5km	m ³	85.15		
3	3 An. 8	Mbushje me çakell shkembor	m ³	51.09		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	131		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5.00		
SHUMA III						
IV PUNIME TROTUARE(2x0.75 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	22.93		
2	3.158/5a	Transport dheu me auto 5km	m ³	22.93		
3	3 An. 8	Mbushje me çakell shkembor	m ³	2.95		
4	3.208	Shtrese çakelli T=10cm	m ²	229.25		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	19.65		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	262		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	7.86		
8	2.109/2	Shtrese betoni trotuari	m ³	22.925		
SHUMA IV						
V PUNIME VEPRRA ARTI(Mure mbajtese)						
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	26		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	26		
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	96.7		
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.58		
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.6		
SHUMA 6						
VI PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	131		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	131		
11	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	7		
15	3.139	Germime dheu me ekskavator me goma	m ³	26.2		
16	3.158/5a	Transport dheu me auto 5km	m ³	26.2		
17	2.261	Mbushje me rere	m ³	10.48		
18	8	Mbushje me cakull shkembor (kanal)	m ³	16.07		
SHUMA VI						
SHUMA D						

**OBJEKTI : Ndertim Rruga " Sulejman Vokshi segment " Babrru Shpat , Bashkia Kamez
B=4-4.2m , (basf=3.5-4.2 ml+ 1x0.5 kunet)**

D					L=	154
	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	132		
2	3.158/5a	Transport dheu me auto 5km	m ³	132		
3	An. 8	Mbushje me çakell shkembor	m ³	78		

4	3.211	Shtrese çakelli T=20cm	m ²	780	
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	780	
6	3.222/2	Shtrese binderi 1x6 cm	m ²	780	
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	780	
####	An.	Ngritje pusete+kapak gize	cope	2	
####	An.	Spostim shtyllash	cope	4.00	
####	2/426/2	Prishje mure me blloqe + transport	m ³	0	
####	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	308	
####	An.96	Tabele sinjalistike 60-90cm	cope	4	
SHUMA I					
II	PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	53.72	
2	3.158/5a	Transport çakelli me auto 5km	m ³	53.72	
3	3 An. 8	Mbushje me çakell shkembor	m ³	26.86	
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	154	
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	7.7	
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	4.00	
SHUMA II					
III	PUNIME KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	80.0	
2	3.158/5a	Transport çakelli me auto 5km	m ³	80	
3	3 An. 8	Mbushje me çakell shkembor	m ³	48	
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	154	
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5.0	
SHUMA III					
				Shuma	

**OBJEKTI : Nderitim Rruga "Pingul me Rrugen Koferenca e Mukjes " Babrru Koder e kuqe , Bashkia Kamez
(L=150ml,basf= 7.5ml)**

E						L=	150
	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera	
I	PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA			
1	3.139	Germim dheu me eskavator	m ³	45			
2	3.158/5a	Transport dheu me auto 5km	m ³	45			
3	An. 8	Mbushje me çakell shkembor	m ³	60			
4	3.211	Shtrese çakelli T=20cm	m ²	1125			
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1125			
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1125			
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1125			
8	An.	Ngritje pusete+kapak gize	cope	4			
9	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)	ml	300			
10	An.96	Tabele sinjalistike 60-90cm	cope	4			
SHUMA I							
SHUMA E							
SHUMA (A-E)							
TVSH 20%							
TVSH TOTALE							

Preventivues :

Ing. Hajredin MURGU



Drejtori i Pergjithshem

Z.Elvis Gjika



Drejtori P.I-se

Ing. Flora MUÇA


