



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

NDERTIM I RRUGEVE MUSTAFA XHANI DHE NDREKO RINO , BABRRU KODER E KUQE , PASKUQAN

OBJEKTI : Ndertim Rruga "Rruga Mustafa XHANI " Babrru Koder , Bashkia Kamez L=585 m B=7 m , Basfalt = 4.5 m + Kunete 1x0.5 m + Trotuare 1x1.3 + 1x0.7 m

L= 585

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	qemal jusufati
1	3.139	Germim dheu me eskavator	m ³	921.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	921.4		
3	An. 8	Mbushje me çakell shkembor	m ³	403.65		
4	3.211	Shtrese çakelli T=20cm	m ²	2691		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2691		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	2691		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	2691		
8	3.246	Struktura monolite betoni me çakell C 20/25	m ³	131.6		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4.61		
10	An.	Ngritje pusete+kapak gize	cope	3		
11	An.	Spostim shtyllash	cope	14.63		
12	2/426/2	Prishje mure me blloqe + transport	m ³	351		
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)(bardh e kuq)	ml	1755		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
		SHUMA I				
II	PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	234		
2	3.158/5a	Transport çakelli me auto 5km	m ³	234		
3	3 An. 8	Mbushje me çakell shkembor	m ³	117		
4	3.an/1t	F.V. Tuba I brinjzuar Ø 315	ml	585		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	29.25		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	20.0		
		SHUMA II				
II	PUNIME KUN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	380.3		
2	3.158/5a	Transport çakelli me auto 5km	m ³	380.25		
3	3 An. 8	Mbushje me çakell shkembor	m ³	190.125		
4	3.an/1t	F.V. Tuba I brinjzuar Ø 315	ml	585		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	12.0		
		SHUMA II				
III	PUNIME TROTUARE(1x1.3+1x0.7 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	271		
2	3.158/5a	Transport dheu me auto 5km	m ³	271		
3	3 An. 8	Mbushje me çakell shkembor	m ³	162		
4	3.208	Shtrese çakelli T=10cm	m ²	1082		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	1082		
6	3.617	F.V. Bordura betoni e parapregatitur C 20/25 15x25 cm	ml	1170		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	35.1		

8	2.109/2	Shtrese betoni trotuari	m ³	108.225		
SHUMA III						
6. PUNIME VEPRA ARTI (MURE MBAJTESE)						
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	117		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	117		
3	3.246	Struktura monolite betoni me çakell C 20/25	m ³	293		
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	2.34		
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	3.5		
SHUMA 6						
IV						
PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	585		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndrçimin	ml	585		
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	20		
4	3.139	Germime dheu me ekskavator me goma	m ³	117		
5	3.158/5a	Transport dheu me auto 5km	m ³	117		
6	2.261	Mbushje me rere	m ³	46.8		
7	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	70.2		
SHUMA IV						
SHUMA A						
OBJEKTI : Ndertim Rruga "Rruga Ndreko Rino " Babrru Koder , Bashkia Kamez L= 400 m B= 6.3 m , Basfalt = 4.0 m + Kunete 2x0.5 m + Trotuare 1x1.3 m						

L= 400

B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	574		
2	3.158/5a	Transport dheu me auto 5km	m ³	574		
3	An. 8	Mbushje me çakell shkembor	m ³	164		
4	3.211	Shtrese çakelli T=20cm	m ²	1600		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1600		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1600		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1600		
8	3.246	Struktura monolite betoni me çakell C 20/25	m ³	150.00		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	5.25		
10	An.	Ngritje pusete+kapak gize	cope	4		
11	An.	Spostim shtyllash	cope	10.00		
12	2/426/2	Prishje mure me blloqe + transport	m ³	240		
13	An.152	Vizime me boje bikomponente 15cm(gjatesore+kembesore)(bardh e kuq)	ml	1200		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
SHUMA I						
II						
PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	160		
2	3.158/5a	Transport çakelli me auto 5km	m ³	160		
3	3 An. 8	Mbushje me çakell shkembor	m ³	80		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	400		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	40		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	15.00		
SHUMA II						
II						
PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	160		
2	3.158/5a	Transport çakelli me auto 5km	m ³	160		
3	3 An. 8	Mbushje me çakell shkembor	m ³	80		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	400		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	12.00		

SHUMA II						
PUNIME TROTUARE(1x1 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m³	68		
2	3.158/5a	Transport dheu me auto 5km	m³	68		
3	3 An. 8	Mbushje me çakell shkembor	m³	34		
4	3.208	Shtrese çakelli T=10cm	m²	340		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m²	340		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	800		
7	2/262/4	Beton per fiksim bordure C16/20	m³	24		
8	2.109/2	Shtrese betoni trotuari	m³	34		
SHUMA III						
6. PUNIME VEPRA ARTI (MURE MBAJTESE)						
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m³, ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjete	m3	45		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	45		
3	3.246	Struktura monolite betoni me çakell C 20/25	m3	55		
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.23		
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.3		
SHUMA 6			ton			
IV						
PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	400		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndrçimin	ml	400		
3	3An/55	F.v pusea elektrike kontrolli PVC 40x40 x40	cope	8		
4	3.139	Germime dheu me ekskavator me goma	m³	80		
5	3.158/5a	Transport dheu me auto 5km	m³	80		
6	2.261	Mbushje me rere	m³	32		
7	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m³	48		
SHUMA IV						
SHUMA B						
SHUMA A+B						
TVSH 20%						
TVSH TOTALE						

Preventivues :
Ing. Hajredin MURGU

Drejtori i Pergjithshem
Z.Elvis Gjika

Drejtori P.I-se
Ing. Flora MUÇA

MIRATOI
Rakip SULI

KRYETAR

