

Objekti: Preventiv Rruga Erzeni i vjeter, Vau i Grave, Katundi Ri
Rikonstuksion rruga Erzeni i vjeter, Vau i Grave, Katundi Ri L=821ml

PREVENTIV PUNIMESH

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA	ÇMIMI	VLEFTA
		1. PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	100		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	80		
		SHUMA 1:				
		2. PUNIME NE RRUGE DHE PUNIME SHITESASH				
4	3.212/b	Shtrese stabilizant t=10cm	m2	2463		
5	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri,per bankinat	m3	82		
6	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	2463		
7	3.233/1	Shtrese asfaltbetoni me zall lavatrice,4cm,me mak	m2	2463		
		SHUMA 2:				
Shuma 1+2						
TVSH (20%)						
Totali						

Punoi: Ing. Lorenc Facja
Ing. Eni Turkeshi
Ark.Alba Kokomani
Ing.Jetmir Kurti

Jetmir
Kurti

Digitally signed by
Jetmir Kurti
Date: 2024.04.19
13:03:02 +02'00'

Eni
Turkeshi

Digitally signed by Eni
Turkeshi
Date: 2024.04.22
11:51:35 +02'00'

Alba

Digitally signed by
Alba Kokomani
Date: 2024.04.22
13:29:12 +02'00'