

PREVENTIV

PROJEKTI: "Ndertim i Sheshit te Bashkise Malesi e Madhe"						
Nr	Nr Analiz	Pershkrimi i zerit	Njesi	Sasia	Cmimi	Shuma ne Lek
PERMBLEDHJE						
1		TOTALI (1-4)				
2						
3		Shuma - 2				
4		TVSH 20%				
5		SHUMA TOTALE E NDERTIMIT				
I - PUNIME PRISHJE						
1	2.426/3	Prishje shtresa betoni	m ³	23.00	-	-
2	3.89/b	Germim toke e zakonshme	m ³	128.00	-	-
3	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	128.00	-	-
					Shuma 1	-
II - Sheshe dhe Kalime Kembesoresh						
1	An 8/M3	Shtrese Cakelli (2x10)cm	m ³	180.00	-	-
2	AN	Pllaka guri Sheshi t=5cm	m ²	661.50	-	-
3	3.628	Llac nen pllaka, t=2cm	m ²	661.50	-	-
4	3.244	Beton C 20/25, t=10-15cm	m ³	119.00	-	-
5	3.287	F.V Hekur	ton	2.55	-	-
6	3.616	F.v bordure betoni 12x25	ml	125.00	-	-
7	AN	Kornize +zgare kanali e zinkuar	ml	25.00	-	-
8	3.242	Beton C12/15	m ³	1.80	-	-
9	3.An/2t	Tub HDPE Ø400mm	ml	16.00	-	-
10	2.520	Tub PVC Ø110mm	ml	13.00	-	-
11	2.261	F.V. Rere	m ³	5.00	-	-
12	An22/M2	Pusete b/a shiu 40 x 40 cm, h = 100 cm	cope	3.00	-	-
					Shuma 2	-
III- PUNIME PER NDERTIMIN E NDRICIMIT RRUGOR						
1	AN	F.V. Shtylle metalike H=5.8m, dekorative	cope	5.00	-	-
2	AN	Ndriçues Spot	cope	14.00	-	-
3	AN	F.V. Kabell FG7OR 0.6/ 1KV. 5x16mm2	ml	3.00	-	-
4	AN	F.V. Kabell FG7OR 0.6/ 1KV. 5x10mm2	ml	130.00	-	-
5	2.519	Tub I brinjezuar Ø 90 mm	ml	130.00	-	-
6	An/M3	F.V kuader Komandimi	cope	1.00	-	-
					Shuma 3	-
IV- PUNIME GJELBRIMI						
1	AN	F.V. Dhe humosor per mbushje	m3	48.44	-	-
2	An 164/M-3	F.V. Fidane Peme dekorative (magnolia & acacia dealbata)	cope	14.00	-	-
3	An	Stol urban	cope	4.00	-	-
					Shuma 4	-

InfraKonsult
 Drejtuesi Ligjor
 Ing. Redi STRUGA