



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

Nr _____ Prot.

Kamez me ___/___/2017

PREVENTIV

Ndertim Rruge Dede Gjon Luli + Seg. Arben Broci , Rruga Asim Vokshi ne kufi me Nj. Bashkiake nr.11 Tirane + Rruga Abaz Ermenji + Ndertim seg. Rruga Ajet Xhindoli Paskuqan 2

NDERTIM RRUGA "Dede Gjon Luli+ Seg. Arben Broci " , Paskuqan 2 , Nj.Ad. Paskuqan , B. Kamez	
<i>Rruga L= 600 m, B= 7 m Basfalt= 5 m, beton 1x0.4 m, bankine 1x1 m</i>	

2017

NR	ANALIZ.	EMERTIMI I PUNIMIT	Njesi	Sasia	Çmimi	Vlefte
I. Punime ne rruge dhe degezime B=7.0 m , l=600 m						
1	3.139	Germim dheu me eskavator	m ³	265		
2	3.158/5a	Transport dherash me auto 5 km	m ³	265		
3	3.353	Mbushje Çakull Shkemb	m ³	862		
4	3.208	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	3,237		
5	3/212/6	Shtrese stabilizanti 10 cm	m ²	3,000		
6	3.229/1	Shtrese binderi 5 cm + Sperkatje me emulsion	m ²	3,000		
7	3.233/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	3,000		
8	An	Spostim Shtyllash Elektrike	cop	12		
9	An	Spostim Gabine	cope	1		
10	2/426/2	Prishje Avllie	m ³	112		
11	An	Ngritje Pusete me kapak gize + Riparime Pusete	cope	14		
12	An	Heqje Tubin nga Kanali O 1000mm	ml	50		
13	An	Vendosje b/a Ø 1000 mm	m	25		
14	2.558	F.V tuba b/a Ø 1000 mm	m	10		
15	2/262/4	Beton per anesore C 16/20	m ³	103		
Shuma I						

NDERTIM RRUGA " Abaz Ermenji " , Paskuqan 2 , Nj.Ad. Paskuqan , B. Kamez

Rruga L= 530 m, B=6 m Basfalt=4m, baNKIN 2x1 m

NR	ANALIZ.	EMERTIMI I PUNIMIT	Njesi	Sasia	Çmimi	Vlefte
I. Punime ne rruge dhe degezime B=5 m , l=530 m						
1	3.139	Germim dheu me eskavator	m ³	170		
2	3.158/5a	Transport dherash me auto 5 km	m ³	170		
3	3.353	Mbushje Çakull Shkemb	m ³	240		
4	3.158/5a	Transport çakull me auto 5 km	m ³	240		
5	3.208	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	2,650		
6	3/212/6	Shtrese stabilizanti 10 cm	m ²	2,650		

7	3.229/1	Shtrese binderi 5 cm + Sperkatje me emulsion	m ²	2,120		
8	3.233/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	2,120		
9	An	Spostim Shtyllash Elektrike	cop	12		
10	2/426/2	Prishje Avllie	m ³	126		
11	2.110/2	Mure betoni + Bordura anesor te preg. ne vend	m ³	42		
Shuma I						
PUNIME K.U.N						
1	3.139	Germim dheu me eskavator	m ³	180		
2	3.158/5a	Transport dherash me auto 5 km	m ³	180		
3	3.353	Mbushje me Çakull	m ³	120		
4	3.158/5a	Transport çakull me auto 5 km	m ³	120		
5	2.554	F V tuba betoni O 400 mm	ml	120		
6	2.575	Pusete kontrolli me kapak gize 1x1x1.5 m	cop	3		
Shuma IV						
Shuma Totale e Abaz Ermenji (I+II)						

NDERTIM KOLEKTORI DHE RRUGA " ASIM ZENELI " , Paskuqan 2 , Kufiri ndarese me Bashkine Tirane

NR	NR. ANALIZ.	EMERTIMI I PUNIMIT	Njesi	Sasia	Çmimi	Vlefte
ne ne rruge Asim Zeneli dhe degezime B= 9m , l= 390 m basflt = 5 , + bankine 2x2m						
1	0.022	Germim dheu me eskavator	m ³	650		
2	3.158/5a	Transport dherash me auto 5 km	m ³	650		
3	3.353	Mbushje Çakull Shkemb (t=20 cm)	m ³	390		
4	3.158/5a	Transport çakull me auto 5 km	m ³	390		
5	3.617/1	F.V bordura betoni 15x30cm	ml	390		
6	3.238	Struktura monolite betoni, C-12/15, m Kundrabordure + kunete	m ³	98		
7	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	50		
8	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak gize	cope	8		
9	3.210	Shtrese çakelli t=15 cm, perhapur e ngjeshur me makineri	m ²	3,510		
10	3.187	Shtrese stabilizanti 10 cm	m ²	2,010		
11	3.229/1	Shtrese binderi 5 cm + Sperkatje me emulsion	m ²	2,010		
12	3.233/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	2,010		
Shuma I						
PUNIME KUN (Ujra te Larta + Ujra te Ndotura) O 1500, O 2000 ml 390 m,)						
1	2/426/2	Prishje Avllie	m ³	278		
2	3.139	Germim dheu me eskavator	m ³	2,560		
3	3.158/5a	Transport dherash me auto 5 km	m ³	2,560		
4	3.353	Mbushje me Çakull	m ³	1,890		
5	3.158/5a	Transport çakull me auto 5 km	m ³	1,890		
6	An	Heqje Tubin nga Kanali O 1500 -2000mm	ml	390		
7	An	Vendosje Tubi ne Kanal O1500- 2000 mm	ml	312		
8	2.560	F.V tuba b/a Ø 1500 mm	m	25		
9	An	F.V tuba b/a Ø 1500 mm	m	52		
10	An-3	Ndertim puseta betoni H=4-5m, 3.5x2.5m + kapak gize	cope	9		
Shuma II						

Shuma Totale e Rrugës (I+II)

NDERTIM RRUGA seg. " Ajet Xhindoli " deri tek Rruga abdyll Elmazi , Paskuqan 2 Vreshte ,
Rruga L= 192 m, B= 7 m Basfalt= 5 m, beton , bankine 2x1 m

NR	NR. ANALIZ.	EMERTIMI I PUNIMIT	Njesi	Sasia	Çmimi	Vlefte
I. Punime ne rruge dhe degezime B= 7.0 m , l=192 m						
1	3.139	Germim dheu me eskavator	m ³	134		
2	3.158/5a	Transport dherash me auto 5 km	m ³	134		
3	3.353	Mbushje Çakull Shkambi	m ³	134		
4	3.158/5a	Transport çakull me auto 5 km	m ³	134		
5	3.208	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	1,152		
6	3/212/6	Shtrese stabilizanti 10 cm	m ²	960		
7	3.229/1	Shtrese binderi 5 cm + Sperkatje me emulsion	m ²	960		
8	3.233/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	960		
9	An	Spostim Shtyllash Elektrike	cop	3		
10	2/426/2	Prishje Avllie	m ³	84		
11	An	Ngjitje Pusete me kapak gize	cope	10		
12	2/262/4	Beton per anesore C 16/20	m ³	14		
		Shuma I				
		Shuma I+II+III+IV				
			T. V. SH.			
			SHUMA			

Shenim: Preventivi eshte hartuar ne Baze te analizave te çmimeve me VKM nr.629 dt.15.07.2015

Preventivoi:

Ing.Hajredin MURGU

Ing. Elmaz MURATI

Ing. Armir ZERE

DREJTORI P.K.ZH.T-SE

Ark.Arber TOLA

**MIRATOI
Xhelal MZIU**

K R Y E T A R