

PREVENTIV

Objekti: "Rikon.i rruges kalaja Petralb, Rikon. rruga Gurre e vogel dhe ndertim ure Lela-Arriku"

Nr	Nr Analizes	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
I		RIKONSTRUKSION I RRUGES PETRALBE PJESA II				
1	3.87/B	Germim toke e forte me eskavator me zinxhire +hedhje ne toke	m ³	88.7		
2	3.124/1A	Germ. shkembimi mesatar, me cekic me eskavator me zinxhire	m ³	274.0		
3	3.124/2A	Germ. shkembimi forte, me cekic me eskavator me zinxhire	m ³	95.0		
		SHUMA I				
II		RIKONSTRUKSION RRUGA G.VOGEL , RRUGA CANI, CELAMI				
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , nivelim traseje gjeresi > 2 m, toke zak, kategoria IV, me shk ne toke	m ³	173.60		
2	2.262/4	Shtrese betoni C 16/20 t=15cm L=510 ML B=3.5 ML T=15CM	m ³	267.75		
3	Analize	F.V. zgare hekuri (15x15cm) 6mm perfshi xhuntimet	m ²	1785.00		
		SHUMA II				
III		NDERTIM URA LELA DHE ARRIKU NJESIA ADMINISTRATIVE GURRE				
A		NDERTIM URA TE LAGJIA LELA GURRE				
1	3.108/a	Germim eskavator me zinxhir prani uji	m ³	118.0		
2	3.125/b	Germim shkembimi eskavat me zinxhire 1m ³ shkarkim toke	m ³	11.0		
3	3.245	Struktura monolite betoni C25/30 per kembet e ures	m ³	112.0		
		SHUMA A				
B		NDERTIM URA TE LAGJIA ARRIKU GURRE				
1	3.108/a	Germim eskavator me zinxhir prani uji	m ³	83.1		
2	3.125/b	Germim shkembimi eskavat me zinxhire 1m ³ shkarkim toke	m ³	8.0		
3	3.245	Struktura monolite betoni C25/30 per kembet e ures	m ³	90.0		
		SHUMA B				
		SHUMA III = SHUMA A+SHUMA B				
		SHUMA I+II+III				
		TVSH		20%		
		SHUMA TOTALE				