

REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

Nr. Prot.

Kamez me / /2017

P R E V E N T I V - Z B A T I M I

Objekti : Ndertim I Rruges Mustafa LITA , Babrru Koder e Kuqe - Bulcesh , Bashkia

Nr.	Nr.An.	Emërtimi i procesit të punës	Njësia	Sasia	Çmimi	Vlera - leke
I. Punime ne rrugen (Mustafa Mustafa Lita) , degezime B= 5 m Basf= 4 + Bankine 2x0.5 , L= 2730 m						
1	3.an-49	Thyerje Betoni t=10 cm + transport	m ³	18		
2	3.114/b	Germim dheu ne trupin e rruges	m ³	1,002		
3	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	524		
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	13,990		
5	3/212/6	Shtreses stabilizant t=10 cm	m ²	11,050		
6	3.229/1	Shtrese binderi 5 cm + Sperkatje me emuls	m ²	11,050		
7	3.233/1	Shtrese asfalto betoni 4 cm + Sperkatje me	m ²	11,050		
8	2.109/2	Struktura monolite betoni, C 6/10, per themel + xokol	m ³	300.171		
9	3.158/5a	Transport dherash me auto 5 km	m ³	1,128		
10	anal	Heqje dhe Montim Shtylla Elektrike (Kabll	cope	14		
Shuma II						
III. Ndertim Trotuari te Rruges 2 x 0.5						
1	3.87/a	Germim dheu me eskavator gome 0.25 m3 ne kanale mer gjersi deri 2 m toke e zakonshme , kat III me shk. Ne toke	m ³	126		

2	3.353	Mbushje me cakell per bankine (t=20 cm)	m ³	112		
3	2.556	F.V. tub Betoni O 600 mm	ml	20		
4	An	Ngritje Pusete KUZ (1x1x1.5)	cope	4		
		Shuma III				0
		Shuma Totale		I+II+III+IV+V		0
		TVSH 20 %	20%			0
		Shuma Totale				0

Shenim : Hartuar ne baze te VKM nr. 629 dt 15.07.2015

Preventivues:

Ing. Hajredin MURGU

Drejtori D.P.K.ZH.T

Ark. Arber TOLA

