

PREVENTIV

Objekti: Rikon. I rruges Kalaja Petralbe Pjesa II, Rik. Rruga Gurre e Vogel dhe ndertim ure Lela-Arriku

Nr	Nr Analizes	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
I						
RIKONSTRUKSION I RRUGES PETRALBE PJESA II						
1	3.87/B	Germim toke e forte me eskavator me zinxhire +hedhje ne toke	m ³	698.8		
2	3.124/1A	Germ. shkemb mesatar, me cekic me eskavator me zinxhire	m ³	235.0		
3	3.124/2A	Germ. shkemb forte, me cekic me eskavator me zinxhire	m ³	82.0		
SHUMA I						
RIKONSTRUKSION RRUGA G.VOGEL , RRUGA CANI, CELAMI						
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , nivelim traseje gjeresi > 2 m, toke zak, kategoria IV, me shk ne toke	m ³	1050.60		
2	2.262/4	Shtrese betoni C 16/20 t=15cm L=490 ML B=3.5 ML T=15CM	m ³	257.25		
3	Analize	F.V. zgare hekuri (15x15cm) 6mm perfshi xhuntimet	m ²	1715.00		
SHUMA II						
III						
NDERTIM URA LELA DHE ARRIKU NJESIA ADMINISTRATIVE GURRE						
A						
NDERTIM URA TE LAGJIA LELA GURRE						
1	3.108/a	Germim eskavator me zinxhir prani uji	m ³	118.0		
2	3.125/b	Germim shkemb eskavat me zinxhire 1m ³ shkarkim toke	m ³	11.0		
3	3.245	Struktura monolite betoni C25/30 per kembet e ures	m ³	112.0		
SHUMA A						
B						
NDERTIM URA TE LAGJIA ARRIKU GURRE						
1	3.108/a	Germim eskavator me zinxhir prani uji	m ³	83.1		
2	3.125/b	Germim shkemb eskavat me zinxhire 1m ³ shkarkim toke	m ³	8.0		
3	3.245	Struktura monolite betoni C25/30 per kembet e ures	m ³	90.0		
SHUMA B						
SHUMA III = SHUMA A+SHUMA B						
SHUMA I+II+III						
TVSH						
20%						
SHUMA TOTALE						