

PREVENTIV

OBJEKTI : RIKUALIFIKIMI URBAN I FASADAVE QENDRES BELSH

INVESTITORI : BASHKIA BELSH

Nr	Nr.Anal,	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
		Rikonstruksioni godinave				
1	2.426/5	Prishje mure betoni	m3	110		
2	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	130		
3	2.70/2	Mur me tulle te lehtesuara dopio deri 3m me llaç perzier M25	m3	110		
4	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m2	420		
5	2.206	Kasete shkarkimi me llamarine xingat	cope	50		
6	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	80		
7	2.334	Suva e zakonshme fasade mur tulle lartesi mbi 8 m	m2	2100		
8	2.331	Suva e zakonshme fasade mur tulle h ~ 8 m	m2	2197		
9	An	Prishje suva e zakonshme fasade mur tulle h ~ 8 m	m2	3810		
10	2.308/a	Suvatim me grafiato h > 4 m	m2	4400		
11	An	Veshje fasade me mermer travetin	m2	220		
12	2.324/2	Plintuse mermeri h = 10cm	ml	150		
13	2.395/a	Dyer d/alumini dopio xham.	m2	25		
14	2.375/a	Dritare d/alumini dyfish xham.	m2	80		
15	2.404/1	Boje hidroplastike importi cilesi e l-re	m2	4438		
16	2.431	Skele metalike me tubo fasade ~8m	m2	1800		
17	2.431	Skele metalike me tubo fasade > 12m	m2	520		
					Shuma A	
					Shuma B	
		Shuma e plote				
		Fondi Rezerve 3%				
		SHUMA				
		20 % TVSH				
		SHUMA TOTALE				