



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

Nr ____ Prot.

Kamez me ____/____/2017

PREVENTIV

NDERTIM RRUGA KONISPOLI , RRUGA ZEF LLESH DOÇI + RRUGA TIRANA + RRUGA BERATI +

OBJEKTI : Ndertim RRUGE "LURE" LAKNAS

(L = 1480 ml, trotuar b= 2x1.5m)

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME TROTUARE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.208	Shtrese çakelli T=10cm	m ²	4200		
2	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m ²	3360		
3	3.618	F.V. Bordura betoni e parapregatitur C 20/25 15x30 cm	ml	2800		
4	210/2	Fv bordura anesore e pergatitur ne vend 40 x20 ansore	m ³	201.80		
5	2/262/4	Beton per shtrese betoni poshte bordures C16/20	m ³	84		
6	2/262/4	Shtrese betoni per trotuari 10cm	m ²	327.6		
7	3.139	Germime dheu me ekskavator me goma	m ³	210		
8	3.158/5a	Transport dheu me auto 5km	m ³	210		
		SHUMA I				
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	828.8		

2	3.158/5a	Transport dheu me auto 5 km	m ³	828.8		
3	3/353	Mbushje me çakell shkembor	m ³	477.8		
4	3.an/1t	F.V. Tuba i brinjezuar Ø 315 mm	ml	2741		
5	2.262/4	Shtrese betoni c 16/20 Kunete betoni	m ³	145		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	99		
SHUMA II						
III	PUNIME PER NDRICIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	
1	3.654	F.V. Tub PVC Ø100 per telefonine	ml	1400		
2	3.654	F.V. Tub PVC Ø100 per elektrikun, ndriçimin	ml	1400		
3	3.139	Germime dheu me ekskavator me goma	m ³	700		
4	3.158/5a	Transport dheu me auto 5 km	m ³	700		
5	2.261	Mbushje me rere	m ³	210		
6	3/353	Mbushje me cakull shkembor (kanal)	m ³	470		
SHUMA III						
IV	PUNIME PER GJELBERIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	
<u>1</u>	An	F.V. Bordura betoni 0.6 x 0.2 x 0.8 ml	ml	490		
<u>2</u>	An	Punime dheu dhe mbushje me humus (2300	m ³	230		
<u>3</u>	3.643	Mbjellje bari ne lulishte	m ²	2300		
				Shuma IV		
SHUMA I+II+III+IV						
OBJEKTI : Ndertim Rruga "Zef Llesh Doçi+ Konispoli " Laknas						
(L = 823 ml, B =6.5m, b = 5.3 m)						
Nr	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
B	PUNIME NE RRUGE					
1	3.139	Germim dheu me eksavator	m ³	452		
2	3.158.5a	Transport dheu me auto 5 km	m ³	452		
3	3.353	Mbushje me cakull	m ³	1131		
4	3.208	Shtrese cakulli t=10 cm	m ²	4526		
5	3.212.b	Shtrese stabilizanti t= 10 cm	m ²	3868		
6	3.229.2	Shtrese binderi 1x5cm	m ²	3868		
7	3.231.1	Shtrese asfaltobetoni 1x4 cm	m ³	3868		

8	2.426.2	Prishje muresh me blloqe	m ³	68	
9	An.	Spostim Shtyllle Betoni	cope	18	
10	3.617.1	F.V. bordure 15x30 cm	ml	1592	
11	3.139	Germim dheu me eksavator per K.u.b	m ³	374.8	
12	3.158.5a	Transport dheu me auto 5 km per K.u.b	m ³	374.8	
13	3.353	Mbushje me cakull shkembi	m ³	418	
14	2.An.1t	F.V. Tubo brinjzuar Ø 315 mm	ml	1580	
15	2.262.4	Shtrese betoni per kunete	m ³	115	
16	2/262/4	Beton per fiksime bordure	m ³	36	
17	3.An.23	Pusetash shiu me kapak gize 40x60	cope	48	
18	An.	Ngjitje pusetash me kapak gize	cope	16	
		SHUMA I			

Ndertim " Rruga Tirana + Rruga Berati " + Fusha Sportit , Laknas , Bashkia Kamez

Rruga L= 828m, B=4.5 m Basfalt= 4 m,

NR	NR. ANALIZ.	EMERTIMI I PUNIMIT	Njesi	Sasia	Çmimi	Vlefte
C		I. Punime ne rruge dhe degezime B=4m , l=608 m				
1	3.139	Germim dheu me eskavator	m ³	486		
2	3.158/5a	Transport dherash me auto 5 km	m ³	486		
3	3.353	Mbushje Çakull Shkembi	m ³	608		
4	3.158/5a	Transport çakull me auto 5 km	m ³	608		
5	3.208	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	2,432		
6	3/212/6	Shtrese stabilizanti 10 cm	m ²	2,432		
7	3.229/1	Shtrese binderi 5 cm + Sperkatje me emulsion	m ²	2,432		
8	3.233/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	2,432		
9	An	Spostim Shtyllash Elektrike	cop	10		
10	2/426/2	Prishje Avllie	m ³	56		
11	2.110/2	Mure betoni + Bordura anesor te preg. ne vend	m ³	10		
		Shuma I				

PUNIME K.U.N				
1	3.139	Germim dheu me eskavator	m ³	33
2	3.158/5a	Transport dherash me auto 5 km	m ³	33
3	3.353	Mbushje me Çakull	m ³	36
4	3.158/5a	Transport çakull me auto 5 km	m ³	36
5	2.556	F V tuba betoni 600 mm	ml	7
Shuma IV				
Shuma Totale e Rrugës (I+II)				0
Fusha e Sportit Laknas				
1	2,1	Germim dheu me krah + transport	m ³	160
2	3/139	Germim dheu per themel	m ³	26
3	2.109/2	Mur Betoni + Xokol C 12/15	m ³	43
4	2.182	Konstruksion metalik te thjeshta + porte	ton	1.12
5	3.353	Mbushje cakull shkembi	m ³	158
6	3.212/a	Shtres Stabilizanti	m ²	1000
Shuma e Rrugës + Fusha				
SHUMA TOTAL A+B + C				
T.V.SH 20%				
TOTALI				

Preventivues:

Ing. Elmaz MURATI
Ing. Hajredin MURGU

Drejtori D.P.K.ZH.T

Ark. Arber TOLA

**MIRATOI
Xhelal MZIU**

K R Y E T A R