

## PREVENTIV

Objekti: SISTEMIM ASFALTIM RRUGA LAGJA GJEOLUGU BULQIZE

Nr.	NR.AN	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI	VLERA
<b>A</b>						
<b>SEGMENTI I</b>						
<b>1</b>						
<b>PUNIME GERMIM-MBUSHJE NE RRUGE</b>						
1	3.104/b	Germim dheu me ekskavator 0.5 m <sup>2</sup> , b > 2 m, toke zak, kategoria IV, me shk ne mjet	m <sup>3</sup>	37		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	37		
<b>SHUMA 1</b>						
<b>2</b>						
<b>PUNIME SHITESASH NE RRUGE</b>						
1	3.211	Shtrese çakelli mbeturine kave t=1x20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	508		
2	3.212/b	Shtrese stabilizant t=10cm	m <sup>2</sup>	508		
3	3.222/2	Shtrese binderi me granil gur kave, 6cm, me makineri	m <sup>2</sup>	452		
4	3.226/1	Shtrese asfaltbetoni me granil quri kave, 4cm, me makineri	m <sup>2</sup>	452		
5	3.244	Struktura monolite betoni C.20/25, kuneta	m <sup>3</sup>	7.0		
<b>SHUMA 2</b>						
<b>3</b>						
<b>PUNIME TROTUARI</b>						
1	3.104/b	Germim dheu me ekskavator 0.5 m <sup>2</sup> , b > 2 m, toke zak, kategoria IV, me shk ne mjet	m <sup>3</sup>	9		
2	3.244/1	Struktura te holla monolite betoni C.20/25 (bordura e pasme)	m <sup>3</sup>	2		
3	3.240	Struktura monolite betoni c12/15 (fiksime bordure)	m <sup>3</sup>	3		
4	3.618	Bordura betoni 20x35 cm	m	116		
5	3.205/1	Shtrese zhavori lumi t=15cm, perhapur e ngjeshur me makineri	m <sup>2</sup>	90		
6	2.261	Shtrese rere per nivelim pllake t=4 cm	m <sup>3</sup>	4		
7	3.620	Trotuar me plaka betoni 20x10x6cm	m <sup>2</sup>	90		
8	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	9		
<b>SHUMA 3</b>						

<b>4 PUNIME K.U.B</b>				
1	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke	m <sup>3</sup>	36
2	2.261	Shtrese rere	m <sup>2</sup>	3.1
3	An.164/1a	Mbushje me cakell	m <sup>3</sup>	10.2
4	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	102
5	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak qize	copë	5
6	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	36
<b>SHUMA 4</b>				
<b>5 PUNIME ELEKTRIKE</b>				
1	3.An/53	F V shtylla metalike per ndricim, H=7m, d=160mm	copë	4
2	AN 3	FV Ndricules LED 81.6 w	copë	4
3	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	copë	4
4	An	F V kuader komandimi komplet me santeri+fotoelement	copë	1
5	2 a-106	Automat magneto-termik 380V,40A, 4P,Id=0.03A	copë	4
6	AN 4	F.V. morseteri shtylle 3P-sig.16A+kapak	copë	4
7	3.An/et	FV elektroda tokezimi te xinguar 50x3mm, L=150cm	copë	4
8	4.150/7	F.V. perciellesa Cu 16mm <sup>2</sup>	ml	20
9	AN 3	F.V. Kabell FG7OR 0.6/ 1KV, 5x10mm <sup>2</sup>	ml	10
10	AN 5	F.V. Kabell FG7OR 0.6/ 1KV, 5x6mm <sup>2</sup>	ml	82
11	AN 6	F.V. Kabell FG7OR 0.6/ 1KV, 3x1.5mm <sup>2</sup>	m	38
12	AN 7	F.V. tub fleksibel me 2 shtresa D=75mm per elektrik	ml	92
13	3.654/1	Furnizim, vendosje tuba plastmasi ø 80 (linjat rezerve inxhinierike)	ml	164
14	2.575	Puse kontrolli 1x1x1.5m	cope	2
15	3.An/tp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	copë	4
16	3.240	Struktura monolite betoni C 12/15	m <sup>3</sup>	1
17	AN 8	Shirit Sinjalizues	ml	82
18	2.261	Rere	m <sup>2</sup>	2
19	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke	m <sup>3</sup>	5
20	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	5
<b>SHUMA 5</b>				
<b>6 PUNIME PER SINJALISTIKE</b>				
1	An130	Vijejim shirita gjatesor dhe anesor me gjeresi 15 cm. Termoplastike (sprajt)	ml	214
2	An151	Vizime me boje bikomponente (vizime kembesoresh, shigjeta drejtimi etj)	m <sup>2</sup>	7
3	An48	Tabele katrore normal me A=60	cope	1
4	An97	Tabela tetekendore normal me A-B, 90-30 (STOP)	cope	1
<b>SHUMA 6</b>				
<b>SHUMA A (1-6)</b>				

<b>B</b>					
<b>SEGMENTI II</b>					
<b>1 PUNIME GERMIM-MBUSHJE NE RRUGE</b>					
1	3.104/b	Germim dheu me ekskavator 0.5 m <sup>3</sup> , b > 2 m, toke zak, kategoria IV, me shk ne mjet	m <sup>3</sup>	430	
2	An-49	Prishje struktura prej betoni	m <sup>3</sup>	30	
3	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	430	
<b>SHUMA 1</b>					
<b>2 PUNIME SHITESASH NE RRUGE</b>					
1	3.211	Shtrese çakelli mbeturine kave t=1x20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	900	
2	3.212/c	Shtrese stabilizant t=15cm	m <sup>2</sup>	900	
3	3.222/2	Shtrese binderi me granil gur kave 6cm me makineri	m <sup>2</sup>	850	
4	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m <sup>2</sup>	850	
5	3.244	Struktura monolite betoni C 20/25, kuneta	m <sup>3</sup>	6.3	
<b>SHUMA 2</b>					
<b>3 PUNIME TROTUARI</b>					
1	3.104/b	Germim dheu me ekskavator 0.5 m <sup>3</sup> , b > 2 m, toke zak, kategoria IV, me shk ne mjet	m <sup>3</sup>	96	
2	3.244/1	Struktura te holla monolite betoni C 20/25 (bordura e pasme)	m <sup>3</sup>	17	
3	3.240	Struktura monolite betoni c12/15 (fiksime bordure)	m <sup>3</sup>	10	
4	3.618	Bordura betoni 20x35 cm	ml	320	
5	3.205/1	Shtrese zhavori lumi t=15cm, perhapur e ngjeshur me makineri	m <sup>2</sup>	230	
6	2.261	Shtrese rere per nivelim pllake t=4 cm	m <sup>2</sup>	9	
7	3.620	Trotuar me pllaka betoni 20x10x6cm	m <sup>2</sup>	230	
8	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	96	
<b>SHUMA 3</b>					
<b>4 PUNIME K.U.B</b>					
1	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke	m <sup>3</sup>	31	
2	2.261	Shtrese rere	m <sup>2</sup>	2.6	
3	An.164/1a	Mbushje me cakell	m <sup>3</sup>	7.7	
4	AN 1	F.V. tub PVC 250 mm l brinjezuar	ml	40	
5	3.An2t	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	64	
6	An - 23	Pusetë b/a shiu 40 x 60, h = 100 cm, me kapak qize	copë	4	
7	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	31	
<b>SHUMA 4</b>					

<b>5 PUNIME ELEKTRIKE</b>				
1	3.An/53	F V shtylla metalike per ndricim, H=7m, d=160mm	copë	8
2	3.An	FV ndricues Smart VP CL1 CR M-S 250W GG FAE 44004,me llampe 250W/230V	copë	8
3	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	copë	8
4	An	F V kuader komandimi komplet me santeri+fotoelement	copë	8
5	2 a-106	Automat magneto-termik 380V,40A, 4P,Id=0.03A	copë	1
6	AN 4	F.V. morseteri shtylle 3P=sig.16A+kapak	copë	8
7	3.An/et	FV elektroda tokezimi te xingvara 50x3mm, L=150cm	copë	8
8	4.150/7	F.V. percjellesa Cu 16mm <sup>2</sup>	ml	50
9	AN	F.V. Kabell FG7OR 0.6/ 1KV, 5x10mm <sup>2</sup>	ml	10
10	AN 5	F.V. Kabell FG7OR 0.6/ 1KV, 5x6mm <sup>2</sup>	ml	178
11	AN 6	F.V. Kabell FG7OR 0.6/ 1KV, 3x1.5mm <sup>2</sup>	m	76
12	AN 7	F.V. tub fleksibel me 2 shtresa D=75mm per elektrik	ml	178
13	3.654/1	Furnizim, vendosje tuba plastmasi ø 80 (linjat rezerve inxhinierike)	ml	340
14	An	F.V. Tuba metalik D=219mm	ml	5
15	2.575	Puse kontrolli 1x1x1.5m	cope	6
16	3.An/bp	FV puse te plastike 40x40x40, kapak te forte RIC 1084+1086	copë	8
17	3.240	Struktura monlite betoni C 12/15	m <sup>3</sup>	1
18	AN 8	Shirit Sinjalizues	ml	178
19	2.261	Rere	m <sup>3</sup>	3
20	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke	m <sup>3</sup>	10
21	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	10
<b>SHUMA 5</b>				
<b>6 PUNIME NE VEPRA ARTI</b>				
<b>KANAL DHE MUR BETON</b>				
1	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke	m <sup>3</sup>	34
2	3.244	Struktura monlite betoni C 20/25 per kanal in (detaji 2)	m <sup>3</sup>	7
3	3.244	Struktura monlite betoni C 20/25 per kanal + mur (detaji 1)	m <sup>3</sup>	66.5
4	3.633	Fuqature llac cemento M - 50, t=0.05 cdo 3ml	m <sup>2</sup>	20
5	An.164/1a	Mbushje me cakell e gur gurore,perhapur e ngjeshur me makineri ne shtresa cdo 20 cm (poshte kanaleve)	m <sup>3</sup>	7
6	2.182	Konstruksione metalike te thjeshta	ton	1.759
7	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	34
<b>Shuma 6</b>				

<b>7 PUNIME GJELBERIM, MBROJTJE SKARPATE</b>				
1	An169	F.V mbjellje peme dekorative Bli 16-18cm ne trotuar (cdo 6m)	copë	12
<b>SHUMA 7</b>				
<b>8 PUNIME PER SINJALISTIKE</b>				
1	An130	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Termoplastike (sprajt)	m	428
2	An151	Vizime me boje bikomponente (vizime kembesoresh, shigjeta drejtimi etj)	m <sup>2</sup>	15.3127
3	An48	Tabele katrore normal me A=60	cope	6
4	An97	Tabela tetekendore normal me A-B, 90-30 (STOP)	cope	2
5	An155	F V tabela rruqore te ndryshme D=90cm	cope	2
<b>SHUMA 8</b>				
<b>SHUMA B (1-8)</b>				
<b>SHUMA A + B</b>				
<b>Fondi Rezerve 5 %</b>			<b>5%</b>	
<b>SHUMA</b>				
<b>T.V.SH. 20 %</b>			<b>20%</b>	
<b>TOTALI</b>				

Sherime: Crimet e preventivit jane ne baze manualit te crimeve te vitit 2015.

Preventivues :  
ERALD-G SHP.K

Inq. Gezim Islami