

PREVENTIV

Objekti: Ndertim Rrjet Ujesjellesi Ne Zonen Koder Babrru, Ne Rruget: "Sali Vranishti, Prengaj, Xhorxhi Martini, 1 Maj, 28 Nentori"

INVESTITORI: "U.K.T." sha

SIPERMARRESI: "U.K.T" sh.a

Nr.	Nr/an.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Shuma
1	An	Prerje asfalti	ml	4		0
2	3.212/c	Shtrese stabilizanti t=15	m2	2		0
3	3.222/2	Shtrese binderi gr.g.kave 6cm	m2	2		0
4	3.226/1	Shtrese asfalt-beton gr.g.kave 4cm	m2	2		0
5	3.89/a	Ger. dheu me eks. goma 0.25m ³ ,me gjersi 2m,t.z.shk.mj	m3	5232		0
6	3.25/a	Germim me krah seksion te detyruar b<1,h=1.5m,t.z	m3	583		0
7	2.261	Shtrese rere	m3	880		0
8	2.19	Hedhje,mbushje,ngjeshje dheu	m3	2719		0
9	2.258	Nenshtrese zhavor	m3	2437		0
10	3.197/1	Prishje shtrese cakulli t=15cm me makineri	m2	2775		0
11	An.M3	Prishje shtrese asfalti me makineri	m2	200		0
12	2.429/4	Prishje shtrese betoni	m3	36		0
13	2.262/3	Shtrese betoni C12/15	m3	26		0
14	3.287	F.V.Hekur I zakonshem ø 6-10mm (zgare per shtrese)	ton	1.04		0
15	3.158/5a	Transport dheu me auto deri 5 km	m3	3096		0
16	2.491/h	F.V.Tub e rakorderi ujesjellesi PE100PN10 Dj-110mm	ml	565		0
17	2.491/g	F.V.Tub e rakorderi ujesjellesi PE100PN10 Dj-90mm	ml	525		0
18	An	F.V.Tub e rakorderi ujesjellesi PE100PN10 Dj-75mm	ml	170		0
19	2.491/f	F.V.Tub e rakorderi ujesjellesi PE100PN10 Dj-63mm	ml	1290		0
20	2.491/e	F.V.Tub e rakorderi ujesjellesi PE100PN10 Dj-50mm	ml	810		0
21	2.491/d	F.V.Tub e rakorderi ujesjellesi PE100PN10 Dj-40mm	ml	1750		0
22	2.491/c	F.V.Tub e rakorderi ujesjellesi PE100PN10 Dj-32mm	ml	742		0
23	2.491/b	F.V.Tub e rakorderi ujesjellesi PE100PN10 Dj-25mm	ml	2160		0
24	2.538	F.V.Pjese speciale çeliku Ø-200mm (tronket D-100,D-65,50 mm)	kg	65		0
25	4.113/4	F.V.Fllanxe celiku Dn-100mm	cope	2		0
26	4.113/2	F.V.Fllanxe celiku Dn-50mm	cope	3		0
27	An	F.V.Fllanxe celiku Dn-65mm	cope	1		0

28	4.123/4	F.V.Saracineske Pn16 Dn-100mm	cope	2		0
29	4.123/1	F.V.Saracineske Pn16 Dn-65mm	cope	1		0
30	4.123/1	F.V.Saracineske Pn16 Dn-50mm	cope	3		0
31	120	F.V.Manikote ef Dj-110mm	cope	4		0
32	119	F.V.Manikote ef Dj-90mm	cope	2		0
33	118	F.V.Manikote ef Dj-75mm	cope	1		0
34	114	F.V.Manikote ef Dj-63mm	cope	4		0
35	113	F.V.Manikote ef Dj-50mm	cope	4		0
36	112	F.V.Manikote ef Dj-40mm	cope	7		0
37	713	F.V.Manikote ef Dj-32mm	cope	9		0
38	716	F.V.Manikote ef Dj-25mm	cope	425		0
39	397	F.V.Reduksion D-110x90mm	cope	2		0
40	391	F.V.Reduksion D-90x63mm	cope	1		0
41	390	F.V.Reduksion D-90x50mm	cope	1		0
42	390	F.V.Reduksion D-90x40mm	cope	2		0
43	388	F.V.Reduksion D-75x50mm	cope	1		0
44	387	F.V.Reduksion D-75x40mm	cope	1		0
45	385	F.V.Reduksion D-63x50mm	cope	1		0
46	384	F.V.Reduksion D-63x40mm	cope	2		0
47	383	F.V.Reduksion D-63x32mm	cope	3		0
48	382	F.V.Reduksion D-50x40mm	cope	2		0
49	381	F.V.Reduksion D-50x32mm	cope	3		0
50	240	F.V.Reduksion D-40x25mm	cope	118		0
51	239	F.V.Reduksion D-32x25mm	cope	59		0
52	453	F.V.Tee ef Dj-90mm	cope	3		0
53	452	F.V.Tee ef Dj-75mm	cope	2		0
54	451	F.V.Tee ef Dj-63mm	cope	5		0
55	450	F.V.Tee ef Dj-50mm	cope	4		0
56	449	F.V.Tee ef Dj-40mm	cope	118		0
57	448	F.V.Tee ef Dj-32mm	cope	59		0
58	90	F.V.Adaptor PE Dj-110mm	cope	2		0
59	97	F.V.Adaptor PE Dj-75mm	cope	1		0
60	628	F.V.Adaptor PE Dj-63mm	cope	2		0
61	An	F.V.Adaptor PE Dj-50mm	cope	1		0
62	502	F.V.Fllanxhe per adaptor PE Dj-110mm	cope	2		0
63	500	F.V.Fllanxhe per adaptor PE Dj-75mm	cope	1		0
64	629	F.V.Fllanxhe per adaptor PE Dj-63mm	cope	2		0
65	An	F.V.Fllanxhe per adaptor PE Dj-50mm	cope	1		0
66	An	F.V.Stafe ef Dj-110x32mm	cope	3		0
67	An	F.V.Stafe ef Dj-110x25mm	cope	15		0
68	An	F.V.Stafe ef Dj-90x40mm	cope	1		0
69	An	F.V.Stafe ef Dj-90x32mm	cope	1		0
70	An	F.V.Stafe ef Dj-90x25mm	cope	22		0
71	An	F.V.Stafe ef Dj-75x25mm	cope	19		0
72	An	F.V.Stafe ef Dj-63x25mm	cope	40		0

73	An	F.V.Stafe ef Dj-50x25mm	cope	50		0
74	179	F.V.Rakorderi D-25x3/4"	cope	425		0
75	2.494/1	F.V.Saracineske D-3/4"	cope	425		0
76	2.491	F.V.Rakorderi xing.D-1" (niples,brryl)	kg	68		0
77	An	F.V.Kasete ujematesi e vendosur ne mure	cope	425		0
78	2.575	F.V.Pusete kontrolli 1x1x1.5m	cope	2		0
79	2.576	F.V.Pusete kontrolli 1.5x1.5x1.5m	cope	2		0
SHUMA						0
FOND REZERVE 5 %						0
SHUMA						0
T.V.SH. 20 %						0
SHUMA TOTALE						0

Projektuese
Ing.Erlinda PESHKU

Preventivuese
Ing.Shpresa GJURA

PERGJ.SEKTORI
Ing.Albana MILO

Dr.Drejt.Tek
Ing.Haxhire GERMAJSI

Dr.Dep.ING.
Ing.Ortjon DHAMI

