

**BASHKIA KAVAJE****Drejtoria e Planifikimit dhe Zhvillimit te Territorit & Drejtoria e Projektit, Politikave te Zhvillimit dhe Investimeve te Huaja****P R E V E N T I V****Objekti: Sistemim i ambienteve ne lagjen nr 2 tek ushtria (Parku Rekreativ faza II)****Investitor: Bashkia Kavaje**

Punime Ndricimi Rruga Kryesore (L=790m: gjeresi=5m)						
1	3.an/53	F.V shtylla metalike per ndricim. H=3.5m. d=160mm	cope	40		0
2	3.An/ksh	F.V krah shtylla metalike	cope	40		0
3	3.an/57b	F.V puseta elektrike kontrolli PVC 30x30x30cm	cope	40		0
4	2.552	F.V tuba betoni Ø200mm per fiksimin e shtyllave	ml	40		0
5	An	F.v kuader komandimi komplet me santeri + fotoelement	cope	1		0
6	3.An	F.V ndricues smart 250W	cope	40		0
7	4.131/3.5	F.V kabell FG7OR 4x10mm2	ml	890		0
8	An	tel bakri Ø6mm2	ml	40		0
9	3.An/et	F.v elektroda tokezimi te zinkuara 50x3mm, L=150cm	cope	40		0
10	An/man3	F.V Morseteri shtylle 3P+sig.8a+ kapak	cope	40		0
11	An	kasete metalike 50x50	cope	1		0
12	An	automat 4 polar 80-100A	cope	1		0
13	4.131/3.5	F.V Kabell FG7OR 4x16mm2	ml	50		0
14	An	Fotoelement	cope	1		0
15	An	Leshues manjetik me bobine 220V	cope	1		0
16	An	Automat tek 40A	cope	6		0
Shuma II						0

Punime ne palestren sportive (S=285m2)						
1	3.159/e	Germim dheu kat II-te me skreper	m3	28		0
2	2-37/5a	Transport materiale ndertimi+ dheu deri 5km	m3	28		0
3	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	285		0
4	3.212/b	Shtrese stabilizant t=10cm	m2	285		0
5	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	1.13		0
6	2.262/4	Shtrese betoni C 16/20 (t=10cm)	m3	28		0
7	3.616/a	Bordura trotuari 15x25cm te parapergatitura	ml	80		0
Shuma III						0

Punime Basene Ujore 355 m2						
1	3.159/e	Germim dheu kat II-te me skreper	m3	350		0
2	2-37/5a	Transport materiale ndertimi+ dheu deri 5km	m3	350		0
3	2.288	Shtrese me pllaka granili me boje pa borduren e betonit	m2	400		0
4	3.21	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	355		0
5	2.262/3	Shtrese betoni C 12/15	m3	36		0
6	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	6		0
7	3.245	Strukture monolite betoni C25-30 (dysHEME, mur rrethues, stola)	m3	117		0
8	2.267/1	Shtrese me pllaka porcelanat importi	m2	514		0
9	An	Shtrese pllakash guri me gdhendje e borcarduar mozaik 8cm (sheshi)	m2	52		0
10	3.616/a	F.V Bordura betoni trotuari 15x25cm te parapergatitura (sheshi)	ml	30		0
11	3.616/a	F.V Bordura trotuari 15x25cm te parapergatitura (peme)	ml	32		0
12	2.195	Hidroizolim dysHEMEJE me 2 guaine e ngjitur 100% 4mm	m2	420		0
13	2.154	Solete(dhoma teknike) b/a paranderur C25/30(dhoma teknike) t=25cm	m2	120		0
14	3.245	Strukture monolite betoni dysHEME +mure+ plinta(dhoma teknike)	m3	82		0
15	2.166	F V hekur periodik Ø 6 - 10 mm (dhoma teknike mure +dysHEMEJA)	ton	4.60		0
16	2.167	F.V hekur periodik Ø >12 mm (dhoma teknike trare, plinta)	ton	1.28		0
17	2.262/4a	Beton M-150 per themel(shtrese 10cm)	m3	47		0
18	2.197	H/izolim me dy shtresa k/katramat	m2	784		0
Shuma IV						0

Punime ne kendin e lojrave per femije (S=650m2)						
1	3.159/e	Germim dheu kat II-te me skreper	m3	65		0
2	2-37/5a	Transport materiale ndertimi+ dheu deri 5km	m3	65		0
3	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	650		0
4	3.212/b	Shtrese stabilizant t=10cm	m2	650		0
5	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	2.57		0
6	2.262/4	Shtrese betoni C 16/20 (t=10cm)	m3	65		0
7	3.616/a	Bordura trotuari 15x25cm te parapergatitura	ml	100		0
					Shuma V	0

Punime ne terrene sportive (Fusha Basketbolli Tenis) 765m2

1	3.159/e	Germim dheu kat II-te me skreper	m3	77		0
2	2-37/5a	Transport materiale ndertimi+ dheu deri 5km	m3	77		0
3	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	765		0
4	3.212/b	Shtrese stabilizant t=10cm	m2	765		0
5	3.226/3	Shtrese asfaltobetoni me ngjyre me granil guri kave, 6cm, me makineri	m2	765		0
6	3.837/a	Rrethim me rrjete teli	m2	480		0
					Shuma VI	0

Punime Ndricimi Terrene Sportive (S=765m2)

1	3.an/53	F.V shtylla metalike per ndricim, H=7m, d=160mm	cope	6		0
2	3.An/ksh	FV krah shtylla metalike	cope	8		0
3	3.an/57b	F.V puseta elektrike kontrolli PVC 30x30x30cm	cope	6		0
4	2,552	F.V tuba betoni Ø200mm per fiksimin e shtyllave	ml	6		0
5	An	F.v kuader komandimi komplet me santeri + fotoelement	cope	1		0
6	3.An	F.V ndricues smart 250W	cope	8		0
7	4.131/3.5	F.V kabell FG7OR 4x10mm2	ml	130		0
8	An	tel bakri Ø6mm2	ml	6		0
9	3.An/et	F.v elektroda tokezimi te zinkuara 50x3mm, L=150cm	cope	6		0
10	An/man3	F.V Morseteri shtyllle 3P+sig.8a+ kapak	cope	6		0
					Shuma II	0

Punime Furnizimi me Energji nga Kabina 6/2

1	4.131/3.5	F.V kabell FG7OR 4x16mm2	ml	300		0
2	An	F.V Tub fleksibel D=63mm	ml	300		0
3	An	kasete metalike 50x50	cope	1		0
4	An	automat 4 polar 80-100A	cope	1		0
5	4.131/3.5	F.V Kabell FG7OR 4x16mm2	ml	50		0
6	An	Fotoelement	cope	1		0
7	An	Leshues manjetik me bobine 220V	cope	1		0
8	An	Automat tek 40A	cope	6		0
					SHUMA VII	0

Punime te tjera FAZA 2

1	An164	F.V. Fidane Peme dekorative	cope	307		0
2	3.639	Shtrim pllaka guri 50x40cm t=6cm	m2	610		0
3	3,643	Mbjellje me bar	m2	26000		0
					SHUMA VIII	0
					Total	24,995,616
					TVSH 20%	4,999,123
					SHUMA TOTAL	29,994,739

*Shenim : Cmimet jane vendosur ne baze te manualit te punimeve te ndertimit te miratuara nga Keshilli i Ministrave Nr. 629 , Datë 15 .07. 2015
suplementare 8 % dhe fitim te planifikuar 10 %*

