

## Preventivi

**Objekti: Rehabilitim, sistemim asfaltim I rruges shkolla e mesme qender Selenice**

Nr.	Analiza	Pershkrimi i Punimeve	Njesia	Sasia
<b>A</b>				
<b>PUNIME PER EVADIMIN E MBETURINAVE</b>				
<b>A-1. Punime dhe dhe transport mbeturinash</b>				
1	An-49	Prishje struktura prej betoni	m <sup>3</sup>	240
2	3.158/2a	Transport dheu me auto deri 2.0 km	m <sup>3</sup>	2,091
<b>Shuma A-1</b>				
				<b>Shuma A</b>
<b>B</b>				
<b>PUNIME PER NDERTIMIN E RRUGES</b>				
<b>B-1 Rruge dhe Sheshe</b>				
1	3.89/a	Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m <sup>3</sup>	1,850.0
2	3.An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m <sup>3</sup>	1,890.0
3	3.212/c	Shtrese stabilizant t=15cm	m <sup>2</sup>	4,750.0
4	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m <sup>2</sup>	4,250.0
5	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m <sup>2</sup>	4,250.0
<b>Shuma B-1</b>				
<b>C</b>				
<b>Trotuaret</b>				
1	3.89/a	Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m <sup>3</sup>	250.00
2	An.164/1b (M-3)	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m <sup>3</sup>	780.00
3	3.62	Trotuar, me 6 cm beton, me pllaka	m <sup>3</sup>	3,250.00
4	3.244/1	Struktura te holla monolite betoni C 20/25	m <sup>3</sup>	230.00
5	3.287	F V hekur betoni i zakonshem 6-10 mm	ton	15.00
6	3.618	F V bordura betoni 20x35 cm	ml	1,100.00
7	3.240	Shtrese betoni C12/15	m <sup>3</sup>	43.00
<b>D</b>				
<b>Punime dekorative</b>				
1	An.6	Stol tip 1 (170cm x 50cm)	cope	21.00
2	An167	F.V. peme me d > 10 cm	cope	140.00
3	An151	Boje bikomponente	m <sup>2</sup>	240.00
4	An99	Tabele sinjalizimi	cope	30.00
<b>E</b>				
<b>Punime Elektrike</b>				
1	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	26.00
2	An	FV ndricues LED , 76W, 220 - 240 V	cope	26.00
3	An	FV puseste plastike 40x40x40, kapak betoni	cope	26.00
4	3.An/et	FV elektroda tokezimi te xinguar 50x3mm, L=150cm	cope	26.00
5	An- M3	F V kuader komandimi komplet me santeri+fotoelement	cope	1.00
6	An.3	F.V. Tuba metalik D=110mm	ml	24.00
7	An.4	F.V. Kabell XYMM 0.6/ 1KV. 3x2.5mm2	ml	180.00
8	An.5	F.V. Kabell FG7OR 0.6/ 1KV. 4x 6mm2	ml	550.00
9	3.654/1	Furnizim, vendosje tuba plastmasi ø 80	ml	550.00
10	3.379	F.V. Rere nen dhe mbi tubacione PE + kompaktesim	m <sup>3</sup>	23.00
11	An	F.V Percjelles per tokezim 16 mm2	ml	61.00

Per: C.E.C GROUP shpk  
Vangjush MBRICE  
Anduen MBRICE

		SHUMA 1		
		T.V.SH. 20%		
		VLERA NE TOTAL		