

PREVENTIVI I PUNIMEVE

Emertimi i objektit : Asfaltim i rruges tek ofiçina, Fshati Rranxa

Porositesi : Bashkia Vau Dejes

Projektuesi: "TAULANT" SHPK

Nr.	Nr. Analize	Pershkrimi	Njesia	Sasia	Çmimi	Vlera
		I. PUNIME NE RRUGE				
1	3.106/b	Germim dheu me ekskavator zingjir 0.5 m ³ , ne kanale gjeresi > 2 m, prani uji ~ 2m, kategoria IV, me shk ne mjet	m3	330		
2	3,207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	2000		
3	3.212/c	Shtrese stabilizant t=15cm	m3	1900		
4	3.229/1	Shtrese binderi me zall lavatrice,5cm,me makineri	m2	1850		
5	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3cm, me makineri	m2	1850		
6	3.212/b	Shtrese stabilizant t=10cm per bankina	m2	518		
			Shuma 1			
					T.V.SH 20%	
					SHUMA TOTALE	

**Preventivoi
"TAULANT" SHPK**Procurement
Albania