

**MIRATOI
KRYETARI BASHKISE
Fatos Tushe**

P R E V E N T I V
OBJEKTI :SISTEMIM ASFALTIM I RRUGES ME FSHATIN LEKAJ "
L=1045ml b=4ml +(2x0.5ml)

Nr	N/ an.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
1.Punime germimi						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	85		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	320		
3	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	405		
					Shuma1	
2.Punime shtresash						
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	5500		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	5500		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	4400		
4	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m2	4400		
					Shuma 2	
3.Punime te KUB						
1	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni(Merimetim tombino ekzistuese)	ml	50		
2	3.364	Tombino me tuba betoni Ø 500, mbi shtrese betoni(Hyrjet ne objekt)	ml	60		
3	2.262/3	Shtrese betoni C12/15 (kanal i hapur)	m3	105		
4	2.258	Shtrese zhavorri t=8cm	m ³	95		
					Shuma 3	
5.Tabela rrugore e vijeze						
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	9		
2	An157	F V tabela rrugore treguese 60x20cm	cope	2		
3	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	2105		
					Shuma 5	
					Shuma 1-5	
					Tvsh 20%	
					Totali	

Punoi: Ing.Ariola Dylia

**Zyra e projekteve
Ark.Maksim Cuko**

**Drejtoria e Planifikimit
Ing.Mimoza Haxhiu**

