

PREVENTIV

OBJEKTI: "RIKONSTRUKSION I KANALEVE VADITESE NE BASHKINE LIBRAZHD, PER VITIN 2019"

Nr	Nr.An.	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlefte
	<b>1</b>	<b>Kanalit Ujites Lunik - Zdrajsh Verri Loti Dyte: Prusi - Zdrajsh Verri</b>				
1	3.48/a	Rrafshim skarpate ne germim,me kra	m2	655		-
2	3.25/b	Germim seksion detyruar toke zakonsh.Pastrim dhe vendosje tubi	m3	285		-
3	3.95/b	Germim esk 0.25 per ulje bankine dhe skarpate	m3	336		-
4	3.161/2	Rrafshim skarpate me eskav 0.25 ne germim	m2	110		-
5	3.2	Prerje bime te vogla (ferra e shkurre)	m2	1200		-
6	629-630	Suvatim mur guri me ll/c M- 50	m2	405		-
7	3.243/1	Struktura te holle betoni C 16/20 t = 6 cm	m3	48.1		-
8	3.241	Strukture betoni C 12 / 15 per portale	m3	8.14		-
9	3.236	Strukture monolite butobetoni me 25 % gure	m3	76.5		-
10	3.290	FV Hekur i parapergatitur $\Phi$ 4 mm , zgare 15 cm x 15 cm	ton	0.185		-
11	An	FV Tubo korrogato SN-4 ; 315 mm	ml	42		-
12	An	FV Tubo korrogato SN-4 ; 400 mm	ml	78		-
13	An	FV Tubo korrogato SN-4 ; 500 mm	ml	12		-
14	an	Grup gjenerator per prerje/saldim (cbllokimin e sifonit Galan)	op	8		-
15	4.113/8	FV Fllanxhe celiku teke 200 mm	cope	1		-
16	4.123/4	FV Saraqineske 100 mm 6 AT	cope	1		-
17	An	Trasport materiale auto 10 deri 17 km	t/km	4316		-
18	2.37/1b	Trasport materiale me kafshe deri 1 km	ton	266.5		-
		<b>Shuma</b>	<b>leke</b>			-
		<b>Kanali ujites ujembledhesit Vehcan</b>				
1	3.48a	Rrafshim skarpate ne germim,me kra	m2	900		-
2	3.47/1b	Mbushje, rrafshim e ngjeshje	m3	47.28		-
3	3.243/1	Strukture e holle monolite betoni t = 6 cm veshje	m3	76.6		-
4	3.25/b	Germim me kra seksion detyruar toke zak	m3	75		-
5	2.37/1b	Trasport materiale me kafshe deri 1 km	ton	160		-
6	An	Trasport materiale ndertimi auto 25 km	t/km	4000		-
		<b>Shuma</b>	<b>leke</b>			-
		<b>Rikonstruksion Kanali Malit, Hotolisht</b>				
1	3.1	Skarifikim bari me lopate	m2	1514		-
2	An20	Germim shkemb seksion lire me kra	m3	55		-
3	An.124/3a	Germim shkemb sek i lire, me mina te vogla,me ekskavator 1 m3 + transport	m3	30		-
4	An 30	Germim shkemb seksion detyruar me kra	m3	309		-
5	3.155	Pastrim kanali nga dhera e llumra	m3	433		-
6	3.243/1	Strukture betoni e holle C16/20	m3	304		-
7	An	FV Zgare hekuri 4 mm2 parapergatitur 15 x15 cm	m2	3750		-
8	An	Trasport auto materiale ndertimi 20 km	t/km	15500		-

9	2.37/1b	Trasport materiale me kafshe deri 1 km	ton	760		-
		<b>Shuma</b>	<b>leke</b>			-
		<b>SHUMA</b>				-
		<b>T.V.SH. 20%</b>				-
		<b>TOTALI</b>				-

