

**MIRATOI
KRYETARI I BASHKISE
FATOS TUSHE**

PREVENTIV

Objekti: Sistemim, asfaltim I rruges ne fshatin Shegas
(Gjatesia e rruges l=1531ml , me b= 4m asfalt dhe 2x0.5 bakinat me stabilizant)

Nr.anal.	Emertimi I punimeve	Njesia		Cmimi	Vlera
	Punime ne rruge l=1560ml				
3.89/a	Germim trup rruge + zgjerimi	m3	150		
3.158/3a	Trasport dheu deri 3km	m3	150		
3.211	Shtrese cakelli t=20cm per zgjerim rruge	m2	850		
3.208	Shtrese cakelli 10 cm	m2	850		
3.212/b	Shtrese stabilizanti 10cm	m2	6576		
3.208	Shtrese cakelli 10 cm	m2	6576		
3.231/1	Shtrese asfalto-betoni 3cm	m2	6576		
3.229/1	Shtrese binderi 5 cm	m2	6576		
3.212/b	Shtrese stabilizanti 10cm per bankinat	m2	1540		
3.208	Shtrese cakelli 10 cm per bankinat	m2	1540		
				Shuma A	
	Punime per kanale				
3.89/a	Germim dheu esk. me goma 0.25m3 me shk.e auto	m3	56.4		
3.158/3a	Trasport dheu deri 3km	m3	56.31		
3.364	Tombino betoni Ø500	ml	10		
				Shuma B	
				Shuma A+B	
				Tvsh 20%	
				Totali	

Punoi .Ing.B.Bekaj

**DREJTORIA PLANIFIKIMIT
MIMOZA HAXHIU**

