

P R E V E N T I V

OBJEKTI: "SISTEMIM ASFALTIM RRUGA NE FSHATIN "RRAPEZ" L=830 m

Nr	N/ an.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
SEGMENTI 1 L=260m						
1.Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	115		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	115		
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	155		
					Shuma1	
2.Punime shtresash						
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	1560		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	1560		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1300		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	1300		
	2.262/3	Shtrese betoni C12/15 t=10cm	m3	13		
9	3.617/1	F.V bordura betoni 15x30	ml	260		
10	2262/3	Shtrese betoni nen bordure 10cm	m3	7.8		
					Shuma 3	
SHUMA 1						
SEGMENTI 2 L=250m						
1.Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	170		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	170		
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	145		
					Shuma1	
2.Punime shtresash						
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	1500		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	1500		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1250		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	1250		
	2.262/3	Shtrese betoni C12/15 t=10cm	m3	25		
9	3.617/1	F.V bordura betoni 15x30	ml	500		
10	2262/3	Shtrese betoni nen bordure 10cm	m3	15		
					Shuma2	
Punime te KUB						
15	3.116/a	Germim kanali me gjeresi deri 2m,tok e zak .me shk.ne mjet	m3	150		
16	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	150		
17	3.An/1t	F.V tubo brinjezuar Ø315	ml	10		
18	3.An/2t	F.V tubo brinjezuar Ø400	ml	250		
19	2.261	Shtrese rere nen dhe mbi tub	m3	30		
20	An-22/1	Puseta shimbledhese b/a 40x40 me kapak gize	cope	5		
21	2.575	Puseta kontrolli 1x1 me kapak gize	cope	5		
					Shuma 4	
SHUMA 2						
SEGMENTI 3 L=110m						
1.Punime germimi						

1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	100		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	100		
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	37		
					Shuma1	
		2.Punime shtresash				
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	660		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	660		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	550		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	550		
					Shuma2	
SHUMA 3						
		SEGMENTI 4 L=210m				
		1.Punime germimi				
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	77		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	77		
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	18		
					Shuma1	
		2.Punime shtresash				
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	1160		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	1160		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	950		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	950		
					Shuma2	
SHUMA 4						
					Shuma 1-4	
					Shuma	
					Fond rez. 1.8%	
					Tvsh 20%	
					Totali	