

Preventivi pa cmime

Objekti: Riparimi i rruges hyrje Zhapokik

RIPARIM I RRUGËS HYRJE ZHAPOKIK						
Nr.	Analiza	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (lek)	SHUMA (lek)
A						
PUNIME PER EVADIMIN E MBETURINAVE						
A-1. Punime dhe dhe transport mbeturinash						
1	An-49	Prishje struktura prej betoni	m ³	3		
2	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	860		
Shuma A-1						
					Shuma A	
B						
PUNIME PER NDERTIMIN E RRUGES						
B-1 Rruge dhe Sheshe						
1	3.87b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke	m ³	860.0		
2	3.An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	590.0		
3	3.212/b	Shtrese stabilizant t=10cm	m ²	2,850.0		
4	3.221/1	Shtrese binderi 4cm	m ²	2,850.0		
5	3.224/1	Shtrese asfaltobetoni 3cm	m ²	2,850.0		
6	3.246	Struktura monolite betoni me çakell C 20/25	m ³	11.00		
7	3.287	F V hekur betoni i zakonshem 6-10 mm	ton	1.20		
8	3.616/a	F V bordura betoni 15x25 cm	ml	8.0		
Shuma B-1						
					Shuma B	
C						
Strukturat						
1	3.87b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke	m ³	125.00		
2	An.164/1b (M-3)	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	85.00		
3	3.245	Struktura monolite betoni C25/30 (muret mbajtes)	m ³	10.00		
4	3.244	Struktura monolite betoni C20/25 (muret prites)	m ³	8.00		
5	An - 55 (M-3)	F.V Tub drenazhi Ø=150mm	ml	25.00		
6	3.287	F V hekur betoni i zakonshem 6-10mm	ton	1.00		
7	3.288	F V hekur betoni i zakonshem >12mm	ton	2.00		
8	3.240	Shtrese betoni C12/15	m ³	3.00		
9	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	ml	18.00		
					Shuma C	
Total punime ne tre segmentet						
FONDI REZERVE 2%						
SHUMA 1						
T.V.SH. 20%						
VLERA NE TOTAL						

Per: C.E.C GROUP shpk

Vangjush MBRICE

Anduen MBRICE

