

PREVENTIV

Objekti: RIKONSTRUKSION KATI PARE TEKNIK I SHKOLLES 9-VJEÇARE VEHÇAN, HOTOLISHT
BASHKIA LIBRAZHD

NR	NR ANAL	EMERTIMI I PUNIMEVE	Njesia	Sasia	Çmimi	VLERA
	1	PUNIME PRISHJE				
1	An	Heqje dyer te brendshme +transport	m ²	13.00		-
2	An	Heqje dritare+transport	m ²	58.00		-
3	An	Prishje suvatimi ne mure+tavane	m ²	1,777.50		-
4	An	Prishje shtrese pllake+transport mbeturina	m ²	375.00		-
		Shuma 1				-
	2	PUNIME DYER DRITARE				
1	2.375/a	Dritare d/alumini dyfish xham	m ²	59.50		-
2	2.383/1	F V dyer te brendeshme druri importi cilesi e I-re.	m ²	22.11		-
3	2.273/5	Pragje dritare me mermer t=3 cm	m ²	12.25		-
4	2.395	Dyer d/alumini tek xham (dhe vetrata)	m ²	6.40		-
		Shuma 2				-
	3	PUNIME SUVATIMI DHE VESHJE				
1	2.3	Suva solete h4 m me drejtues, me krah (riparime)	m ²	387.50		-
2	2.31	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	800.00		-
3	2.308/a	Suvatim me grafiato h > 4 m	m ²	590.00		-
4	2.348	Suva xokoli me granil e çimento te zakonshme me çokitje	m ²	64.00		-
5	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m ²	390.00		-
6	2.324a	Plintuse pllake grez	ml	281.00		-
7	2.326	Veshje me pllake majolike	m ²	23.50		-
8	2.404	Boje hidroplastike	m ²	1,187.50		-
9	2.273	Shkalle mermeri te brendeshme+korimano	m ²	15.00		-
10	2.404/1	Boje hidroplastike importi cilesi e I-re	m ²	590.00		-
11	2.268	Shkalle montazhi granili me boje	m ³	6.30		-
12	An	Fasho (rip) druri ne mur	ml	60.00		-
13	2.289	Trotuar me lluster cimento, pa borduren e betonit	m ²	72.00		-
14	3.616	F V bordura betoni 12x25 cm	ml	96.00		-
15	2.328	Patinim muri allçi	m2	168.00		-
		Shuma 3				-
	4	PUNIME ÇATIE (TARACE)				
1	2.219	Ndertim catie vendi, 4 pjerresi 27% tj. marsejeze	m ²	470.00		-
2	2.209/b	Ulluk shkarkimi vertikal me baker Ø 120	ml	36.00		-
3	2.212/b	Ulluk shkarkimi horizontal me baker 33cm	ml	102.00		-
4	2.206/b	Kasete shkarkimi me llamarine bakri 1.0mm	cope	6.00		-
		Shuma 4				-
	5	PUNIME GERMIMI, RRETHIMI L=140 MI				
1	2.5	Germim e mbushje dheu me krah kategoria III per themele, h = 1.5m	m ³	55.00		-
2	2.15	Germim e mbushje dheu me krah per kanale kategoria III, h = 1.5 m	m ³	6.20		-
3	2.109/2	Themel e xokol betoni C - 12/15	m ³	109.00		-
4	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m	m ³	10.00		-
5	2.31	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	362.00		-

6	An	Zgare per rrethim me profila hekuri , h=0.80 m	m ²	112.00		-
7	2.390/1	Porte rrethimi	m ²	3.00		-
8	2.258	Nenshtrese zhavori	m ³	17.00		-
		Shuma 5				-
	6	PUNIME PER SISTEMIMIN E JASHEM				
1	3.89/b	Germim me makineri , toke zakonshme	m ³	140.00		-
2	3.45/1	Germim me krahe, toke e zakonshme + transport 5km	m ³	100.00		-
	2.109/2	Themel e xokol betoni C - 12/15	m ³	60.00		-
3	2.288	Shtrese me pllaka betoni, per rruge dhe sheshe , t=6cm	m ²	120		-
4	2.261	Shtrese rere	m ³	12		-
5	2.258	Nenshtrese zhavori	m ³	12		-
		Shuma 6				-
	7	PUNIME ELEKTRIKE				
1	2.480/2	F.v tub plasmasi Φ18~21mm	ml	102		-
2	2.481/2	F.v percjelles PV-500 Φ2.5mm ²	ml	324		-
3	2.481/5	F.vpercjelles PV500 Φ10mm ²	ml	120		-
4	2.485	F.v celesa e priza 10A me nulifikim	cope	28		-
5	2.487	F.v kuti drivacioni plastike	cope	16		-
6	2.49	F.v kuti automat sekondar me 10 vende	cope	1		-
7	2.485/d	F.v priza shuko "GEVIS" universal	cope	16		-
8	2.490/1	F,v automat termo/el manj. Diferencial 2P 220v	cope	1		-
9	2.a - 73	Elektroda togezimi ,profil zing. E bakterizuar L = 1.5	cope	4		-
10	2.a-93	Percjelles togezimi Cu, S= 35mm ² I zhveshur	ml	32		-
		Shuma 7				-
		SHUMA(1 deri 7)				-
		5 %Fond rezerve				-
		Shuma				-
		20 % T.V.Sh				-
		SHUMA TOTALE				-

PUNOI
ZYRA E PROJEKTEVE DHE INVESTIMEVE